

Asbestos Register

(Hazardous Materials and Risk Assessment)

School:	Floraville Public School (4379)
Region:	Hunter/Central Coast AMU
State Electorate:	Swansea
Local Government Area:	Lake Macquarie

Last Reviewed By:	Greencap 24-JUN-2015
Last Revised By:	

Historical Fibro In Grounds Investigations/Events	No
<p>No previous investigations have been recorded against the school. However, asbestos containing materials maybe present in grounds from time to time and caution must be exercised prior to any grounds disturbance.</p>	

4379 - Floraville Public School
Site Plan (10380)



Preface to Asbestos Register

Limitations

Asbestos Registers established (first surveyed 2007/08) and maintained for the Department of Education (DoE) are limited in extent, in that:

1. All inspections and surveys of materials and finishes in DoE facilities are non-disturbance, with
2. Samples undertaken by hygienist to determine whether a sample is an Asbestos Containing Material (ACM),
3. The hygienist may apply a single sample to like materials within a space and adjoining spaces, but not normally between buildings,
4. Successive inspections have reduced any inconclusive records such as 'assumed asbestos' in difficult to access areas, by undertaking additional sampling with lifting devices.
5. In compliance with WHS Act 2011 and WHS Regulations 2017, additional inspections have been undertaken in ceiling spaces and sub-floor areas where access is possible.
 - o Where the ground floor is slab on ground, no inspection is made beneath the slab.
 - o Where fibro fragments (ACM taken for sampling) are located in ceiling spaces or sub floor voids air monitoring is normally undertaken at time of sampling, and clearance undertaken as soon as practicable.
6. No attempt has been made to identify any ACM that is hidden from view or encapsulated within
 - o Any wall cavity
 - o Sub floor area, particularly formwork for slabs in/on ground,
 - o Services (that may use ACM) such as: pipe lagging, asbestos cement pipes, flues.
7. All known ACM in Grounds (Fibro in Grounds) is made available in associated site specific asbestos management plans in DoE electronic files.
Notwithstanding information provided, ACM may be present in grounds from time to time and caution must be exercised prior to any grounds disturbance.

Use of the Asbestos Register

Prior to any disturbance works being undertaken in a building to which this asbestos register applies it will be necessary to confirm the extent of any ACM by a disturbance investigation:

- If the building was built prior to 2003
- If any ACM has been identified in the Asbestos Register for the building.

Update of Asbestos Registers

Asbestos Register Data is updated regularly by the DoE Hygienist Panel via the Online Asbestos Register Tool (Managed by Business Systems, School Infrastructure NSW). Internal users can view the latest edition of the Asbestos Register in the AMS.

Please note: The Department's external website may not contain the latest revision of the Asbestos Register.

Notes 1: Vermiculite

- During 2018/19, all vermiculite occurrences in DoE schools identified in 2007/08, were 'composite tested' in accordance with a safe work NSW agreed procedure. This required multiple testing of all vermiculite occurrences.
- During the period 2007/08 to 2018/19, some vermiculite has been over sheeted and a warning is indicated for schools where this has happened.

Note 2: DoE website link for information is here:

<https://www.schoolinfrastructure.nsw.gov.au/about-us/working-with-us/schools-asbestos-register.html>
<https://education.nsw.gov.au/about-us/strategies-and-reports/our-reports-and-reviews/schools-asbestos-register>

Note 3: Material Condition Assessment

The material condition assessment descriptors from Section 3 of the Asbestos Management Plan (AMP) is extracted below. Please read the AMP in its entirety for further information.

3.3.2.1 Material condition assessment

The OART records the material condition of identified ACM in the following format:

Rating	Description
Good condition (1)	For non-friable asbestos that is sealed and has no visible damage. This primarily related to asbestos cement (AC) sheet and vinyl tiles
Minimal damage (2)	For non-friable asbestos that has a very small amount of damage, eg hairline cracks.
Some damage / unsealed (3)	For non-friable asbestos with significant breakage or several small areas where material has been damaged, revealing loose asbestos fibres. Non-friable asbestos that is unsealed.
Poor condition (4)	For non-friable asbestos that has extensive damage. Visible asbestos debris
Friable asbestos (5)	Any occurrence of friable asbestos

Product	Material Description	Extent	Location	Material Condition	Risk Status	Remediation Priority	Result
B00A - Administration/Library - 1973 - Brick/Block							
Exterior							
Wall Linings Internal - Infill	Flat AC Sheeting	30	East, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Gable Verge Lining	Flat AC Sheeting	30m2	North, South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Eaves Linings	Flat AC Sheeting	60m2	East, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00A - R0011 - Distribution Board - .62 m2						Note: No inspection of live electrical installation	
Electrical - Mounting Board	Resinous Board	2	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00A - R0016 - Movement - 44.37 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	4m2	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00A - R0017 - Home Base/Practical Activities - 47.41 m2							
No Asbestos							
B00A - R0018 - Withdrawal Space - 2hb - 13.67 m2							
No Asbestos							
B00A - R0019 - Home Base Store - 6.91 m2							
No Asbestos							
B00A - R0020 - Home Base - 46.12 m2							
No Asbestos							
B00A - R0021 - Home Base Store - 6.71 m2							
No Asbestos							
B00A - R0022 - Practical Activities - 1hb - 10.69 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	2m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00A - R0023 - Practical Activities - 1hb - 10.99 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	2m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00A - R1005 - Distribution Board - .46 m2						Note: No inspection of live electrical installation	
Ceiling Structures/Linings	Flat AC Sheeting	1m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Electrical - Backing Board	Resinous Board	1	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Assumed Asbestos
B00A - R1006 - Movement - 44.4 m2							
Ceiling Structures/Linings	Flat AC Sheeting	45m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	10m2	East, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00A - R1007 - Home Base - 47.41 m2							
No Asbestos							
B00A - R1008 - Practical Activities - 1hb - 11.03 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	2m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00A - R1009 - Home Base Store - 6.91 m2							
No Asbestos							
B00A - R1010 - Withdrawal Space - 2hb - 13.67 m2							
No Asbestos							
B00A - R1011 - Home Base Store - 6.72 m2							

No Asbestos							
B00A - R1012 - Home Base - 46.12 m2							
No Asbestos							
B00A - R1013 - Practical Activities - 1hb - 10.73 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	2m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00B - General Learning/Staff Facilities - 1973 - Brick/Block							
Exterior							
Wall Linings Internal - Infill	Flat AC Sheeting	30	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Gable Verge Lining	Flat AC Sheeting	30m2	East, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Eaves Linings	Flat AC Sheeting	30m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00B - R0001 - Movement - 42.37 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	12m2	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00B - R0002 - Movement - 2.18 m2							
No Asbestos							
B00B - R0003 - Sports Store - 6.1 m2							
No Asbestos							
B00B - R0005 - General Storeroom - 6.73 m2							
Floor Coverings Res/Textile	Vinyl Tiles	7m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
B00B - R0006 - Movement - 14.02 m2							
Floor Coverings Res/Textile	Vinyl Tiles	15m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Structures/Linings	Vermiculite - Composite Sample - (10 - 40 m2) - (X3)						
B00B - R0007 - Home Base Store - 6.71 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles	7m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00B - R0008 - Special Programs Room - 56.85 m2							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	57m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
B00B - R0009 - Stairs - 10.67 m2							
No Asbestos							
B00B - R0010 - Home Base - 43.73 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	44m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00B - R0011 - Practical Activities - 1hb - 14.66 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (10 - 40 m2) - (X3)						
Floor Coverings Res/Textile	Vinyl Sheet	15m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)

B00B - R1001 - Movement - 47.69 m2							
Ceiling Structures/Linings	Flat AC Sheeting	48m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	12m2	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00B - R1002 - Home Base - 58.04 m2							
Furniture / Fixtures - Blackboard	Flat AC Sheeting						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	59m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00B - R1003 - Home Base Store - 6.71 m2							
Floor Coverings Res/Textile	Vinyl Tiles	7m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00B - R1004 - Movement - 13.88 m2							
Floor Coverings Res/Textile	Vinyl Tiles	14m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00B - R1005 - Home Base Store - 6.67 m2							
Floor Coverings Res/Textile	Vinyl Tiles	7m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00B - R1006 - Home Base - 56.55 m2							
Furniture / Fixtures - Blackboard	Flat AC Sheeting						
Furniture / Fixtures - Blackboard	Flat AC Sheeting						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	57m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00B - R1007 - Stairs - 15.01 m2							
Ceiling Structures/Linings	Flat AC Sheeting	16m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00B - R9001 - General Storeroom - 28.51 m2							
No Asbestos							
B00C - General Learning - 1968 - Brick/Block							
Exterior							
Wall Linings Internal - Infill	Flat AC Sheeting	30	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Eaves Linings	Flat AC Sheeting	30m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Gable Verge Lining	Flat AC Sheeting	30m2	East, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00C - R0001 - Movement - 48.49 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	12m2	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0002 - Home Base - 57.33 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	58m2	Throughout	Mnimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						

Wall Linings Internal - Infill	Flat AC Sheeting	4m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0003 - Home Base Store - 5.57 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles	6m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0004 - Movement - 7.1 m2							
Floor Coverings Res/Textile	Vinyl Tiles	8m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00C - R0005 - Movement - 7.06 m2							
Floor Coverings Res/Textile	Vinyl Tiles						
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
B00C - R0006 - Home Base Store - 6.26 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles	7m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0007 - Home Base - 57.17 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	58m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
Wall Linings Internal - Infill	Flat AC Sheeting	58m2	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0008 - Sports Store - 11.45 m2							
No Asbestos							
B00C - R0009 - Sports Store - 3.2 m2							
No Asbestos							
B00C - R0010 - Movement - 10.52 m2							
No Asbestos							
B00C - R0011 - Stairs - 3.2 m2							
No Asbestos							
B00C - R1001 - Movement - 40.97 m2							
Ceiling Structures/Linings	Flat AC Sheeting	41m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	10m2	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R1002 - Home Base - 57.01 m2							
Furniture / Fixtures - Blackboard	Flat AC Sheeting						
Wall Linings Internal - Infill	Flat AC Sheeting	2m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R1003 - Home Base Store - 5.48 m2							
Floor Coverings Res/Textile	Vinyl Sheet						
B00C - R1004 - Movement - 7.69 m2							
No Asbestos							
B00C - R1005 - Movement - 7.63 m2							

No Asbestos							
B00C - R1006 - Home Base Store - 6.27 m2							
Floor Coverings Res/Textile	Vinyl Sheet						
B00C - R1007 - Home Base - 57 m2							
Furniture / Fixtures - Blackboard	Flat AC Sheeting						
Wall Linings Internal - Infill	Flat AC Sheeting	2m2	North	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R1008 - Movement - 12.22 m2							
Ceiling Structures/Linings	Flat AC Sheeting	13m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Electrical - Backing Board	Resinous Board	1	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Assumed Asbestos
B00C - R1009 - Craft Store - 6.82 m2							
Ceiling Structures/Linings	Flat AC Sheeting	7m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R1010 - Movement - 10.53 m2							
No Asbestos							
B00C - R1011 - Stairs - 6.62 m2							
Ceiling Structures/Linings	Flat AC Sheeting	7m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00D - General Learning/Administration - 1968 - Brick/Veneer							
Exterior							
Eaves Linings	Flat AC Sheeting	60m2	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	30	West, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Gable Verge Lining	Flat AC Sheeting	20m2	North, South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00D - R0001 - Movement - 6.4 m2							
Ceiling Structures/Linings	Flat AC Sheeting	7m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00D - R0002 - Entry Vestibule - 15.74 m2							
No Asbestos							
B00D - R0003 - Movement - 96.48 m2							
Ceiling Structures/Linings	Flat AC Sheeting	97m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	30m2	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00D - R0004 - Movement - 8.55 m2							
No Asbestos							
B00D - R0005 - Distribution Board - 1.03 m2							
						Note: No inspection of live electrical installation	
Wall Linings Internal	Flat AC Sheeting	16m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Structures/Linings	Flat AC Sheeting						
B00D - R0006 - General Storeroom - 8.15 m2							
No Asbestos							
B00D - R0007 - Special Programs Room - 20.18 m2							
No Asbestos							
B00D - R0008 - Staff Toilet - 4.66 m2							

Floor Coverings Res/Textile	Vinyl Tiles							
B00D - R0009 - Deputy Principal - 14.24 m2								
No Asbestos								
B00D - R0010 - Staff Room Annexe - 14.61 m2								
Wall Linings Internal - Infill	Flat AC Sheeting	2m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00D - R0011 - Cleaning Distributed Store - 1.75 m2								
No Asbestos								
B00D - R0012 - Home Base - 56.88 m2								
Furniture / Fixtures - Blackboard	Flat AC Sheeting							
Wall Linings Internal - Infill	Flat AC Sheeting	4m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00D - R0013 - Home Base Store - 4.64 m2								
Ceiling Structures/Linings	Flat AC Sheeting	5m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)	
B00D - R0014 - Movement - 18.28 m2								
No Asbestos								
B00D - R0015 - Home Base Store - 4.62 m2								
Ceiling Structures/Linings	Flat AC Sheeting	5m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)	
B00D - R0016 - Home Base - 56.81 m2								
Furniture / Fixtures - Blackboard	Flat AC Sheeting							
Wall Linings Internal - Infill	Flat AC Sheeting	4m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00D - R0017 - Home Base - 86.11 m2								
Furniture / Fixtures - Blackboard	Flat AC Sheeting							
Wall Linings Internal - Infill	Flat AC Sheeting	4m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00D - R0018 - Toilets - Boys/Girls - 3.3 m2								
Floor Coverings Res/Textile	Vinyl Sheet							
Ceiling Structures/Linings	Flat AC Sheeting	4m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00D - R0019 - Movement - 15.31 m2								
No Asbestos								
B00D - R0020 - Home Base Store - 6.13 m2								
No Asbestos								
B00D - R0021 - Home Base - 56.96 m2								
Furniture / Fixtures - Blackboard	Flat AC Sheeting							
Wall Linings Internal - Infill	Flat AC Sheeting	4m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00D - R0022 - General Storeroom - 2.66 m2								
Ceiling Structures/Linings	Flat AC Sheeting							
B00D - R9001 - General Storeroom - 76.26 m2								
No Asbestos								
B00E - General Learning - 1968 - Brick/Veneer								
Exterior								
Wall Linings Internal - Infill	Flat AC Sheeting	12	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)	
Gable Verge Lining	Flat AC Sheeting	20m2	East, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	

Eaves Linings	Flat AC Sheeting	20m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
Interior							
B00E - R0001 - Movement - 34.48 m2							
Ceiling Structures/Linings	Flat AC Sheeting	35m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	10m2	South, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00E - R0002 - Home Base - 57.11 m2							
Furniture / Fixtures - Blackboard	Flat AC Sheeting						
Wall Linings Internal - Infill	Flat AC Sheeting	8m2	North and South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00E - R0003 - Home Base Store - 4.6 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	1m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00E - R0004 - Movement - 18.34 m2							
No Asbestos							
B00E - R0005 - Home Base Store - 4.6 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	1m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00E - R0006 - Home Base - 56.95 m2							
Furniture / Fixtures - Blackboard	Flat AC Sheeting						
Wall Linings Internal - Infill	Flat AC Sheeting	8m2	North and South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00F - Other-After School Care - 1950 - Timber							
Exterior							
Wall Cladding	Flat AC Sheeting						
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00F - R0001 - Movement - 13.88 m2							
Ceiling Structures/Linings	Flat AC Sheeting	14m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00F - R0002 - Out Of School Hours Care Centre - 53.88 m2							
Ceiling Structures/Linings	Flat AC Sheeting	54m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00G - Pupil Facilities - 1968 - Brick/Block							
Exterior							
Gable Verge Lining	Flat AC Sheeting	30m2	North, South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
Eaves Linings	Flat AC Sheeting	60m2	East, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	3	North, Lower portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Interior							

B00G - R0007 - Toilets - Girls - 34.15 m2							
Ceiling Structures/Linings	Flat AC Sheeting	35m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00G - R0008 - Toilets - Boys - 24.73 m2							
Ceiling Structures/Linings	Flat AC Sheeting	25m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Partition Walls (Cubicles)	Compressed AC Sheet	20m2	Variable positions	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00G - R0009 - Canteen - 28.34 m2							
No Asbestos							
B00G - R0010 - Movement - 31.48 m2							
Wall Linings Internal	Flat AC Sheeting						
B00G - R0011 - General Storeroom - 41.51 m2							
Wall Linings Internal	Flat AC Sheeting						
B00G - R0012 - Movement - 27.06 m2							
Wall Linings Internal	Flat AC Sheeting						
B00I - General Learning - 2006 - Fibre Cement Clad							
Exterior							
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00I - R0001 - Movement - 38.47 m2							
No Asbestos							
B00I - R0002 - Practical Activities - 1hb - 19.4 m2							
No Asbestos							
B00I - R0003 - Home Base Store - 6.02 m2							
No Asbestos							
B00I - R0004 - Home Base - 59.2 m2							
No Asbestos							
B00I - R0005 - Withdrawal Space - 2hb - 11.36 m2							
No Asbestos							
B00I - R0006 - Home Base - 59.19 m2							
No Asbestos							
B00I - R0007 - Home Base Store - 6.02 m2							
No Asbestos							
B00I - R0008 - Practical Activities - 1hb - 19.41 m2							
No Asbestos							
B00J - Administration/Library - 2010 - Brick/Veneer							
Exterior							
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00J - R0001 - Entry Vestibule - 29 m2							
No Asbestos							
B00J - R0002 - Movement - 43.5 m2							
No Asbestos							
B00J - R0003 - Interview - 15.3 m2							
No Asbestos							
B00J - R0004 - Principal - 17.02 m2							
No Asbestos							
B00J - R0005 - Deputy Principal - Type 2 - 13.28 m2							
No Asbestos							

B00J - R0006 - Deputy Principal - Type 1 - 13.28 m2	
No Asbestos	
B00J - R0007 - Interview/Office - Type 3 - 17.73 m2	
No Asbestos	
B00J - R0008 - Security Store - 14.28 m2	
No Asbestos	
B00J - R0009 - Staff Toilet - 4.93 m2	
No Asbestos	
B00J - R0010 - Staff Toilet - 4.84 m2	
No Asbestos	
B00J - R0011 - Staff Toilet - 5.1 m2	
No Asbestos	
B00J - R0012 - Cleaning Distributed Store - 4.12 m2	
No Asbestos	
B00J - R0013 - Access Shower/Toilet - 5.88 m2	
No Asbestos	
B00J - R0014 - Sick Bay - 8.27 m2	
No Asbestos	
B00J - R0015 - Clerical/Printing - 24.13 m2	
No Asbestos	
B00J - R0016 - Clerical Office - 34.1 m2	
No Asbestos	
B00J - R0017 - External Movement - 182.07 m2	
No Asbestos	
B00J - R0018 - Main Switch Board - 3.18 m2	
No Asbestos	
B00J - R0019 - Movement - 22.37 m2	
No Asbestos	
B00J - R0020 - Staff Room Annexe - 29.04 m2	
No Asbestos	
B00J - R0021 - Staff Room - 61.5 m2	
No Asbestos	
B00J - R0022 - Movement - 5.13 m2	
No Asbestos	
B00J - R0023 - Lift - 5.06 m2	
No Asbestos	
B00J - R0024 - Movement - 5.04 m2	
No Asbestos	
B00J - R0025 - External Movement - 2.43 m2	
No Asbestos	
B00J - R0026 - External Stairs - 2.69 m2	
No Asbestos	
B00J - R1001 - External Movement - 165.26 m2	
No Asbestos	
B00J - R1002 - Reading Area - 229.52 m2	
No Asbestos	
B00J - R1003 - Library Office/Workroom - 26.49 m2	
No Asbestos	
B00J - R1004 - Communications Room - 8.04 m2	
No Asbestos	
B00J - R1005 - K.L.A. Store - 19.26 m2	

No Asbestos		
B00J - R1006 - External Stairs - 3.43 m2		
No Asbestos		
B00J - R1007 - Distribution Board - .75 m2		Note: No inspection of live electrical installation
No Asbestos		
B00J - R1008 - Toilet - Lobby - 2.98 m2		
No Asbestos		
B00J - R1009 - Cleaning Distributed Store - 3.44 m2		
No Asbestos		
B00J - R1010 - Staff Toilet - 5.41 m2		
No Asbestos		
B00J - R1011 - Special Programs Room - Type 1 - 38.13 m2		
No Asbestos		
B00J - R1012 - Movement - 5.13 m2		
No Asbestos		
B00K - Other-Community Use - 2010 - Brick/Veneer		
Exterior		
Ceiling Voids	No Asbestos Found	
Underfloor Voids - Slab on Ground	No Asbestos Found	
Interior		
B00K - R0001 - External Movement - 12.92 m2		
No Asbestos		
B00K - R0002 - Access Shower/Toilet/Change - 14.36 m2		
No Asbestos		
B00K - R0003 - Distribution Board - 1.13 m2		Note: No inspection of live electrical installation
No Asbestos		
B00K - R0004 - P.E Store - 17.37 m2		
No Asbestos		
B00K - R0005 - Communal Space - 208.11 m2		
No Asbestos		
B00K - R0006 - Raised Platform - 62.55 m2		
No Asbestos		
B00K - R0007 - Communal/Performance Store - 11.23 m2		
No Asbestos		
B00K - R0008 - Movement - 7.99 m2		
No Asbestos		
B00K - R0009 - Sports Store - 17.4 m2		
No Asbestos		
B00K - R0010 - Ramp - 11.67 m2		
No Asbestos		
B00K - R0011 - Movement - 12.85 m2		
No Asbestos		
B00K - R0012 - Hall Chair Store - 11.91 m2		
No Asbestos		
B00K - R0013 - Cleaning Distributed Store - 5.49 m2		
No Asbestos		
B00K - R0014 - External Movement - 275.17 m2		
No Asbestos		
B00K - R0015 - Sound Cupboard - 2.31 m2		
No Asbestos		
B00K - R0016 - Toilet - Lobby - 3.28 m2		

No Asbestos		
B00K - R0017 - Toilets - Girls - 34.67 m2		
No Asbestos		
B00K - R0018 - Toilet - Lobby - 3.53 m2		
No Asbestos		
B00K - R0019 - Toilets - Boys - 20.79 m2		
No Asbestos		
B00L - General Learning/Other - 2011 - Brick/Veneer		
Exterior		
Ceiling Voids	No Asbestos Found	
Underfloor Voids - Slab on Ground	No Asbestos Found	
Interior		
B00L - R0001 - Practical Activities - 18.14 m2		
No Asbestos		
B00L - R0002 - Home Base - 59.87 m2		
No Asbestos		
B00L - R0003 - Home Base Store - 6.45 m2		
No Asbestos		
B00L - R0004 - Withdrawal Space - 2hb - 11.47 m2		
No Asbestos		
B00L - R0005 - Practical Activities - 17.47 m2		
No Asbestos		
B00L - R0006 - Home Base - 59.88 m2		
No Asbestos		
B00L - R0007 - Home Base Store - 6.38 m2		
No Asbestos		
B00L - R0008 - Toilets - Boys - 20.47 m2		
No Asbestos		
B00L - R0009 - Toilets - Girls - 20.19 m2		
No Asbestos		
B00L - R0010 - Access Shower/Toilet/Change - 6.67 m2		
No Asbestos		
B00L - R0011 - Cleaning Distributed Store - 4.89 m2		
No Asbestos		
B00L - R0012 - General Assistant/Bulk Store - 21.5 m2		
No Asbestos		
B00L - R0013 - Garden Store - 18 m2		
No Asbestos		
B00L - R0014 - Distribution Board - .65 m2		
No Asbestos		Note: No inspection of live electrical installation
B00L - R0015 - External Movement - 16.74 m2		
No Asbestos		
B00L - R0016 - External Movement - 153.46 m2		
No Asbestos		
B00L - R0017 - Movement - 11.44 m2		
No Asbestos		
B00L - R1001 - Practical Activities - 19.84 m2		
No Asbestos		
B00L - R1002 - Home Base - 58.79 m2		
No Asbestos		

B00L - R1003 - Home Base Store - 5.51 m2	
No Asbestos	
B00L - R1004 - Withdrawal Space - 1hb - 8.74 m2	
No Asbestos	
B00L - R1005 - Distribution Board - .66 m2	Note: No inspection of live electrical installation
No Asbestos	
B00L - R1006 - Home Base Store - 6.22 m2	
No Asbestos	
B00L - R1007 - Home Base - 60.17 m2	
No Asbestos	
B00L - R1008 - Practical Activities - 18.98 m2	
No Asbestos	
B00L - R1009 - Withdrawal Space - 2hb - 11.33 m2	
No Asbestos	
B00L - R1010 - Home Base - 60.22 m2	
No Asbestos	
B00L - R1011 - Home Base Store - 6.22 m2	
No Asbestos	
B00L - R1012 - Practical Activities - 19.68 m2	
No Asbestos	
B00L - R1013 - External Movement - 133.26 m2	
No Asbestos	
B00L - R1014 - External Stairs - 25.13 m2	
No Asbestos	

Demountables

There are no Demountable(s) Located at this school as per the AMS records as of 09-Sep-2020