

Asbestos Register

(Hazardous Materials and Risk Assessment)

School:	King Street Public School (4514)
Region:	Hunter/Central Coast AMU
State Electorate:	Upper Hunter
Local Government Area:	Singleton

Last Reviewed By:	Greencap 04-DEC-2014
Last Revised By:	

Historical Fibro In Grounds Investigations/Events	No
<p>No previous investigations have been recorded against the school. However, asbestos containing materials maybe present in grounds from time to time and caution must be exercised prior to any grounds disturbance.</p>	

4514 - King Street Public School
Site Plan (11097)



Preface to Asbestos Register

Limitations

Asbestos Registers established (first surveyed 2007/08) and maintained for the Department of Education (DoE) are limited in extent, in that:

1. All inspections and surveys of materials and finishes in DoE facilities are non-disturbance, with
2. Samples undertaken by hygienist to determine whether a sample is an Asbestos Containing Material (ACM),
3. The hygienist may apply a single sample to like materials within a space and adjoining spaces, but not normally between buildings,
4. Successive inspections have reduced any inconclusive records such as 'assumed asbestos' in difficult to access areas, by undertaking additional sampling with lifting devices.
5. In compliance with WHS Act 2011 and WHS Regulations 2017, additional inspections have been undertaken in ceiling spaces and sub-floor areas where access is possible.
 - o Where the ground floor is slab on ground, no inspection is made beneath the slab.
 - o Where fibro fragments (ACM taken for sampling) are located in ceiling spaces or sub floor voids air monitoring is normally undertaken at time of sampling, and clearance undertaken as soon as practicable.
6. No attempt has been made to identify any ACM that is hidden from view or encapsulated within
 - o Any wall cavity
 - o Sub floor area, particularly formwork for slabs in/on ground,
 - o Services (that may use ACM) such as: pipe lagging, asbestos cement pipes, flues.
7. All known ACM in Grounds (Fibro in Grounds) is made available in associated site specific asbestos management plans in DoE electronic files.
Notwithstanding information provided, ACM may be present in grounds from time to time and caution must be exercised prior to any grounds disturbance.

Use of the Asbestos Register

Prior to any disturbance works being undertaken in a building to which this asbestos register applies it will be necessary to confirm the extent of any ACM by a disturbance investigation:

- If the building was built prior to 2003
- If any ACM has been identified in the Asbestos Register for the building.

Update of Asbestos Registers

Asbestos Register Data is updated regularly by the DoE Hygienist Panel via the Online Asbestos Register Tool (Managed by Business Systems, School Infrastructure NSW). Internal users can view the latest edition of the Asbestos Register in the AMS.

Please note: The Department's external website may not contain the latest revision of the Asbestos Register.

Notes 1: Vermiculite

- During 2018/19, all vermiculite occurrences in DoE schools identified in 2007/08, were 'composite tested' in accordance with a safe work NSW agreed procedure. This required multiple testing of all vermiculite occurrences.
- During the period 2007/08 to 2018/19, some vermiculite has been over sheeted and a warning is indicated for schools where this has happened.

Note 2: DoE website link for information is here:

<https://www.schoolinfrastructure.nsw.gov.au/about-us/working-with-us/schools-asbestos-register.html>

<https://education.nsw.gov.au/about-us/strategies-and-reports/our-reports-and-reviews/schools-asbestos-register>

Note 3: Material Condition Assessment

The material condition assessment descriptors from Section 3 of the Asbestos Management Plan (AMP) is extracted below. Please read the AMP in its entirety for further information.

3.3.2.1 Material condition assessment

The OART records the material condition of identified ACM in the following format:

Rating	Description
Good condition (1)	For non-friable asbestos that is sealed and has no visible damage. This primarily related to asbestos cement (AC) sheet and vinyl tiles
Minimal damage (2)	For non-friable asbestos that has a very small amount of damage, eg hairline cracks.
Some damage / unsealed (3)	For non-friable asbestos with significant breakage or several small areas where material has been damaged, revealing loose asbestos fibres. Non-friable asbestos that is unsealed.
Poor condition (4)	For non-friable asbestos that has extensive damage. Visible asbestos debris
Friable asbestos (5)	Any occurrence of friable asbestos

Product	Material Description	Extent	Location	Material Condition	Risk Status	Remediation Priority	Result
B00A - Administration/Staff Facilities - 1964 - Brick/Veneer							
Exterior							
Ceiling Voids - Flat Roof	No Asbestos Found						
Underfloor Voids	Non Accessible Area						
Interior							
B00A - R0001 - Principal - 18.58 m2							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)						
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00A - R0002 - Security Store - 3.16 m2							
No Asbestos							
B00A - R0003 - Sick Bay - Shower/Toilet - 3.81 m2							
No Asbestos							
B00A - R0004 - General Storeroom - 17.84 m2							
No Asbestos							
B00A - R0008 - Clerical Office - 11.6 m2							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)						
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00A - R0009 - Duplicating Workroom - 31.79 m2							
No Asbestos							
B00A - R0010 - Sick Bay - 8.11 m2							
No Asbestos							
B00A - R0011 - Interview - 14.76 m2							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)						
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00A - R0012 - Movement - 19.62 m2							
No Asbestos							
B00A - R0013 - Staff Room Annexe - 15.84 m2							
No Asbestos							
B00A - R0014 - Staff Toilet - 3.6 m2							
No Asbestos							
B00A - R0015 - Staff Toilet - 3.57 m2							
No Asbestos							
B00A - R0016 - Security Store - 7.42 m2							
No Asbestos							
B00A - R0017 - Staff Room Annexe - 12.64 m2							
No Asbestos							
B00A - R0018 - Staff Room - 71.09 m2							
No Asbestos							
B00A - R0019 - Entry Vestibule - 33.43 m2							
No Asbestos							
B00A - R0020 - External Movement - 3 m2							
No Asbestos							
B00B - General Learning/Music - 1964 - Brick/Veneer							
Exterior							

Wall Linings Internal - Infill	Flat AC Sheeting							
Ceiling Voids - Flat Roof	No Asbestos Found							
Underfloor Voids	Non Accessible Area							
Interior								
B00B - R0001 - Movement - 2.5 m2								
Ceiling Structures/Linings	Flat AC Sheeting	3m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00B - R0002 - Uniform Shop - 24.54 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (10 - 40 m2) - (X3)							
B00B - R0003 - Staff Toilet - 3.36 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00B - R0004 - Movement - 8.65 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00B - R0005 - Home Base Store - 4.19 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00B - R0006 - Home Base - 57.33 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)							
Plant / Equipment - Flue	Fibre Cement Pipe	1	North, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00B - R0007 - Home Base - 57.17 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)							
Plant / Equipment - Flue	Fibre Cement Pipe	1	South, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00B - R0008 - Home Base Store - 4.46 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00B - R0009 - General Storeroom - 5.06 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00B - R0010 - Movement - 4.07 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00B - R0011 - Movement - 2.47 m2								
Ceiling Structures/Linings	Flat AC Sheeting	3m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00B - R0012 - Movement - 2.32 m2								
Ceiling Structures/Linings	Flat AC Sheeting	3m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00C - General Learning - 1964 - Brick/Veneer								
Exterior								
Wall Linings Internal - Infill	Flat AC Sheeting							
Ceiling Voids - Flat Roof	No Asbestos Found							
Underfloor Voids	Non Accessible Area							
Interior								
B00C - R0001 - Home Base - 57.98 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)							

Plant / Equipment - Flue	Fibre Cement Pipe	1	South west corner	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00C - R0002 - Home Base Store - 4.26 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
B00C - R0003 - Main Switch Board - 1.25 m2							
Wall Linings Internal	Flat AC Sheeting	10m2	Throughout	Some Damage - Unsealed (3)	Low (1)	Medium Priority (4-5)	Chrysotile (white asbestos)
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
B00C - R0004 - Movement - 16.16 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (10 - 40 m2) - (X3)						
B00C - R0005 - Movement - 4.83 m2							
Ceiling Structures/Linings	Flat AC Sheeting	5m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00C - R0006 - Home Base Store - 4.3 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
B00C - R0007 - Home Base - 58.13 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Plant / Equipment - Flue	Fibre Cement Pipe	1	Southeast corner	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00D - General Learning - 1964 - Brick/Veneer							
Exterior							
Wall Linings Internal - Infill	Flat AC Sheeting						
Ceiling Voids - Flat Roof	No Asbestos Found						
Underfloor Voids	Non Accessible Area						
Interior							
B00D - R0001 - Home Base - 58.05 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Plant / Equipment - Flue	Fibre Cement Pipe	1	Southwest corner	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00D - R0002 - Home Base Store - 4.24 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
B00D - R0003 - Movement - 17.62 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (10 - 40 m2) - (X3)						
B00D - R0004 - Movement - 4.8 m2							
Ceiling Structures/Linings	Flat AC Sheeting	5m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00D - R0005 - Home Base Store - 4.26 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
B00D - R0006 - Home Base - 58.05 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Plant / Equipment - Flue	Fibre Cement Pipe	1	Southeast corner	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - Pupil Facilities/Administration - 1964 - Brick/Block							
Exterior							

External Roof Structure	Flat AC Sheeting	8	East, West, Middle portion	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids - Flat Roof	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
Interior							
B00E - R0001 - Toilets - Girls - 30.1 m2							
Ceiling Structures/Linings	Flat AC Sheeting	31m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - R0002 - Toilets - Boys - 28.28 m2							
Ceiling Structures/Linings	Flat AC Sheeting	29m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - R0003 - Staff Toilet - 1.28 m2							
Ceiling Structures/Linings	Flat AC Sheeting	2m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - R0004 - Movement - 46.77 m2							
Ceiling Structures/Linings	Flat AC Sheeting	47m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	8m2	North, South, Upper portion	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - R0005 - General Storeroom - 11.19 m2							
Ceiling Structures/Linings	Flat AC Sheeting	12m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - R0006 - General Assistant/Bulk Store - 21.05 m2							
Ceiling Structures/Linings	Flat AC Sheeting	22m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - R0007 - Movement - 112.65 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	8m2	North, South, Upper portion	Some Damage - Unsealed (3)	Low (1)	Medium Priority (4-5)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - R0008 - Canteen Office/Store - 3.76 m2							
Ceiling Structures/Linings	Flat AC Sheeting	4m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Floor Coverings Res/Textile	Vinyl Tiles						
B00E - R0009 - Staff Toilet - 4.3 m2							
Ceiling Structures/Linings	Flat AC Sheeting	5m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00E - R0010 - Canteen - 24.19 m2							
No Asbestos							
B00E - R0011 - Garden Store - 21.45 m2							
No Asbestos							
B00F - General Learning/Library - 1970 - Brick/Block							
Exterior							
Eaves Linings	Flat AC Sheeting	80m2	East, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids - Flat Roof	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
Interior							
B00F - R0001 - Home Base - 58.02 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Plant / Equipment - Thermocon Heater	Encapsulated Asbestos material within unit	3	Variable positions	Friable Asbestos (5)	Low (1)	Low Priority (2-3)	Assumed Asbestos

Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	58m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00F - R0002 - Home Base Store - 5.75 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles	6m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00F - R0003 - Distribution Board - .76 m2							
Note: No inspection of live electrical installation							
Door - Lining	Flat AC Sheeting	2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00F - R0004 - Movement - 15.81 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (10 - 40 m2) - (X3)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	16m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00F - R0005 - External Movement - 42.21 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
B00F - R0006 - Home Base Store - 4.52 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles	5m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00F - R0007 - Home Base - 57.04 m2							
Plant / Equipment - Thermacon Heater	Encapsulated Asbestos material within unit	3	Variable positions	Friable Asbestos (5)	Low (1)	Low Priority (2-3)	Assumed Asbestos
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	58m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
B00F - R0008 - Movement - 16.59 m2							
No Asbestos							
B00F - R0009 - Cleaning Distributed Store - 5.64 m2							
No Asbestos							
B00F - R0011 - Toilets - Girls - 31.51 m2							
No Asbestos							
B00F - R0012 - Plant - 6.96 m2							
No Asbestos							
B00F - R0013 - Toilets - Boys - 32.82 m2							
No Asbestos							
B00F - R0014 - External Movement - 8.26 m2							
No Asbestos							
B00F - R0016 - Stairs - 4.77 m2							
No Asbestos							
B00F - R0017 - Sports Store - 5.47 m2							
No Asbestos							
B00F - R0018 - Movement - 83.29 m2							

No Asbestos							
B00F - R0019 - Sports Store - 9.9 m2							
No Asbestos							
B00F - R0020 - Sports Store - 7.3 m2							
No Asbestos							
B00F - R1001 - Home Base - 57.79 m2							
No Asbestos							
B00F - R1002 - Home Base Store - 5.73 m2							
No Asbestos							
B00F - R1003 - Distribution Board - .9 m2							
Note: No inspection of live electrical installation							
Door - Lining	Flat AC Sheeting	2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00F - R1004 - Movement - 15.82 m2							
No Asbestos							
B00F - R1005 - Movement - 57.82 m2							
Ceiling Structures/Linings	Flat AC Sheeting	58m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos), Amosite (brown asbestos)
B00F - R1006 - Home Base Store - 4.68 m2							
No Asbestos							
B00F - R1007 - Home Base - 56.83 m2							
No Asbestos							
B00F - R1008 - K.L.A. Store - 28.47 m2							
No Asbestos							
B00F - R1009 - Reading Area - 128.52 m2							
No Asbestos							
B00F - R1010 - Library Office/Workroom - 10.15 m2							
No Asbestos							
B00F - R1011 - Library Office/Workroom - 12.6 m2							
No Asbestos							
B00F - R1012 - Stairs - 11.81 m2							
Ceiling Structures/Linings	Flat AC Sheeting	12m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos), Amosite (brown asbestos)
B00G - General Learning/Staff Facilities - 1970 - Brick/Block							
Exterior							
Eaves Linings	Flat AC Sheeting	70m2	North, South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos), Amosite (brown asbestos)
Ceiling Voids - Flat Roof	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
Interior							
B00G - R0001 - Home Base Store - 6.7 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles						
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00G - R0002 - General Storeroom - 6.8 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles						
B00G - R0003 - Distribution Board - .66 m2							
Note: No inspection of live electrical installation							

Door - Lining	Flat AC Sheeting	2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00G- R0006 - Movement - 8.17 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)						
Floor Coverings Res/Textile	Vinyl Tiles						
B00G- R0007 - Home Base - 57.12 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)						
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
B00G- R0008 - Cleaning Distributed Store - 5.68 m2							
No Asbestos							
B00G- R0009 - Movement - 16.45 m2							
No Asbestos							
B00G- R0010 - Home Base - 56.97 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)						
Floor Coverings Res/Textile	Vinyl Sheet - Adhesive						
B00G- R0011 - Home Base Store - 5.66 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles						
B00G- R0012 - Movement - 15.85 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (10 - 40 m2) - (X3)						
Floor Coverings Res/Textile	Vinyl Tiles						
B00G- R0013 - Home Base Store - 5.66 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						
Floor Coverings Res/Textile	Vinyl Tiles						
B00G- R0014 - Home Base - 57.93 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)						
B00G- R0015 - Stairs - 4.77 m2							
No Asbestos							
B00G- R0016 - External Movement - 58.81 m2							
No Asbestos							
B00G- R0017 - Access Shower/Toilet/Change - 9.04 m2							
No Asbestos							
B00G- R1001 - Home Base Store - 6.71 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)						

Floor Coverings Res/Textile	Vinyl Tiles							
Floor Coverings Res/Textile	Vinyl Tiles							
B00G- R1002 - General Storeroom - 6.75 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
Floor Coverings Res/Textile	Vinyl Tiles							
Floor Coverings Res/Textile	Vinyl Tiles							
B00G- R1003 - Distribution Board - .68 m2								
Note: No inspection of live electrical installation								
Door - Lining	Flat AC Sheeting	2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)	
B00G- R1004 - Staff Toilet - 4.58 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00G- R1005 - Cleaning Distributed Store - 1.95 m2								
Ceiling Structures/Linings	Flat AC Sheeting	2m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)	
B00G- R1006 - Movement - 76.61 m2								
Ceiling Structures/Linings	Flat AC Sheeting	77m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)	
B00G- R1007 - Movement - 8.14 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00G- R1008 - Home Base - 57.12 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)							
Floor Coverings Res/Textile	Vinyl Tiles							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)							
Floor Coverings Res/Textile	Vinyl Tiles							
B00G- R1009 - Home Base - 56.89 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)							
Floor Coverings Res/Textile	Vinyl Tiles							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)							
Floor Coverings Res/Textile	Vinyl Tiles							
Floor Coverings Res/Textile	Vinyl Tiles							
B00G- R1010 - Home Base Store - 5.66 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							
B00G- R1011 - Movement - 15.81 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (10 - 40 m2) - (X3)							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)							
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive							
B00G- R1012 - Home Base Store - 5.63 m2								
Ceiling Structures/Linings	Vermiculite - Composite Sample - (< 10 m2) - (X2)							

B00G - R1013 - Home Base - 57.79 m2							
Ceiling Structures/Linings	Vermiculite - Composite Sample - (40 - 70 m2) - (X5)						
Floor Coverings Res/Textile	Vinyl Tiles						
Floor Coverings Res/Textile	Vinyl Tiles						
B00G - R1014 - Stairs - 11.81 m2							
Ceiling Structures/Linings	Flat AC Sheeting	12m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
B00H - Other-Community Use - 1964 - Brick/Veneer							
Exterior							
Ceiling Voids - Flat Roof	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00H - R0001 - Dental Clinic - 12.64 m2							
No Asbestos							
B00H - R0002 - Dental Clinic - 6.13 m2							
No Asbestos							
B00H - R0003 - Dental Clinic - 1.89 m2							
No Asbestos							
B00H - R0004 - Dental Clinic - 3.86 m2							
No Asbestos							
B00H - R0005 - Dental Clinic - 1.45 m2							
No Asbestos							
B00H - R0006 - Dental Clinic - 8.48 m2							
No Asbestos							
B00H - R0007 - Dental Clinic - .87 m2							
No Asbestos							
B00H - R0008 - Dental Clinic - 8.67 m2							
No Asbestos							
B00H - R0009 - Dental Clinic - 8.56 m2							
No Asbestos							
B00H - R0010 - Dental Clinic - .1 m2							
No Asbestos							
B00H - R0011 - Dental Clinic - 5.57 m2							
No Asbestos							
B00H - R0012 - Dental Clinic - 2.93 m2							
No Asbestos							
B00H - R0013 - Dental Clinic - 8.02 m2							
No Asbestos							
B00H - R0014 - Dental Clinic - 3.43 m2							
No Asbestos							
B00H - R0015 - Dental Clinic - 1.02 m2							
No Asbestos							
B00I - General Learning/Pupil Facilities - 1978 - Brick/Veneer							
Exterior							
Ceiling Voids - Raked Ceiling	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
Interior							

B001 - R0001 - Movement - 6.99 m2	
No Asbestos	
B001 - R0002 - General Storeroom - 3.77 m2	
No Asbestos	
B001 - R0003 - Home Base - 57.44 m2	
No Asbestos	
B001 - R0004 - Home Base Store - 5.43 m2	
No Asbestos	
B001 - R0005 - Practical Activities - 1hb - 39.66 m2	
No Asbestos	
B001 - R0006 - Withdrawal Space - 1hb - 9.65 m2	
No Asbestos	
B001 - R0007 - Home Base - 57.13 m2	
No Asbestos	
B001 - R0008 - Home Base Store - 5.47 m2	
No Asbestos	
B001 - R0009 - Movement - 8.87 m2	
No Asbestos	
B001 - R0010 - Distribution Board - .7 m2	Note: No inspection of live electrical installation
No Asbestos	
B001 - R0011 - Movement - 14.23 m2	
No Asbestos	
B001 - R0012 - Practical Activities - 1hb - 62.99 m2	
No Asbestos	
B001 - R0013 - Cleaning Distributed Store - 1.73 m2	
No Asbestos	
B001 - R0014 - Craft Store - 2.88 m2	
No Asbestos	
B001 - R0015 - Withdrawal Space - 1hb - 9.9 m2	
No Asbestos	
B001 - R0016 - Home Base - 58.37 m2	
No Asbestos	
B001 - R0017 - Home Base Store - 4.15 m2	
No Asbestos	
B001 - R0018 - Seminar/Study - 15.12 m2	
No Asbestos	
B001 - R0019 - Movement - 7.39 m2	
No Asbestos	
B001 - R0020 - Movement - 8.76 m2	
No Asbestos	
B001 - R0021 - Movement - 8.6 m2	
No Asbestos	
B001 - R0022 - Home Base - 57.48 m2	
No Asbestos	
B001 - R0023 - Home Base Store - 5 m2	
No Asbestos	
B001 - R0024 - Withdrawal Space - 1hb - 10.19 m2	
No Asbestos	
B001 - R0025 - Movement - 7.01 m2	
No Asbestos	
B001 - R0026 - Home Base - 56.94 m2	
No Asbestos	

B001 - R0027 - Home Base Store - 5.4 m2							
No Asbestos							
B001 - R0028 - Toilets - Girls - 15.56 m2							
Partition Walls (Cubicles)	Compressed AC Sheet	12m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B001 - R0029 - Cleaning Supplies - 7.43 m2							
No Asbestos							
B001 - R0030 - Toilets - Boys - 15.84 m2							
Partition Walls (Cubicles)	Compressed AC Sheet	6m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B001 - R0031 - Movement - 12.47 m2							
No Asbestos							
B001 - R0032 - Movement - 9.06 m2							
No Asbestos							
B00L - Communal Facilities - 2004 - Concrete							
Exterior							
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
Interior							
B00L - R0001 - Communal Space - 563.77 m2							
No Asbestos							
B00L - R0002 - Hall Chair Store - 28.84 m2							
No Asbestos							
B00L - R0003 - P.E. Store - 9.71 m2							
Floor Coverings Res/Textile	No Asbestos Found						
B00L - R0004 - External Movement - 86.7 m2							
No Asbestos							
B00L - R0005 - Communal/Performance Store - 44.42 m2							
No Asbestos							
B00N - Library - 2011 - Brick/Veneer							
Exterior							
Ceiling Voids	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
Interior							
B00N - R0001 - External Movement - 23.09 m2							
No Asbestos							
B00N - R0002 - Reading Area - 230.73 m2							
No Asbestos							
B00N - R0003 - Library Office/Workroom - 26.62 m2							
No Asbestos							
B00N - R0004 - Communications Room - 8.1 m2							
No Asbestos							
B00N - R0005 - K.L.A. Store - 20.42 m2							
No Asbestos							
B00N - R0006 - Main Switch Board - .72 m2							
No Asbestos							
B00N - R0007 - Toilet - Lobby - 2.49 m2							
No Asbestos							
B00N - R0008 - Cleaning Distributed Store - 3.42 m2							
No Asbestos							

B00N - R0009 - Staff Toilet - 4.92 m2

No Asbestos

B00O - Storage - 1998 - Metal Shed**Exterior**Ceiling Voids - Flat
Roof

No Asbestos Found

Underfloor Voids - Slab
on Ground

No Asbestos Found

Interior**B00O - R0001 - General Assistant/Bulk Store - 18.22 m2**

No Asbestos

B00P - Storage - 2005 - Metal Shed**Exterior**Ceiling Voids - Flat
Roof

No Asbestos Found

Underfloor Voids - Slab
on Ground

No Asbestos Found

Interior**B00P - R0001 - General Storeroom - 34.93 m2**

No Asbestos

Demountables

There are no Demountable(s) Located at this school as per the AMS records as of 09-Sep-2020