

Asbestos Register

(Hazardous Materials and Risk Assessment)

School:	Lightning Ridge Central School (2395)
Region:	North Western NSW AMU
State Electorate:	Barwon
Local Government Area:	Walgett

Last Reviewed By:	WSP 01-NOV-2016
Last Revised By:	

Historical Fibro In Grounds Investigations/Events	No
<p>No previous investigations have been recorded against the school. However, asbestos containing materials maybe present in grounds from time to time and caution must be exercised prior to any grounds disturbance.</p>	

2395 - Lightning Ridge Central School
Site Plan (10638)



Preface to Asbestos Register

Limitations

Asbestos Registers established (first surveyed 2007/08) and maintained for the Department of Education (DoE) are limited in extent, in that:

1. All inspections and surveys of materials and finishes in DoE facilities are non-disturbance, with
2. Samples undertaken by hygienist to determine whether a sample is an Asbestos Containing Material (ACM),
3. The hygienist may apply a single sample to like materials within a space and adjoining spaces, but not normally between buildings,
4. Successive inspections have reduced any inconclusive records such as 'assumed asbestos' in difficult to access areas, by undertaking additional sampling with lifting devices.
5. In compliance with WHS Act 2011 and WHS Regulations 2017, additional inspections have been undertaken in ceiling spaces and sub-floor areas where access is possible.
 - o Where the ground floor is slab on ground, no inspection is made beneath the slab.
 - o Where fibro fragments (ACM taken for sampling) are located in ceiling spaces or sub floor voids air monitoring is normally undertaken at time of sampling, and clearance undertaken as soon as practicable.
6. No attempt has been made to identify any ACM that is hidden from view or encapsulated within
 - o Any wall cavity
 - o Sub floor area, particularly formwork for slabs in/on ground,
 - o Services (that may use ACM) such as: pipe lagging, asbestos cement pipes, flues.
7. All known ACM in Grounds (Fibro in Grounds) is made available in associated site specific asbestos management plans in DoE electronic files.
Notwithstanding information provided, ACM may be present in grounds from time to time and caution must be exercised prior to any grounds disturbance.

Use of the Asbestos Register

Prior to any disturbance works being undertaken in a building to which this asbestos register applies it will be necessary to confirm the extent of any ACM by a disturbance investigation:

- If the building was built prior to 2003
- If any ACM has been identified in the Asbestos Register for the building.

Update of Asbestos Registers

Asbestos Register Data is updated regularly by the DoE Hygienist Panel via the Online Asbestos Register Tool (Managed by Business Systems, School Infrastructure NSW). Internal users can view the latest edition of the Asbestos Register in the AMS.

Please note: The Department's external website may not contain the latest revision of the Asbestos Register.

Notes 1: Vermiculite

- During 2018/19, all vermiculite occurrences in DoE schools identified in 2007/08, were 'composite tested' in accordance with a safe work NSW agreed procedure. This required multiple testing of all vermiculite occurrences.
- During the period 2007/08 to 2018/19, some vermiculite has been over sheeted and a warning is indicated for schools where this has happened.

Note 2: DoE website link for information is here:

<https://www.schoolinfrastructure.nsw.gov.au/about-us/working-with-us/schools-asbestos-register.html>
<https://education.nsw.gov.au/about-us/strategies-and-reports/our-reports-and-reviews/schools-asbestos-register>

Note 3: Material Condition Assessment

The material condition assessment descriptors from Section 3 of the Asbestos Management Plan (AMP) is extracted below. Please read the AMP in its entirety for further information.

3.3.2.1 Material condition assessment

The OART records the material condition of identified ACM in the following format:

Rating	Description
Good condition (1)	For non-friable asbestos that is sealed and has no visible damage. This primarily related to asbestos cement (AC) sheet and vinyl tiles
Minimal damage (2)	For non-friable asbestos that has a very small amount of damage, eg hairline cracks.
Some damage / unsealed (3)	For non-friable asbestos with significant breakage or several small areas where material has been damaged, revealing loose asbestos fibres. Non-friable asbestos that is unsealed.
Poor condition (4)	For non-friable asbestos that has extensive damage. Visible asbestos debris
Friable asbestos (5)	Any occurrence of friable asbestos

Product	Material Description	Extent	Location	Material Condition	Risk Status	Remediation Priority	Result
B00A - General Learning - 1967 - Brick/Veneer							
Exterior							
Ceiling Voids	Requires Inspection						
Underfloor Voids - Slab on Ground	No Asbestos Found						
Eaves Linings	Flat AC Sheeting	15m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Eaves Linings	Flat AC Sheeting	20m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	12	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Mastic						
Interior							
B00A - R0001 - External Movement - 42.26 m2							
Wall Linings Internal - Infill	Flat AC Sheeting	8m2	South	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Structures/Linings	Flat AC Sheeting	43m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00A - R0002 - Movement - 9.09 m2							
No Asbestos							
B00A - R0003 - Home Base Store - 4.11 m2							
No Asbestos							
B00A - R0004 - Practical Activities - 1hb - 5.04 m2							
No Asbestos							
B00A - R0005 - Home Base - 51.56 m2							
No Asbestos							
B00A - R0006 - Home Base - 51.59 m2							
No Asbestos							
B00A - R0007 - Practical Activities - 1hb - 4.89 m2							
Floor Coverings Res/Textile	Vinyl Tiles						
B00A - R0008 - Home Base Store - 4.04 m2							
Non Accessible							
Ceiling Voids	No Asbestos Found						
B00A - R0009 - Movement - 8.84 m2							
No Asbestos							
B00A - R0010 - General Storeroom - 11.82 m2							
No Asbestos							
B00A - R0011 - Interview - 15.46 m2							
No Asbestos							
B00A - R0012 - Plant - 3.34 m2							
Wall Linings Internal - Service Risers / Boxing	Flat AC Sheeting						
B00B - Support Unit - 1911 - Timber							
Exterior							
Underfloor Voids	AC Fragments/Debris	1	Variable positions	Poor Condition - Extensive Damage (4)	Low (1)	Medium Priority (4-5)	Chrysotile (white asbestos)
Ceiling Voids	Non Accessible Area						
Interior							
B00B - R0001 - External Movement - 14.12 m2							
No Asbestos							
B00B - R0002 - Home Base - M - 72.39 m2							

No Asbestos							
B00B - R0003 - Staff Room Annexe - 14.35 m2							
No Asbestos							
B00C - General Learning/Pupil Facilities - 1986 - Brick/Veneer							
Exterior							
Underfloor Voids - Slab on Ground	No Asbestos Found						
Ceiling Voids	No Asbestos Found						
Interior							
B00C - R0001 - External Movement - 386.63 m2							
Ceiling Structures/Linings	Flat AC Sheeting	387m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	10m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0002 - Toilets - Boys - 10.88 m2							
Ceiling Structures/Linings	Flat AC Sheeting	11m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Partition Walls (Cubicles)	Compressed AC Sheet	4m2	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Structures/Linings	Flat AC Sheeting	11m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0003 - Practical Activities - 1hb - 11.65 m2							
No Asbestos							
B00C - R0004 - Toilets - Boys/Girls - 2.99 m2							
No Asbestos							
B00C - R0005 - Home Base - 87.69 m2							
No Asbestos							
B00C - R0006 - Home Base - 51.78 m2							
No Asbestos							
B00C - R0007 - Practical Activities - 1hb - 22.01 m2							
No Asbestos							
B00C - R0008 - Staff Kitchen - 26.74 m2							
Floor Coverings Res/Textile	Vinyl Tiles	27m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0009 - General Storeroom - 21.41 m2							
Floor Coverings Res/Textile	Vinyl Tiles	22m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0010 - Staff Toilet - 4.22 m2							
Wall Linings Internal - Infill	Flat AC Sheeting						
B00C - R0011 - Staff Toilet - 4.6 m2							
Ceiling Structures/Linings	Flat AC Sheeting	5m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	1m2	North	Some Damage - Unsealed (3)	Low (1)	Medium Priority (4-5)	Chrysotile (white asbestos)
B00C - R0012 - Toilets - Girls - 10.75 m2							
Ceiling Structures/Linings	Flat AC Sheeting	6m2	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Partition Walls (Cubicles)	Compressed AC Sheet	6m2	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
B00C - R0013 - General Storeroom - 6.3 m2							
No Asbestos							
B00C - R0014 - Cleaning Distributed Store - 6.66 m2							
Ceiling Structures/Linings	Flat AC Sheeting						
B00C - R0015 - Sports Store - 23.32 m2							
No Asbestos							

B00C - R0016 - Distribution Board - .19 m2							Note: No inspection of live electrical installation	
Ceiling Structures/Linings	Flat AC Sheeting							
B00C - R0017 - Movement - 17.23 m2								
No Asbestos								
B00C - R0018 - Kitchenette - 16.64 m2								
No Asbestos								
B00C - R0019 - General Storeroom - 2.1 m2								
No Asbestos								
B00C - R0020 - General Storeroom - 2.59 m2								
No Asbestos								
B00C - R0021 - Staff Toilet - 1.98 m2								
Plant / Equipment - Incinerator	Encapsulated Asbestos material within unit	1	East	Friable Asbestos (5)	Low (1)	Low Priority (2-3)	Assumed Asbestos	
B00C - R0022 - Communal Space - 113.74 m2								
No Asbestos								
B00C - R0023 - Raised Platform - 37.3 m2								
No Asbestos								
B00C - R0024 - General Storeroom - 9.24 m2								
No Asbestos								
B00C - R0025 - General Storeroom - 11.55 m2								
No Asbestos								
B00C - R0026 - Plant - 9.03 m2								
Wall Linings Internal	Flat AC Sheeting							
B00C - R0027 - Cleaning Supplies - 4.13 m2								
No Asbestos								
B00C - R0028 - Cleaning Distributed Store - 1.68 m2								
Ceiling Structures/Linings	Flat AC Sheeting							
B00D - General Learning - 1986 - Brick/Veneer								
Exterior								
Ceiling Voids	No Asbestos Found							
Underfloor Voids	No Asbestos Found							
Interior								
B00D - R0001 - Home Base Store - 5.8 m2								
No Asbestos								
B00D - R0002 - Home Base - 60.07 m2								
No Asbestos								
B00D - R0003 - Practical Activities - 1hb - 16.44 m2								
No Asbestos								
B00D - R0004 - Outdoor Learning Area - 13.86 m2								
No Asbestos								
B00D - R0005 - External Movement - 34.77 m2								
Ceiling Structures/Linings	Flat AC Sheeting							
B00D - R0006 - Practical Activities - 1hb - 15.87 m2								
No Asbestos								
B00D - R0007 - Home Base - 60.21 m2								
No Asbestos								
B00D - R0008 - Home Base Store - 5.77 m2								
No Asbestos								
B00D - R0009 - Outdoor Learning Area - 13.86 m2								
No Asbestos								
B00D - R0010 - Withdrawal Space - 1hb - 11.89 m2								
No Asbestos								

B00E - General Learning - 1986 - Brick/Veneer

Exterior

Underfloor Voids	No Asbestos Found
------------------	-------------------

Ceiling Voids	No Asbestos Found
---------------	-------------------

Interior

B00E - R0001 - Home Base Store - 5.8 m2

No Asbestos

B00E - R0002 - Home Base - 59.95 m2

No Asbestos

B00E - R0003 - Practical Activities - 1hb - 16.3 m2

No Asbestos

B00E - R0004 - Outdoor Learning Area - 13.89 m2

No Asbestos

B00E - R0005 - External Movement - 34.81 m2

Ceiling Structures/Linings	Flat AC Sheeting
----------------------------	------------------

B00E - R0006 - Practical Activities - 1hb - 16.3 m2

No Asbestos

B00E - R0007 - Home Base - 60.04 m2

No Asbestos

B00E - R0008 - Home Base Store - 5.77 m2

No Asbestos

B00E - R0009 - Outdoor Learning Area - 13.81 m2

No Asbestos

B00E - R0010 - Withdrawal Space - 1hb - 11.86 m2

No Asbestos

B00F - General Learning - 1986 - Brick/Veneer

Exterior

Underfloor Voids	No Asbestos Found
------------------	-------------------

Ceiling Voids	No Asbestos Found
---------------	-------------------

Interior

B00F - R0001 - Home Base Store - 5.8 m2

No Asbestos

B00F - R0002 - Home Base - 59.94 m2

No Asbestos

B00F - R0003 - Practical Activities - 1hb - 16.31 m2

No Asbestos

B00F - R0004 - Outdoor Learning Area - 13.89 m2

No Asbestos

B00F - R0005 - External Movement - 34.8 m2

Ceiling Structures/Linings	Flat AC Sheeting
----------------------------	------------------

B00F - R0006 - Practical Activities - 1hb - 16.3 m2

No Asbestos

B00F - R0007 - Home Base - 59.85 m2

No Asbestos

B00F - R0008 - Home Base Store - 5.8 m2

No Asbestos

B00F - R0009 - Outdoor Learning Area - 13.89 m2

No Asbestos

B00F - R0010 - Withdrawal Space - 1hb - 11.86 m2

No Asbestos

B00G - Pupil Facilities - 1970 - Brick/Block**Exterior**

Eaves Linings	Flat AC Sheeting	22m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Eaves Linings	Flat AC Sheeting	12m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
Ceiling Voids - Flat Roof	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						

Interior**B00G - R0001 - Toilets - Boys - 42.95 m2**

Ceiling Structures/Linings	Flat AC Sheeting	43m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Partition Walls (Cubicles)	Compressed AC Sheet						

B00G - R0002 - Toilets - Girls - 43.01 m2

Ceiling Structures/Linings	Flat AC Sheeting	44m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Partition Walls (Cubicles)	Compressed AC Sheet						

B00I - Agricultural Science - 2000 - Brick/Veneer**Exterior**

Underfloor Voids - Slab on Ground	No Asbestos Found						
Ceiling Voids	No Asbestos Found						

Interior**B00I - R0001 - Class Tools Storage - 11.25 m2**

No Asbestos							
-------------	--	--	--	--	--	--	--

B00I - R0002 - Agriculture Covered Area - 35.39 m2

No Asbestos							
-------------	--	--	--	--	--	--	--

B00I - R0003 - Plant Space - 24.19 m2

No Asbestos							
-------------	--	--	--	--	--	--	--

B00I - R0004 - No Access - 35.89 m2

No Asbestos							
-------------	--	--	--	--	--	--	--

B00J - Administration - 2000 - Brick/Veneer**Exterior**

Underfloor Voids - Slab on Ground	No Asbestos Found						
Ceiling Voids	No Asbestos Found						

Interior**B00J - R0001 - Interview - 12.94 m2**

Floor Coverings Res/Textile	No Asbestos Found						
-----------------------------	-------------------	--	--	--	--	--	--

B00J - R0002 - Deputy Principal - 12.91 m2

Floor Coverings Res/Textile	No Asbestos Found						
-----------------------------	-------------------	--	--	--	--	--	--

B00J - R0003 - Movement - 37.53 m2

Floor Coverings Res/Textile	No Asbestos Found						
-----------------------------	-------------------	--	--	--	--	--	--

B00J - R0004 - Clerical Office - 84.36 m2

Floor Coverings Res/Textile	No Asbestos Found						
-----------------------------	-------------------	--	--	--	--	--	--

B00J - R0005 - Principal - 17.57 m2

Floor Coverings Res/Textile	No Asbestos Found						
-----------------------------	-------------------	--	--	--	--	--	--

B00J - R0006 - Staff Toilet - 4.04 m2

No Asbestos							
-------------	--	--	--	--	--	--	--

B00J - R0007 - Staff Toilet - 4.09 m2

No Asbestos							
-------------	--	--	--	--	--	--	--

B00J - R0008 - Distribution Board - 10.75 m2		Note: No inspection of live electrical installation
No Asbestos		
B00J - R0009 - Interview - 12.83 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00J - R0010 - Interview - 12.88 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00J - R0011 - Canteen Office/Store - 12.9 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00J - R0012 - Movement - 26.62 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00J - R0013 - Communications Cupboard - 1.95 m2		
No Asbestos		
B00J - R0014 - Staff Kitchen - 4.82 m2		
No Asbestos		
B00J - R0015 - Community Clinic - 12.92 m2		
No Asbestos		
B00J - R0016 - Toilets - Girls - 2.12 m2		
No Asbestos		
B00J - R0017 - Toilets - Boys - 2.12 m2		
No Asbestos		
B00J - R0018 - Community Clinic - 12.92 m2		
No Asbestos		
B00J - R0019 - Duplicating Workroom - 12.81 m2		
No Asbestos		
B00J - R0020 - Security Store - 12.88 m2		
No Asbestos		
B00J - R0021 - Cleaning Distributed Store - 4.01 m2		
No Asbestos		
B00J - R0022 - External Movement - 179.41 m2		
No Asbestos		
B00J - R0023 - External Movement - 3.65 m2		
No Asbestos		
B00K - Technological & Applied Studies - 2000 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00K - R0001 - External Movement - 28.17 m2		
No Asbestos		
B00K - R0002 - Outdoor Workshop - 95.65 m2		
No Asbestos		
B00K - R0003 - Welding/Hot Metals Area - 10.84 m2		
No Asbestos		
B00K - R0004 - Kiln Room - 9.66 m2		
No Asbestos		
B00K - R0005 - Communications Cupboard - 1.32 m2		
No Asbestos		
B00K - R0006 - Materials Store - 9.3 m2		
No Asbestos		
B00K - R0007 - Plant - 6.69 m2		
No Asbestos		

B00K - R0008 - Distribution Board - .8 m2		Note: No inspection of live electrical installation
No Asbestos		
B00K - R0009 - L.P.G Store - 1.22 m2		
No Asbestos		
B00K - R0010 - External Movement - 289.52 m2		
No Asbestos		
B00K - R0011 - Materials Workshop - Type 2 - 120.81 m2		
No Asbestos		
B00K - R0012 - General Learning Space - 60.01 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00K - R0013 - General Learning Space - 60.06 m2		
No Asbestos		
B00K - R0014 - Plant - 7.4 m2		
No Asbestos		
B00K - R0015 - Cleaning Distributed Store - 3.8 m2		
No Asbestos		
B00K - R0016 - Laundry - 9.06 m2		
No Asbestos		
B00K - R0017 - Resource/Project Store - 42.13 m2		
No Asbestos		
B00K - R0018 - Materials Store - 14.03 m2		
No Asbestos		
B00K - R0019 - Pantry - 4.66 m2		
No Asbestos		
B00K - R0020 - Preparation - 14.03 m2		
No Asbestos		
B00K - R0021 - General Learning Space - 59.13 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00K - R0022 - Materials Workshop - Type 2 - 104.8 m2		
No Asbestos		
B00K - R0023 - General Learning Space - 60.88 m2		
No Asbestos		
B00K - R0024 - Distribution Board - 1.97 m2		Note: No inspection of live electrical installation
No Asbestos		
B00K - R0025 - Plant - 1.98 m2		
No Asbestos		
B00L - Library - 2004 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00L - R0001 - Entry - 24.82 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0002 - Computer Resource - 10.84 m2		
No Asbestos		
B00L - R0003 - Distribution Board Cupboard - .83 m2		Note: No inspection of live electrical installation
No Asbestos		
B00L - R0004 - System Administrators Office - 13.65 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0005 - Careers Advisers Office - 12.5 m2		

Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0006 - Movement - 10.3 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0007 - Staff Toilet - 5.1 m2		
No Asbestos		
B00L - R0008 - Disabled Toilet - 4.92 m2		
No Asbestos		
B00L - R0009 - Seminar - 12.95 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0010 - Seminar - 12.95 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0011 - Audio Visual Workroom - 28.3 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0012 - General Storeroom - 6.46 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0013 - General Storeroom - 6.7 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0014 - Computer Store - 10.12 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0015 - Computer Learning Space - 64.75 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0016 - Workroom - 56.86 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00L - R0017 - External Movement - 292.88 m2		
No Asbestos		
B00L - R0018 - Main Area - 236.64 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00M - Staff Facilities - 2004 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00M - R0001 - Staff Study - 16.32 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00M - R0002 - Distribution Board Cupboard - .81 m2		
Note: No inspection of live electrical installation		
No Asbestos		
B00M - R0003 - Security Store - 14.84 m2		
No Asbestos		
B00M - R0004 - Cleaning Distributed Store - 2.83 m2		
No Asbestos		
B00M - R0005 - Disabled Toilet - 5.66 m2		
No Asbestos		
B00M - R0006 - Staff Toilet - 4.78 m2		
No Asbestos		
B00M - R0007 - Staff Toilet - 4.78 m2		
No Asbestos		
B00M - R0008 - Staff Toilet - 4.78 m2		
No Asbestos		
B00M - R0009 - Interview - 12.8 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00M - R0010 - Interview - 13.06 m2		

Floor Coverings Res/Textile	No Asbestos Found	
B00M - R0011 - Movement - 32.98 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00M - R0012 - Duplicating Workroom - 30.34 m2		
No Asbestos		
B00M - R0013 - Staff Study - 94.77 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00M - R0014 - Commonroom - 77.21 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00M - R0015 - External Movement - 181.54 m2		
No Asbestos		
B00N - Multi Purpose Facilities - 2004 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00N - R0001 - Community Clinic - 13.23 m2		
No Asbestos		
B00N - R0002 - Sports Store - 22.14 m2		
No Asbestos		
B00N - R0003 - Shower/Change - 14.72 m2		
No Asbestos		
B00N - R0004 - Movement - 22.38 m2		
No Asbestos		
B00N - R0005 - Movement - 19.74 m2		
No Asbestos		
B00N - R0006 - Shower/Change - 5.69 m2		
No Asbestos		
B00N - R0007 - Shower/Change - 14.71 m2		
No Asbestos		
B00N - R0008 - Staff Change - 5.68 m2		
No Asbestos		
B00N - R0009 - Hall Chair Store - 24.25 m2		
No Asbestos		
B00N - R0010 - Sports Store - 19.36 m2		
No Asbestos		
B00N - R0011 - Hall Chair Store - 20.94 m2		
No Asbestos		
B00N - R0012 - Multi-Purpose Space - 477.34 m2		
No Asbestos		
B00N - R0013 - Plant - .8 m2		
No Asbestos		
B00N - R0014 - Distribution Board Cupboard - .99 m2		
No Asbestos		Note: No inspection of live electrical installation
B00N - R0015 - General Storeroom - .71 m2		
No Asbestos		
B00N - R0016 - External Movement - 199.01 m2		
No Asbestos		
B00N - R0017 - External Movement - 10.57 m2		
No Asbestos		
B00N - R0018 - External Movement - 10.57 m2		

No Asbestos		
B00O - Pupil Facilities - 2004 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00O - R0001 - Canteen - 44.7 m2		
No Asbestos		
B00O - R0002 - Canteen Office/Store - 11.97 m2		
No Asbestos		
B00O - R0003 - Canteen - 2.47 m2		
No Asbestos		
B00O - R0004 - External Movement - 175.5 m2		
No Asbestos		
B00P - Pupil Facilities - 2004 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00P - R0001 - Toilets - Girls - 36.47 m2		
No Asbestos		
B00P - R0002 - Toilets - Boys - 29.22 m2		
No Asbestos		
B00P - R0003 - Cleaning Distributed Store - 3.33 m2		
No Asbestos		
B00P - R0004 - Distribution Board Cupboard - .73 m2		
No Asbestos		Note: No inspection of live electrical installation
B00P - R0005 - External Movement - 98.45 m2		
No Asbestos		
B00Q - Science/Art - 2004 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00Q - R0001 - Garden Store - 15.25 m2		
No Asbestos		
B00Q - R0002 - Cleaning Supplies - 12.54 m2		
No Asbestos		
B00Q - R0003 - Bulk Store - 35.07 m2		
No Asbestos		
B00Q - R0004 - Resources Store - 20.62 m2		
No Asbestos		
B00Q - R0005 - Cleaning Distributed Store - 5.04 m2		
No Asbestos		
B00Q - R0006 - Distribution Board Cupboard - .89 m2		
No Asbestos		Note: No inspection of live electrical installation
B00Q - R0007 - General Learning Space - 59.82 m2		

Floor Coverings Res/Textile	No Asbestos Found	
B00Q - R0008 - General Learning Space - 59.82 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00Q - R0009 - Visual Arts Workshop - 99.25 m2		
No Asbestos		
B00Q - R0010 - Dark Room - 27.23 m2		
No Asbestos		
B00Q - R0011 - Preparation - 46.07 m2		
No Asbestos		
B00Q - R0012 - Movement - 11.09 m2		
No Asbestos		
B00Q - R0013 - Apparatus Store - 16.4 m2		
No Asbestos		
B00Q - R0014 - Botany/Zoology - 16.02 m2		
No Asbestos		
B00Q - R0015 - Chemical Store - 12.52 m2		
No Asbestos		
B00Q - R0016 - Distribution Board Cupboard - .95 m2		Note: No inspection of live electrical installation
No Asbestos		
B00Q - R0017 - General Learning Space - 60.13 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00Q - R0018 - General Learning Space - 60.29 m2		
Floor Coverings Res/Textile	No Asbestos Found	
B00Q - R0019 - Science Laboratory - 99.54 m2		
No Asbestos		
B00Q - R0020 - External Movement - 261.69 m2		
No Asbestos		
B00Q - R0021 - External Movement - 10.56 m2		
No Asbestos		
B00R - General Learning - 2009 - Fibre Cement Clad		
Exterior		
Ceiling Voids	No Asbestos Found	
Underfloor Voids	No Asbestos Found	
Interior		
B00R - R0001 - External Movement - 38.48 m2		
No Asbestos		
B00R - R0002 - Practical Activities - 1hb - 19.4 m2		
No Asbestos		
B00R - R0003 - Home Base Store - 6.02 m2		
No Asbestos		
B00R - R0004 - Home Base - 59.2 m2		
No Asbestos		
B00R - R0005 - Withdrawal Space - 2hb - 11.36 m2		
No Asbestos		
B00R - R0006 - Home Base - 59.19 m2		
No Asbestos		
B00R - R0007 - Home Base Store - 6.02 m2		
No Asbestos		
B00R - R0008 - Practical Activities - 1hb - 19.41 m2		
No Asbestos		
B00S - General Learning - 2009 - Fibre Cement Clad		

Exterior		
Ceiling Voids	No Asbestos Found	
Underfloor Voids	No Asbestos Found	
Interior		
B00S - R0001 - External Movement - 38.48 m2		
No Asbestos		
B00S - R0002 - Practical Activities - 1hb - 19.4 m2		
No Asbestos		
B00S - R0003 - Home Base Store - 6.02 m2		
No Asbestos		
B00S - R0004 - Home Base - 59.2 m2		
No Asbestos		
B00S - R0005 - Withdrawal Space - 2hb - 11.36 m2		
No Asbestos		
B00S - R0006 - Home Base - 59.19 m2		
No Asbestos		
B00S - R0007 - Home Base Store - 6.02 m2		
No Asbestos		
B00S - R0008 - Practical Activities - 1hb - 19.41 m2		
No Asbestos		
B00T - General Learning - 2010 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00T - R0001 - External Movement - 28.38 m2		
No Asbestos		
B00T - R0002 - Seminar - Type 2 - 19.12 m2		
No Asbestos		
B00T - R0003 - Resources Store - 10.04 m2		
No Asbestos		
B00T - R0004 - Computer Store - 9 m2		
No Asbestos		
B00T - R0005 - Computer Learning Space - 91.37 m2		
No Asbestos		
B00T - R0006 - Distribution Board - .82 m2		
No Asbestos		Note: No inspection of live electrical installation
B00U - Administration - 2010 - Brick/Veneer		
Exterior		
Underfloor Voids - Slab on Ground	No Asbestos Found	
Ceiling Voids	No Asbestos Found	
Interior		
B00U - R0001 - Toilets-Boys - 3.57 m2		
No Asbestos		
B00U - R0002 - Toilets-Girls - 3.54 m2		
No Asbestos		

Demountables

OS 601 10739 - Learning Unit - Standard/Withdrawal - Placement Date : 30-JUN-1995

Exterior

Eaves Linings	Flat AC Sheeting	11.52m2	Assumed Asbestos
Landing	Compressed AC Sheet	1.2m2	Assumed Asbestos
Step Treads	Compressed AC Sheet	1.08m2	Assumed Asbestos

Interior

R1- Entry

End Wall Panel	Flat AC Sheeting	18m2	Assumed Asbestos
Ceiling Structures/Linings	Flat AC Sheeting	8m2	Assumed Asbestos

R2- General Learning Space

End Wall Panel	Flat AC Sheeting	18m2	Assumed Asbestos
Ceiling Structures/Linings	Flat AC Sheeting	55m2	Assumed Asbestos

R3- Store

Ceiling Structures/Linings	Flat AC Sheeting	10m2	Assumed Asbestos
----------------------------	------------------	------	------------------

OS 601 10742 - Learning Unit - Standard/Withdrawal - Placement Date : 30-JUN-1995

Exterior

Eaves Linings	Flat AC Sheeting	11.52m2	Assumed Asbestos
Landing	Compressed AC Sheet	1.2m2	Assumed Asbestos
Step Treads	Compressed AC Sheet	1.08m2	Assumed Asbestos

Interior

R1- Entry

End Wall Panel	Flat AC Sheeting	18m2	Assumed Asbestos
Ceiling Structures/Linings	Flat AC Sheeting	8m2	Assumed Asbestos

R2- General Learning Space

End Wall Panel	Flat AC Sheeting	18m2	Assumed Asbestos
Ceiling Structures/Linings	Flat AC Sheeting	55m2	Assumed Asbestos

R3- Store

Ceiling Structures/Linings	Flat AC Sheeting	10m2	Assumed Asbestos
----------------------------	------------------	------	------------------

OS 601 10999 - Learning Unit - Standard/Withdrawal - Placement Date : 25-FEB-1999

Exterior

Eaves Linings	Flat AC Sheeting	11.52m2	Assumed Asbestos
Landing	Compressed AC Sheet	1.2m2	Assumed Asbestos
Step Treads	Compressed AC Sheet	1.08m2	Assumed Asbestos

Interior

R1- Entry

End Wall Panel	Flat AC Sheeting	18m2	Assumed Asbestos
Ceiling Structures/Linings	Flat AC Sheeting	8m2	Assumed Asbestos

R2- General Learning Space

End Wall Panel	Flat AC Sheeting	18m2	Assumed Asbestos
Ceiling Structures/Linings	Flat AC Sheeting	55m2	Assumed Asbestos

R3- Store

Ceiling Structures/Linings	Flat AC Sheeting	10m2	Assumed Asbestos
----------------------------	------------------	------	------------------

OS 601 12844 - Learning Unit - Standard/Withdrawal - Placement Date : 05-FEB-1997

Exterior

Eaves Linings	Flat AC Sheeting	11.52m2	Assumed Asbestos
Landing	Compressed AC Sheet	1.2m2	Assumed Asbestos
Step Treads	Compressed AC Sheet	1.08m2	Assumed Asbestos

Interior

R1- Entry			
End Wall Panel	Flat AC Sheeting	18m2	Assumed Asbestos
Ceiling Structures/Linings	Flat AC Sheeting	8m2	Assumed Asbestos
R2- General Learning Space			
End Wall Panel	Flat AC Sheeting	18m2	Assumed Asbestos
Ceiling Structures/Linings	Flat AC Sheeting	55m2	Assumed Asbestos
R3- Store			
Ceiling Structures/Linings	Flat AC Sheeting	10m2	Assumed Asbestos