

# Asbestos Register

(Hazardous Materials and Risk Assessment)

School:	Lochinvar Public School (2417)
Region:	Hunter/Central Coast AMU
State Electorate:	Maitland
Local Government Area:	Maitland

Last Reviewed By:	Greencap 07-OCT-2015
Last Revised By:	

Historical Fibro In Grounds Investigations/Events	<b>No</b>
<p>No previous investigations have been recorded against the school. However, asbestos containing materials maybe present in grounds from time to time and caution must be exercised prior to any grounds disturbance.</p>	

2417 - Lochinvar Public School  
Site Plan (11179)



1:931

Printed: 21-Mar-2020

# Preface to Asbestos Register

## Limitations

Asbestos Registers established (first surveyed 2007/08) and maintained for the Department of Education (DoE) are limited in extent, in that:

1. All inspections and surveys of materials and finishes in DoE facilities are non-disturbance, with
2. Samples undertaken by hygienist to determine whether a sample is an Asbestos Containing Material (ACM),
3. The hygienist may apply a single sample to like materials within a space and adjoining spaces, but not normally between buildings,
4. Successive inspections have reduced any inconclusive records such as 'assumed asbestos' in difficult to access areas, by undertaking additional sampling with lifting devices.
5. In compliance with WHS Act 2011 and WHS Regulations 2017, additional inspections have been undertaken in ceiling spaces and sub-floor areas where access is possible.
  - o Where the ground floor is slab on ground, no inspection is made beneath the slab.
  - o Where fibro fragments (ACM taken for sampling) are located in ceiling spaces or sub floor voids air monitoring is normally undertaken at time of sampling, and clearance undertaken as soon as practicable.
6. No attempt has been made to identify any ACM that is hidden from view or encapsulated within
  - o Any wall cavity
  - o Sub floor area, particularly formwork for slabs in/on ground,
  - o Services (that may use ACM) such as: pipe lagging, asbestos cement pipes, flues.
7. All known ACM in Grounds (Fibro in Grounds) is made available in associated site specific asbestos management plans in DoE electronic files.  
Notwithstanding information provided, ACM may be present in grounds from time to time and caution must be exercised prior to any grounds disturbance.

## Use of the Asbestos Register

Prior to any disturbance works being undertaken in a building to which this asbestos register applies it will be necessary to confirm the extent of any ACM by a disturbance investigation:

- If the building was built prior to 2003
- If any ACM has been identified in the Asbestos Register for the building.

## Update of Asbestos Registers

Asbestos Register Data is updated regularly by the DoE Hygienist Panel via the Online Asbestos Register Tool (Managed by Business Systems, School Infrastructure NSW). Internal users can view the latest edition of the Asbestos Register in the AMS.

Please note: The Department's external website may not contain the latest revision of the Asbestos Register.

## Notes 1: Vermiculite

- During 2018/19, all vermiculite occurrences in DoE schools identified in 2007/08, were 'composite tested' in accordance with a safe work NSW agreed procedure. This required multiple testing of all vermiculite occurrences.
- During the period 2007/08 to 2018/19, some vermiculite has been over sheeted and a warning is indicated for schools where this has happened.

## Note 2: DoE website link for information is here:

<https://www.schoolinfrastructure.nsw.gov.au/about-us/working-with-us/schools-asbestos-register.html>

<https://education.nsw.gov.au/about-us/strategies-and-reports/our-reports-and-reviews/schools-asbestos-register>

## Note 3: Material Condition Assessment

The material condition assessment descriptors from Section 3 of the Asbestos Management Plan (AMP) is extracted below. Please read the AMP in its entirety for further information.

### 3.3.2.1 Material condition assessment

The OART records the material condition of identified ACM in the following format:

Rating	Description
Good condition (1)	For non-friable asbestos that is sealed and has no visible damage. This primarily related to asbestos cement (AC) sheet and vinyl tiles
Minimal damage (2)	For non-friable asbestos that has a very small amount of damage, eg hairline cracks.
Some damage / unsealed (3)	For non-friable asbestos with significant breakage or several small areas where material has been damaged, revealing loose asbestos fibres. Non-friable asbestos that is unsealed.
Poor condition (4)	For non-friable asbestos that has extensive damage. Visible asbestos debris
Friable asbestos (5)	Any occurrence of friable asbestos

Product	Material Description	Extent	Location	Material Condition	Risk Status	Remediation Priority	Result
<b>B00A - General Learning/Administration - 1975 - Brick/Veneer</b>							
<b>Exterior</b>							
Gable Verge Lining	Flat AC Sheeting						
Eaves Linings	Flat AC Sheeting	20m2	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	12	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
<b>Interior</b>							
<b>B00A - R0001 - Staff Toilet - 3.33 m2</b>							
No Asbestos							
<b>B00A - R0002 - Clerical Office - 19.14 m2</b>							
No Asbestos							
<b>B00A - R0003 - Clerical Office/Workroom - 11.34 m2</b>							
No Asbestos							
<b>B00A - R0004 - Entry Vestibule - 11.12 m2</b>							
No Asbestos							
<b>B00A - R0005 - External Movement - 76.66 m2</b>							
Ceiling Structures/Linings	Flat AC Sheeting	77m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Wall Linings Internal - Infill	Flat AC Sheeting	10m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
<b>B00A - R0006 - Home Base Store - 11.24 m2</b>							
Floor Coverings Res/Textile	Vinyl Tiles	12m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
<b>B00A - R0007 - Movement - 11.19 m2</b>							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	12m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
<b>B00A - R0008 - Home Base - 56.44 m2</b>							
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	57m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
<b>B00A - R0009 - Home Base - 56.36 m2</b>							
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)						
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
<b>B00A - R0010 - Practical Activities - 1hb - 14.23 m2</b>							
Floor Coverings Res/Textile	Vinyl Tiles						
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
<b>B00A - R0011 - Toilets - Boys - 17.95 m2</b>							
Partition Walls (Cubicles)	Compressed AC Sheet	6m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)
<b>B00A - R0012 - Toilets - Girls - 16.76 m2</b>							
Partition Walls (Cubicles)	Compressed AC Sheet	6m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos) , Amosite (brown asbestos)

**B00B - General Learning - 1913 - Timber****Exterior**

Underfloor Voids	Non Accessible Area						
Eaves Linings	Flat AC Sheeting	22m2	North, South, East, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Assumed Asbestos
Ceiling Voids	No Asbestos Found						

**Interior****B00B - R0001 - External Movement - 13.8 m2**

Ceiling Structures/Linings	Flat AC Sheeting	14m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
----------------------------	------------------	------	------------	--------------------	---------	--------------------	-----------------------------

**B00B - R0002 - Home Base - 46.36 m2**

Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						
Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	47m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)

**B00B - R0003 - Practical Activities - 1hb - 4.57 m2**

No Asbestos

**B00B - R0004 - Home Base - 44.73 m2**

Floor Coverings Res/Textile	Vinyl Tiles (Under Floor Covering/Carpet)	45m2	Throughout	Minimal Damage (2)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Floor Coverings Res/Textile	Vinyl Tiles - Adhesive						

**B00B - R0005 - Withdrawal Space - 1hb - 10.19 m2**

No Asbestos

**B00B - R0006 - Movement - 8.31 m2**

No Asbestos

**B00B - R0007 - Home Base Store - 9.79 m2**

No Asbestos

**B00C - Pupil Facilities/Building Services - 1913 - Timber****Exterior**

Ceiling Voids - Flat Roof	No Asbestos Found						
Underfloor Voids	No Asbestos Found						

**Interior****B00C - R0001 - Movement - 9.96 m2**

Ceiling Structures/Linings	Flat AC Sheeting						
----------------------------	------------------	--	--	--	--	--	--

**B00C - R0002 - Canteen - 9.96 m2**

No Asbestos

**B00C - R0003 - Cleaning Supplies - 7.98 m2**

No Asbestos

**B00C - R0004 - Canteen Covered Area - 3.12 m2**

Electrical - Backing Board	Resinous Board	1	West	Good Condition (1)	Low (1)	Low Priority (2-3)	Assumed Asbestos
----------------------------	----------------	---	------	--------------------	---------	--------------------	------------------

**B00D - Library/Staff Facilities - 1913 - Timber****Exterior**

Underfloor Voids	Non Accessible Area						
Eaves Linings	Flat AC Sheeting	18m2	North, South, East, West	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
Ceiling Voids	No Asbestos Found						

**Interior****B00D - R0001 - Interview - 18.17 m2**

Ceiling Structures/Linings	Flat AC Sheeting	4m2	East	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
----------------------------	------------------	-----	------	--------------------	---------	--------------------	-----------------------------

**B00D - R0002 - Movement - 4.44 m2**

Ceiling Structures/Linings	Flat AC Sheeting	5m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
<b>B00D - R0003 - Principal - 12.39 m2</b>							
Ceiling Structures/Linings	Flat AC Sheeting						
<b>B00D - R0004 - Staff Room Annexe - 53.51 m2</b>							
No Asbestos							
<b>B00D - R0005 - Staff Toilet - 1.89 m2</b>							
Floor Coverings Res/Textile	Vinyl Tiles	2m2	Throughout	Good Condition (1)	Low (1)	Low Priority (2-3)	Chrysotile (white asbestos)
<b>B00D - R0006 - General Storeroom - 8.63 m2</b>							
No Asbestos							
<b>B00E - Communal Facilities - 1913 - Timber Shed</b>							
<b>Exterior</b>							
Gable Verge Lining	Flat AC Sheeting						
Ceiling Voids - Raked Ceiling	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
<b>Interior</b>							
<b>B00E - R0001 - Sports Store - 15.58 m2</b>							
No Asbestos							
<b>B00F - Library/General Learning - 2010 - Fibre Cement Clad</b>							
<b>Exterior</b>							
Ceiling Voids	No Asbestos Found						
Underfloor Voids	No Asbestos Found						
<b>Interior</b>							
<b>B00F - R0001 - External Movement - 31.19 m2</b>							
No Asbestos							
<b>B00F - R0002 - Reading Area - 91.95 m2</b>							
No Asbestos							
<b>B00F - R0003 - Library Office/Workroom - 20.47 m2</b>							
No Asbestos							
<b>B00F - R0004 - Communications Room - 8.4 m2</b>							
No Asbestos							
<b>B00F - R0005 - K.L.A. Store - 9.89 m2</b>							
No Asbestos							
<b>B00G - Other - 1997 - Metal Shed</b>							
<b>Exterior</b>							
Ceiling Voids - Raked Ceiling	No Asbestos Found						
Underfloor Voids - Slab on Ground	No Asbestos Found						
<b>Interior</b>							
<b>B00G - R0001 - General Assistant/Bulk Store - 41.3 m2</b>							
No Asbestos							

## Demountables

### OS 603 10305 - Learning Unit - Standard With P.A.A. A/C - Placement Date : 08-OCT-2015

**Note:** This refurbished demountable may have asbestos present in remnant mastic in window frames.

No Asbestos Found

### OS 837 10469 - Disabled Toilet, Shower Change room - Placement Date : 15-NOV-2018

**Note:** This refurbished demountable may have asbestos present in remnant mastic in window frames.

No Asbestos Found

### OS 840 12740 - Girls Toilet - Placement Date : 26-APR-2016

**Note:** This refurbished demountable may have asbestos present in remnant mastic in window frames.

No Asbestos Found

### OS 810 12929 - FSU/Shelter/Stores - Placement Date : 16-OCT-2017

**Note:** This refurbished demountable may have asbestos present in remnant mastic in window frames.

No Asbestos Found

### OS 606 15076 - Learning Unit - Standard With P.A.A A/C - Placement Date : 15-DEC-2017

**Note:** This refurbished demountable may have asbestos present in remnant mastic in window frames.

No Asbestos Found

### OS 602 15649 - Learning Unit - Standard With P.A.A. - Placement Date : 07-DEC-2015

**Note:** This refurbished demountable may have asbestos present in remnant mastic in window frames.

No Asbestos Found