


Development Consent

Section 4.38 of the Environmental Planning and Assessment Act 1979

As delegate of the Minister for Planning and Public Spaces under delegation executed on 9 March 2020, I approve the Development Application referred to in Schedule 1, subject to the conditions specified in Schedule 2.

These conditions are required to:

- prevent, minimise, or offset adverse environmental impacts;
- set standards and performance measures for acceptable environmental performance;
- require regular monitoring and reporting; and
- provide for the ongoing environmental management of the development.



Erica van den Honert
A/Executive Director
Infrastructure Assessments

Sydney

30 November 2020

SCHEDULE 1

Application Number:	SSD 9483
Applicant:	NSW Department of Education
Consent Authority:	Minister for Planning and Public Spaces
Site:	5 Centennial Avenue and 24 Centennial Avenue, Chatswood Lot 1 DP 812207, Lot 2 DP 812207, Lot C DP 346499, Lot 1 DP 725204, Lots 20-23, Section 6 in DP 2273, Lots 18-21, Section 7 DP 2273, Lots 16-20, Section 8, DP 2271
Development:	Redevelopment of Chatswood Public School and Chatswood High School comprising demolition of selected buildings and construction of new buildings, refurbishment of existing buildings, changes to vehicular access and car parking, tree removal, landscaping, earthworks and site remediation.

DEFINITIONS

Aboriginal object	Has the same meaning as the definition of the term in section 5 of the <i>National Parks and Wildlife Act 1974</i>
Aboriginal place	Has the same meaning as the definition of the term in section 5 of the <i>National Parks and Wildlife Act 1974</i>
Accredited Certifier	Means the holder of accreditation as an accredited certifier under the <i>Building Professionals Act 2005</i> acting in relation to matters to which the accreditation applies.
Advisory Notes	Advisory information relating to the consent but do not form a part of this consent
Applicant	NSW Department of Education or any other person carrying out any development to which this consent applies
Approved disturbance area	The area identified as such on the development layout
Archaeological Salvage	A program of salvage excavation/s to recover information and/or objects from identified archaeological sites
BCA	Building Code of Australia
BC Act	<i>Biodiversity Conservation Act 2016</i>
CEMP	Construction Environmental Management Plan
Certification of Crown building work	Certification under section 6.28(2) of the EP&A Act
Certified Contaminated Land Consultant	A person certified in accordance with the requirements of the Contaminated Land Consultant Certification Policy Version 2 (EPA November 2017) or any subsequent policies as in force from time to time
Certifier	Means a council or accredited certifier or in the case of Crown development, a person qualified to conduct a Certification of Crown Building work
Compliance Reporting Post Approval Requirements	Compliance Reporting Post Approval Requirements as available on the Department's website
Conditions of this consent	The conditions contained in Schedule 2 of this document
Construction	<p>All physical work to enable operation including (unless specifically excluded by a condition) but not limited to the demolition and removal of buildings, the carrying out of works for the purposes of the development, including bulk earthworks, and erection of buildings and other infrastructure permitted by this consent, but excluding the following:</p> <ul style="list-style-type: none"> • building and road dilapidation surveys; • investigative drilling or investigative excavation; • Archaeological Salvage; • establishing temporary site offices (in locations identified by the conditions of this consent); • installation of environmental impact mitigation measures, fencing, enabling works; and • minor adjustments to services or utilities. <p>However, where heritage items, or threatened species or threatened ecological communities (within the meaning of the <i>Biodiversity Conservation Act 2016</i> or <i>Environment Protection and Biodiversity Conservation Act 1999</i>) are affected or potentially affected by any physical work, that work is construction, unless otherwise determined by the Planning Secretary in consultation with EES Group or DPIE Fisheries (in the case of impact upon fish, aquatic invertebrates or marine vegetation)</p>

Council	Willoughby City Council
Day	The period from 7am to 6pm on Monday to Saturday, and 8am to 6pm on Sundays and Public Holidays
Demolition	The deconstruction and removal of buildings, sheds and other structures on the site
Department	NSW Department of Planning, Industry and Environment
Development	The development described in the EIS and Response to Submissions, including the works and activities comprising the redevelopment of Chatswood Public School and Chatswood High School, as modified by the conditions of this consent
Earthworks	Bulk earthworks, site levelling, import and compaction of fill material, excavation for installation of drainage and services
EES Group	Environment, Energy and Science Group of the Department of Planning, Industry and Environment (Former Office of Environment and Heritage)
EIS	The Environmental Impact Statement titled 'Upgrades to Chatswood Public School and Chatswood High School', prepared by DFP dated 23 March 2020, submitted with the application for consent for the development, including any additional information provided by the Applicant in support of the application
ENM	Excavated Natural Material
Environment	Includes all aspects of the surroundings of humans, whether affecting any human as an individual or in his or her social groupings
EPA	NSW Environment Protection Authority
EP&A Act	<i>Environmental Planning and Assessment Act 1979</i>
EP&A Regulation	<i>Environmental Planning and Assessment Regulation 2000</i>
EPL	Environment Protection Licence under the POEO Act
Evening	The period from 6pm to 10pm
Feasible	Means what is possible and practical in the circumstances
Heritage	Encompasses both Aboriginal and historic heritage including sites that predate European settlement, and a shared history since European settlement
Heritage NSW	Heritage, Community Engagement of the Department of Premier and Cabinet
Heritage Item	An item as defined under the <i>Heritage Act 1977</i> , and assessed as being of local, State and/ or National heritage significance, and/or an Aboriginal Object or Aboriginal Place as defined under the <i>National Parks and Wildlife Act 1974</i> , the World Heritage List, or the National Heritage List or Commonwealth Heritage List under the <i>Environment Protection and Biodiversity Conservation Act 1999</i> (Cth), or anything identified as a heritage item under the conditions of this consent
IBRA	Interim Biogeographic Regionalisation for Australia
Incident	An occurrence or set of circumstances that causes, or threatens to cause, material harm and which may or may not be, or cause, a non-compliance <i>Note: "material harm" is defined in this consent</i>
Independent Audit Post Approval Requirements	Independent Audit Post Approval Requirements as available on the Department's website
Land	Has the same meaning as the definition of the term in section 1.4 of the EP&A Act
EMP	Environmental Management Plan

Management and mitigation measures	The management and mitigation measures set out in Appendix 3 of the EIS
Material harm	Is harm that: <ul style="list-style-type: none"> a) involves actual or potential harm to the health or safety of human beings or to the environment that is not trivial; or b) results in actual or potential loss or property damage of an amount, or amounts in aggregate, exceeding \$10,000, (such loss includes the reasonable costs and expenses that would be incurred in taking all reasonable and practicable measures to prevent, mitigate or make good harm to the environment)
Minister	NSW Minister for Planning and Public Spaces (or delegate)
Mitigation	Activities associated with reducing the impacts of the development prior to or during those impacts occurring
Monitoring	Any monitoring required under this consent must be undertaken in accordance with section 9.39 of the EP&A Act
Night	The period from 10pm to 7am on Monday to Saturday, and 10pm to 8am on Sundays and Public Holidays
Non-compliance	An occurrence, set of circumstances or development that is a breach of this consent
OSD	On site detention
Operation	The carrying out of the approved purpose of the development upon completion of construction excluding operational readiness work
Operational readiness work	Use of the completed areas of the site by school staff to prepare for the operation of the school
PSD	Permitted site discharge
Planning Secretary	Planning Secretary under the EP&A Act, or nominee
POEO Act	<i>Protection of the Environment Operations Act 1997</i>
Reasonable	Means applying judgement in arriving at a decision, taking into account: mitigation, benefits, costs of mitigation versus benefits provided, community views, and the nature and extent of potential improvements
Registered Aboriginal Parties	Means the Aboriginal persons identified in accordance with the document entitled " <i>Aboriginal cultural heritage consultation requirements for proponents 2010</i> " (DECCW)
Rehabilitation	The restoration of land disturbed by the development to a good condition, to ensure it is safe, stable and non-polluting
Response to submissions	The Applicant's response to issues raised in submissions received in relation to the application for consent for the development under the EP&A Act
Sensitive receivers	A location where people are likely to work, occupy or reside, including a dwelling, school, hospital, office or public recreational area
Site	The land defined in Schedule 1
Site Auditor	As defined in section 4 of the <i>Contaminated Land Management Act 1997</i>
Site Audit Report	As defined in section 4 of the <i>Contaminated Land Management Act 1997</i>
Site Audit Statement	As defined in section 4 of the <i>Contaminated Land Management Act 1997</i>
TfNSW	Transport for New South Wales
VENM	Virgin Excavated Natural Material
Waste	Has the same meaning as the definition of the term in the Dictionary to the POEO Act
Year	A period of 12 consecutive months

SCHEDULE 2
PART A ADMINISTRATIVE CONDITIONS

Obligation to Minimise Harm to the Environment

- A1. In addition to meeting the specific performance measures and criteria in this consent, all reasonable and feasible measures must be implemented to prevent, and, if prevention is not reasonable and feasible, minimise any material harm to the environment that may result from the construction and operation of the development.

Terms of Consent

- A2. The development may only be carried out:
- (a) in compliance with the conditions of this consent;
 - (b) in accordance with all written directions of the Planning Secretary;
 - (c) generally in accordance with the EIS and Response to Submissions;
 - (d) in accordance with the approved plans in the table below:

Architectural drawings prepared by Architectus			
Dwg No.	Rev	Name of Plan	Date
DA-AX-A0010	E	SSDA - Existing Site Plan	27/02/2020
DA-AX-A0032	E	SSDA - Proposed Site Plan	12/11/2020
DA-AX-A0050	E	SSDA - Lower Ground 2	12/11/2020
DA-AX-A0051	E	SSDA - Lower Ground 1	12/11/2020
DA-AX-A0052	E	SSDA - Ground Floor	12/11/2020
DA-AX-A0053	E	SSDA - Level 1	12/11/2020
DA-AX-A0054	E	SSDA - Level 2	12/11/2020
DA-AX-A0055	D	SSDA - Level 3	12/11/2020
DA-AX-A2000	E	Centennial Avenue - Street Elevations	12/11/2020
DA-AX-A2010	D	Centennial Avenue - Site Sections	12/11/2020
DA-AX-A2011	D	Centennial Avenue - Site Sections	12/11/2020
DA-AQ-A2000	D	Building Q – Elevations – Sheet 1	12/11/2020
DA-AQ-A2001	D	Building Q – Elevations – Sheet 2	12/11/2020
DA-AQ-A2100	C	Building Q – Sections – Sheet 1	12/11/2020
DA-AQ-A2101	C	Building Q – Sections – Sheet 2	12/11/2020
DA-AS-A2000	E	Building S - Elevations - Sheet 1	12/11/2020
DA-AS-A2001	E	Building S - Elevations - Sheet 2	12/11/2020
DA-AS-A2100	D	Building S - Section A - Sheet 1	12/11/2020
DA-AS-A2101	D	Building S - Section B & C - Sheet 2	12/11/2020
DA-AT-A2002	C	Building T Elevations	12/11/2020
DA-AT-A2011	C	Building T Sections	12/11/2020
DA-BX-A0010	D	Existing Site Plan	11/03/2020
DA-BX-A0021	A	Site Demolition Plan	11/03/2020
DA-BX-A0030	H	Site Plan Proposed (Final)	20/11/2020
DA-BX-A0042	F	SSDA - Lower Ground Floor 2	12/11/2020
DA-BX-A0043	F	SSDA - Lower Ground Floor 1	12/11/2020
DA-BX-A0044	F	SSDA - Ground Floor	12/11/2020
DA-BX-A0045	F	SSDA - Level 1	20/11/2020

DA-BX-A0046	F	SSDA - Level 2	20/11/2020
DA-BX-A0047	F	SSDA - Level 3	20/11/2020
DA-BX-A0048	F	SSDA - Level 4	20/11/2020
DA-BX-A0049	G	SSDA - Roof	20/11/2020
DA-BX-A2000	H	Street Elevations	20/11/2020
DA-BX-A2010	E	Site Sections	12/11/2020
DA-BG-A2002	C	Building G - Elevations	1/10/2020
DA-BG-A2011	C	Building G - Sections	1/10/2020
DA-BP-A1113	D	Building P1 + P2 Elevations	1/10/2020
DA-BP-A1114	D	Building P1 + P2 Elevations	1/10/2020
DA-BP-A1115	D	Building P1 + P2 Elevations	1/10/2020
DA-BP-A1116	D	Building P1 + P2 Sections	1/10/2020
Landscape plans prepared by Oculus			
Dwg No.	Rev	Name of Plan	Date
SD-XX-L0001	P3	Site Plan	11/11/2020
SD-XX-L0002	P3	Legend & Material Schedule	11/11/2020
SD-XX-L0003	P3	Material Schedule	11/11/2020
SD-XX-L0004	P3	Master Plant Schedule	11/11/2020
SD-AX-L0501	P3	Tree Retention & Removal Plan	11/11/2020
SD-AX-L0502	P3	Tree Retention & Removal Plan	11/11/2020
SD-AX-L0503	P3	Tree Retention & Removal Plan	11/11/2020
SD-AX-L0504	P3	Tree Retention & Removal Plan	11/11/2020
SD-AX-L1001	P3	Surface Finishes and Materials	11/11/2020
SD-AX-L1002	P3	Surface Finishes and Materials	11/11/2020
SD-AX-L1003	P3	Surface Finishes and Materials	11/11/2020
SD-AX-L1004	P3	Surface Finishes and Materials	11/11/2020
SD-AX-L1301	P3	Grading Plan	11/11/2020
SD-AX-L1302	P3	Grading Plan	11/11/2020
SD-AX-L1303	P3	Grading Plan	11/11/2020
SD-AX-L1304	P3	Grading Plan	11/11/2020
SD-AX-L1501	P3	Planting Plan	11/11/2020
SD-AX-L1502	P3	Planting Plan	11/11/2020
SD-AX-L1503	P3	Planting Plan	11/11/2020
SD-AX-L1504	P3	Planting Plan	11/11/2020
SD-AX-L1701	P3	Fencing & Gates Plan	20/11/2020
SD-AX-L2000	P3	Sections & Elevations	11/11/2020
SD-AX-L2001	P3	Sections & Elevations	11/11/2020
SD-AX-L2002	P3	Sections & Elevations	11/11/2020
SD-BX-L0500	P4	Tree Retention & Removal Plan	20/11/2020
SD-BX-L1001	P4	Surface Finishes Lower Ground 2	11/11/2020
SD-BX-L1002	P4	Surface Finishes and Finishes Lower Ground 1	11/11/2020
SD-BX-L1003	P5	Surface Finishes and Materials Upper Ground	20/11/2020
SD-BX-L1004	P1	Surface Finishes and Materials – Building P2 L4	11/11/2020

SD-BX-L1301	P4	Grading Plan Lower Ground LG2	11/11/2020
SD-BX-L1302	P4	Grading Plan Lower Ground LG1	11/11/2020
SD-BX-L1303	P5	Grading Plan Upper Ground	20/11/2020
SD-BX-L1304	P1	Grading Plan Building P2 – Level 4	11/11/2020
SD-BX-L1501	P4	Planting Plan Lower Ground LG2	11/11/2020
SD-BX-L1502	P4	Planting Plan Lower Ground LG1	11/11/2020
SD-BX-L1503	P5	Planting Plan Upper Ground	20/11/2020
SD-BX-L1504	P1	Planting Plan Building P2 – Level 4	11/11/2020
SD-BX-L1701	P3	Fencing & Gates Plan	20/11/2020
SD-BX-L2000	P3	Sections & Elevations	11/11/2020
SD-BX-L2001	P3	Sections & Elevations	11/11/2020
DA-6000	A	Sections & Elevations Building P1	17/09/2020

- A3. Consistent with the requirements in this consent, the Planning Secretary may make written directions to the Applicant in relation to:
- the content of any strategy, study, system, plan, program, review, audit, notification, report or correspondence submitted under or otherwise made in relation to this consent, including those that are required to be, and have been, approved by the Planning Secretary;
 - any reports, reviews or audits commissioned by the Planning Secretary regarding compliance with this approval; and
 - the implementation of any actions or measures contained in any such document referred to in (a) above.
- A4. The conditions of this consent and directions of the Planning Secretary prevail to the extent of any inconsistency, ambiguity or conflict between them and a document listed in condition A2(c). In the event of an inconsistency, ambiguity or conflict between any of the documents listed in condition A2(c), the most recent document prevails to the extent of the inconsistency, ambiguity or conflict.

Limits of Consent

- A5. This consent lapses five years after the date of consent unless work is physically commenced.

Prescribed Conditions

- A6. The Applicant must comply with all relevant prescribed conditions of development consent under Part 6, Division 8A of the EP&A Regulation.

Planning Secretary as Moderator

- A7. In the event of a dispute between the Applicant and a public authority, in relation to an applicable requirement in this approval or relevant matter relating to the Development, either party may refer the matter to the Planning Secretary for resolution. The Planning Secretary's resolution of the matter must be binding on the parties.

Evidence of Consultation

- A8. Where conditions of this consent require consultation with an identified party, the Applicant must:
- consult with the relevant party prior to submitting the subject document for information or approval; and
 - provide details of the consultation undertaken including:
 - the outcome of that consultation, matters resolved and unresolved; and
 - details of any disagreement remaining between the party consulted and the Applicant and how the Applicant has addressed the matters not resolved.

Staging

- A9. The project may be constructed and operated in stages. Where compliance with conditions is required to be staged due to staged construction or operation, a Staging Report (for either or both construction and operation as the case may be) must be prepared and submitted to the satisfaction of the Planning Secretary. The Staging Report must be submitted to the Planning Secretary no later than one month before the commencement of construction of the first of the proposed stages of construction (or if only staged operation is proposed, one month before the commencement of operation of the first of the proposed stages of operation) unless otherwise approved by the Planning Secretary.

Note: Works may commence upon the Planning Secretary's approval of a Staging Report and satisfaction of all relevant conditions.

- A10. A Staging Report prepared in accordance with condition A9 must:
- (a) if staged construction is proposed, set out how the construction of the whole of the project will be staged, including details of work and other activities to be carried out in each stage and the general timing of when construction of each stage will commence and finish;
 - (b) if staged operation is proposed, set out how the operation of the whole of the project will be staged, including details of work and other activities to be carried out in each stage and the general timing of when operation of each stage will commence and finish (if relevant);
 - (c) specify how compliance with conditions will be achieved across and between each of the stages of the project; and
 - (d) set out mechanisms for managing any cumulative impacts arising from the proposed staging.
- A11. Where a Staging Report is required, the project must be staged in accordance with the Staging Report, as approved by the Planning Secretary.
- A12. Where construction or operation is being staged in accordance with a Staging Report, the terms of this consent that apply or are relevant to the works or activities to be carried out in a specific stage must be complied with at the relevant time for that stage as identified in the Staging Report.

Staging, Combining and Updating Strategies, Plans or Programs

- A13. The Applicant may:
- (a) prepare and submit any strategy, plan (including management plan, architectural or design plan) or program required by this consent on a staged basis (if a clear description is provided as to the specific stage and scope of the development to which the strategy, plan (including management plan, architectural or design plan) or program applies, the relationship of the stage to any future stages and the trigger for updating the strategy, plan (including management plan, architectural or design plan) or program);
 - (b) combine any strategy, plan (including management plan, architectural or design plan), or program required by this consent (if a clear relationship is demonstrated between the strategies, plans (including management plan, architectural or design plan) or programs that are proposed to be combined); and
 - (c) update any strategy, plan (including management plan, architectural or design plan), or program required by this consent (to ensure the strategies, plans (including management plan, architectural or design plan), or programs required under this consent are updated on a regular basis and incorporate additional measures or amendments to improve the environmental performance of the development).
- A14. Any strategy, plan or program prepared in accordance with condition A13, where previously approved by the Planning Secretary under this consent, must be submitted to the satisfaction of the Planning Secretary.
- A15. If the Planning Secretary agrees, a strategy, plan (including management plan, architectural or design plan), or program may be staged or updated without consultation being undertaken with all parties required to be consulted in the relevant condition in this consent.

- A16. Updated strategies, plans (including management plan, architectural or design plan), or programs supersede the previous versions of them and must be implemented in accordance with the condition that requires the strategy, plan, program or drawing.

Structural Adequacy

- A17. All new buildings and structures, and any alterations or additions to existing buildings and structures, that are part of the development, must be constructed in accordance with the relevant requirements of the BCA.

Note: Part 8 of the EP&A Regulation sets out the requirements for the certification of the development.

External Walls and Cladding

- A18. The external walls of all buildings including additions to existing buildings must comply with the relevant requirements of the BCA.

Applicability of Guidelines

- A19. References in the conditions of this consent to any guideline, protocol, Australian Standard or policy are to such guidelines, protocols, Standards or policies in the form they are in as at the date of this consent.
- A20. Consistent with the conditions of this consent and without altering any limits or criteria in this consent, the Planning Secretary may, when issuing directions under this consent in respect of ongoing monitoring and management obligations, require compliance with an updated or revised version of such a guideline, protocol, Standard or policy, or a replacement of them.

Monitoring and Environmental Audits

- A21. Any condition of this consent that requires the carrying out of monitoring or an environmental audit, whether directly or by way of a plan, strategy or program, is taken to be a condition requiring monitoring or an environmental audit under Division 9.4 of Part 9 of the EP&A Act. This includes conditions in respect of incident notification, reporting and response, non-compliance notification, Site audit report and independent auditing.

Note: For the purposes of this condition, as set out in the EP&A Act, "monitoring" is monitoring of the development to provide data on compliance with the consent or on the environmental impact of the development, and an "environmental audit" is a periodic or particular documented evaluation of the development to provide information on compliance with the consent or the environmental management or impact of the development.

Access to Information

- A22. At least 48 hours before the commencement of construction until the completion of all works under this consent, or such other time as agreed by the Planning Secretary, the Applicant must:
- (a) make the following information and documents (as they are obtained or approved) publicly available on its website:
 - (i) the documents referred to in condition A2 of this consent;
 - (ii) all current statutory approvals for the development;
 - (iii) all approved strategies, plans and programs required under the conditions of this consent;
 - (iv) regular reporting on the environmental performance of the development in accordance with the reporting arrangements in any plans or programs approved under the conditions of this consent;
 - (v) a comprehensive summary of the monitoring results of the development, reported in accordance with the specifications in any conditions of this consent, or any approved plans and programs;
 - (vi) a summary of the current stage and progress of the development;
 - (vii) contact details to enquire about the development or to make a complaint;
 - (viii) a complaints register, updated monthly;
 - (ix) audit reports prepared as part of any independent audit of the development and the Applicant's response to the recommendations in any audit report;
 - (x) any other matter required by the Planning Secretary; and
 - (b) keep such information up to date, to the satisfaction of the Planning Secretary and publicly available for 12 months after the commencement of operations.

Compliance

- A23. The Applicant must ensure that all of its employees, contractors (and their sub-contractors) are made aware of, and are instructed to comply with, the conditions of this consent relevant to activities they carry out in respect of the development.

Incident Notification, Reporting and Response

- A24. The Planning Secretary must be notified through the major projects portal immediately after the Applicant becomes aware of an incident. The notification must identify the development (including the development application number and the name of the development if it has one), and set out the location and nature of the incident.
- A25. Subsequent notification must be given and reports submitted in accordance with the requirements set out in **Appendix 2**.

Non-Compliance Notification

- A26. The Planning Secretary must be notified through the major projects portal within seven days after the Applicant becomes aware of any non-compliance. The Certifier must also notify the Planning Secretary through the major projects portal within seven days after they identify any non-compliance.
- A27. The notification must identify the development and the application number for it, set out the condition of consent that the development is non-compliant with, the way in which it does not comply and the reasons for the non-compliance (if known) and what actions have been, or will be, undertaken to address the non-compliance.
- A28. A non-compliance which has been notified as an incident does not need to also be notified as a non-compliance.

Revision of Strategies, Plans and Programs

- A29. Within three months of:
- the submission of a compliance report under condition A32;
 - the submission of an incident report under condition A25;
 - the submission of an Independent Audit under condition C41 or C42;
 - the approval of any modification of the conditions of this consent; or
 - the issue of a direction of the Planning Secretary under condition A2 which requires a review,
- the strategies, plans and programs required under this consent must be reviewed, and the Planning Secretary and the Certifier must be notified in writing that a review is being carried out.
- A30. If necessary to either improve the environmental performance of the development, cater for a modification or comply with a direction, the strategies, plans, programs or drawings required under this consent must be revised, to the satisfaction of the Planning Secretary and Certifier (where previously approved by the Certifier). Where revisions are required, the revised document must be submitted to the Planning Secretary and Certifier for approval and information (where relevant) within six weeks of the review.

Note: This is to ensure strategies, plans and programs are updated on a regular basis and to incorporate any recommended measures to improve the environmental performance of the development.

Compliance Reporting

- A31. Compliance Reports of the project must be carried out in accordance with the Compliance Reporting Post Approval Requirements.
- A32. Compliance Reports must be submitted to the Department in accordance with the timeframes set out in the Compliance Reporting Post Approval Requirements, unless otherwise agreed by the Planning Secretary.
- A33. The Applicant must make each Compliance Report publicly available within 60 days of submitting it to the Planning Secretary.
- A34. Notwithstanding the requirements of the Compliance Reporting Post Approval Requirements, the Planning Secretary may approve a request for ongoing annual operational compliance

reports to be ceased, where it has been demonstrated to the Planning Secretary's satisfaction that an operational compliance report has demonstrated operational compliance.

PART B PRIOR TO COMMENCEMENT OF CONSTRUCTION

Improvements to Public School Residential Boundary Interface

- B1. Prior to the commencement of construction of Buildings P1 and P2, the Applicant must:
- (a) consult with the landowners of 1 James Street, 2 James Street, 1 Jenkins Street and 3 Jenkins Street, Chatswood about providing improvements to their private open space in order to mitigate any visual impacts from the new buildings; and
 - (b) if the relevant landowner/s agrees for improvement works to be carried out on their property, the Applicant must prepare landscape plans including ongoing maintenance instructions prepared by a suitably qualified person; and
 - (c) document the consultation strategy with the subject landowners in the Community Communication Strategy required under condition B14.
- B2. The improvement works detailed in condition B1 are limited to feasible and reasonable landscaping and fencing. Costs associated with providing these improvement works are to be borne by the Applicant. The landowner/s are responsible for any ongoing maintenance requirements (including any ongoing maintenance costs) of the improvement works.
- B3. Prior to the occupation of Buildings P1 and P2, the Applicant must submit evidence that condition B1 has been complied with to the Planning Secretary for approval.

Notification of Commencement

- B4. The Applicant must notify the Planning Secretary in writing of the dates of the intended commencement of construction and operation at least 48 hours before those dates.
- B5. If the construction or operation of the development is to be staged, the Planning Secretary must be notified in writing at least 48 hours before the commencement of each stage, of the date of commencement and the development to be carried out in that stage.

Certified Drawings

- B6. Prior to the commencement of construction (excluding earthworks and demolition), the Applicant must submit to the satisfaction of the Certifier structural drawings prepared and signed by a suitably qualified practising Structural Engineer that demonstrates compliance with this development consent.

External materials and finishes

- B7. Prior to the commencement of construction (excluding earthworks and demolition), a schedule of external materials and finishes of all new buildings must be submitted to the Certifier and comply with the following:
- (a) all external materials colours and finishes are to be predominantly neutral, recessive colours appropriate to the character of the area and compatible with the heritage listed items within the site and in the vicinity; and
 - (b) all external building materials and finishes must reflect the appearance of the buildings shown in the renders included in the renders of Appendix 2 of the EIS and Attachment 2 of the Response to Submissions.

External Walls and Cladding

- B8. Prior to the installation of external walls and cladding, the Applicant must provide the Certifier with documented evidence that the products and systems proposed for use or used in the construction of external walls, including finishes and claddings such as synthetic or aluminium composite panels, comply with the requirements of the BCA. The Applicant must provide a copy of the documentation given to the Certifier to the Planning Secretary within seven days after the Certifier accepts it.

Heritage Photographic Survey

- B9. Prior to commencement of construction, a photographic survey of the Chatswood Primary School is to be lodged with Council for its historical archives. The photographic survey is to be submitted in a report format, and must include:
- (a) a front cover marked with:

- (i) the name/location of the property;
 - (ii) the date of the survey; and
 - (iii) the name of the company or persons responsible for the survey.
- (b) a layout plan of the existing buildings and site which identifies rooms and features shown in the photographs.
- (c) photographs of the interior, exterior, grounds and a streetscape view of the buildings, labelled to indicate their location in relation to the layout plan. Photographic records of each elevation, each room and any architectural/ decorative features or finishes are to be included. Where colour is a feature of the building (for example, the building features stained glass, leadlight or polychrome brickwork), additional colour photographs are to be included in the photographic survey report.

B10. Prior to the commencement of construction, documentary evidence from the Applicant confirming lodgement of the heritage photographic survey to Council is to be provided to the Certifier.

Internal Noise Levels and Ventilation

- B11. Prior to commencement of construction (excluding earthworks and demolition), the Applicant must provide evidence to the Certifier that the proposed building design:
- (a) complies with specified internal noise criteria and recommended acoustic attenuation measures contained in the Acoustic Assessment Report (Ref: 6698-1.1R Rev A), dated 10 March 2020 and prepared by Day Design with certification provided by a suitably qualified acoustic consultant;
 - (b) incorporates the installation of air conditioning systems with fresh air supply to classrooms that require doors and windows to be closed to achieve the internal noise criteria; and
 - (c) certification by a suitably qualified person that all mechanical ventilation and exhaust systems comply with the National Construction Code including:
 - (i) AS1668.1, AS1668.2 and AS3666.1 as applicable, and/or
 - (ii) an alternative solution using an appropriate assessment method.

Protection of Public Infrastructure

- B12. Prior to the commencement of construction, the Applicant must:
- (a) consult with the relevant owner and provider of services that are likely to be affected by the development to make suitable arrangements for access to, diversion, protection and support of the affected infrastructure;
 - (b) prepare a dilapidation report identifying the condition of all public infrastructure in the vicinity of the site (including roads, gutters and footpaths); and
 - (c) submit a copy of the dilapidation report to the Planning Secretary, Certifier and Council.

Pre-Construction Dilapidation Report

B13. Prior to the commencement of construction, the Applicant must submit a pre-commencement dilapidation report to Council and the Certifier. The report must provide an accurate record of the existing condition of adjoining private properties, retaining walls, heritage items and Council assets that are likely to be impacted by the proposed works.

Community Communication Strategy

B14. No later than 48 hours before the commencement of construction, a Community Communication Strategy must be submitted to the Planning Secretary for information. The Community Communication Strategy must provide mechanisms to facilitate communication between the Applicant, Council and the community (including adjoining affected landowners and businesses, and others directly impacted by the development), during the design and construction of the development and for a minimum of 12 months following the completion of construction.

The Community Communication Strategy must:

- (a) identify people to be consulted during the design and construction phases;

- (b) set out procedures and mechanisms for the regular distribution of accessible information about or relevant to the development;
- (c) provide for the formation of community-based forums, if required, that focus on key environmental management issues for the development;
- (d) set out procedures and mechanisms:
 - (i) through which the community can discuss or provide feedback to the Applicant;
 - (ii) through which the Applicant will respond to enquiries or feedback from the community; and
 - (iii) to resolve any issues and mediate any disputes that may arise in relation to construction and operation of the development, including disputes regarding rectification or compensation.

Ecologically Sustainable Development

- B15. Prior to the commencement of construction, unless otherwise agreed by the Planning Secretary, the Applicant must demonstrate that ESD is being achieved by either:
- (a) registering for a minimum 4 star Green Star rating with the Green Building Council Australia and submit evidence of registration to the Certifier; or
 - (b) seeking approval from the Planning Secretary for an alternative certification process.

Outdoor Lighting

- B16. Prior to commencement of lighting installation, evidence must be submitted to the satisfaction of the Certifier that all outdoor lighting within the site has been designed to comply with AS 1158.3.1:2005 Lighting for roads and public spaces – Pedestrian area (Category P) lighting – Performance and design requirements and AS 4282-2019 Control of the obtrusive effects of outdoor lighting.

Demolition

- B17. Prior to the commencement of demolition, demolition work plans required by *AS 2601-2001 The demolition of structures* (Standards Australia, 2001) must be accompanied by a written statement from a suitably qualified person that the proposals contained in the work plan comply with the safety requirements of the Standard. The work plans and the statement of compliance must be submitted to the Certifier and Planning Secretary.

Environmental Management Plan Requirements

- B18. Management plans required under this consent must be prepared having regard to the relevant guidelines, including but not limited to the *Environmental Management Plan Guideline: Guideline for Infrastructure Projects* (DPIE April 2020).

Note:

- *The Environmental Management Plan Guideline is available on the Planning Portal at: <https://www.planningportal.nsw.gov.au/major-projects/assessment/post-approval>*
- *The Planning Secretary may waive some of these requirements if they are unnecessary or unwarranted for particular management plans.*

Construction Environmental Management Plan

- B19. Prior to the commencement of construction, the Applicant must submit a Construction Environmental Management Plan (CEMP) to the Certifier and provide a copy to the Planning Secretary for information. The CEMP must include, but not be limited to, the following:

- (a) Details of:
 - (i) hours of work;
 - (ii) 24-hour contact details of site manager;
 - (iii) management of dust and odour to protect the amenity of the neighbourhood;
 - (iv) external lighting in compliance with AS 4282-2019 Control of the obtrusive effects of outdoor lighting;
 - (v) community consultation and complaints handling as set out in the Community Communication Strategy required by condition B14;

- (b) an unexpected finds protocol for contamination and associated communications procedure to ensure that potentially contaminated material is appropriately managed;
 - (c) an unexpected finds protocol for Aboriginal and non-Aboriginal heritage and associated communications procedure;
 - (d) Construction Traffic and Pedestrian Management Sub-Plan (see condition B20);
 - (e) Construction Noise and Vibration Management Sub-Plan (see condition B21); and
 - (f) Construction Soil and Water Management Sub-Plan (see condition B23).
- B20. The Construction Traffic and Pedestrian Management Sub-Plan (CTPMSP) must be prepared to achieve the objective of ensuring safety and efficiency of the road network and address, but not be limited to, the following:
- (a) be prepared by a suitably qualified and experienced person(s);
 - (b) be prepared in consultation with Council and TfNSW;
 - (c) detail the measures that are to be implemented to ensure road safety and network efficiency during construction in consideration of potential impacts on general traffic, cyclists and pedestrians and bus services;
 - (d) detail heavy vehicle routes, access and parking arrangements;
 - (e) implement a public information campaign to inform the community of any road changes well in advance of the changes;
 - (f) confine temporary road closures to weekends and off-peak hour times;
 - (g) prior to implementation of any road closure during construction, Council must be advised of these changes and a Traffic Control Plan must be submitted to Council for approval;
 - (h) a Traffic Control Plan must include times and dates of changes, signage, road markings and any temporary traffic control measures; and
 - (i) construction access from the Pacific Highway is not permitted unless otherwise approved by TfNSW.
 - (j) a construction zone is not permitted on the Pacific Highway unless otherwise approved by TfNSW.
- B21. The Construction Noise and Vibration Management Sub-Plan must address, but not be limited to, the following:
- (a) be prepared by a suitably qualified and experienced noise expert;
 - (b) describe procedures for achieving the noise management levels in EPA's *Interim Construction Noise Guideline* (DECC, 2009);
 - (c) describe the measures to be implemented to manage high noise generating works such as piling, in close proximity to sensitive receivers;
 - (d) include strategies that have been developed with the community for managing high noise generating works;
 - (e) describe the community consultation undertaken to develop the strategies in condition B21(d);
 - (f) include a complaints management system that would be implemented for the duration of the construction; and
 - (g) include a program to monitor and report on the impacts and environmental performance of the development and the effectiveness of the implemented management measures in accordance with the requirements of condition B18.
- B22. The Construction Waste Management Sub-Plan (CWMSWP) must address, but not be limited to, the procedures for the management of waste including the following:
- (a) the recording of quantities, classification (for materials to be removed) and validation (for materials to remain) of each type of waste generated during construction and proposed use;
 - (b) information regarding the recycling and disposal locations; and

- (c) confirmation of the contamination status of the development areas of the site based on the validation results.
- B23. The Applicant must prepare a Construction Soil and Water Management Sub-Plan (CSWMSP) and the plan must address, but not be limited to the following:
- (a) be prepared by a suitably qualified expert, in consultation with Council;
 - (b) measures to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site;
 - (c) describe all erosion and sediment controls to be implemented during construction, including as a minimum, measures in accordance with the publication *Managing Urban Stormwater: Soils & Construction* (4th edition, Landcom 2004) commonly referred to as the 'Blue Book';
 - (d) provide a plan of how all construction works will be managed in a wet-weather events (i.e. storage of equipment, stabilisation of the Site);
 - (e) detail all off-Site flows from the Site; and
 - (f) describe the measures that must be implemented to manage stormwater and flood flows for small and large sized events, including, but not limited to 1 in 5-year ARI and 1 in 100-year ARI.
- B24. A Driver Code of Conduct must be prepared and communicated by the Applicant to heavy vehicle drivers and must address the following:
- (a) minimise the impacts of earthworks and construction on the local and regional road network;
 - (b) minimise conflicts with other road users;
 - (c) minimise road traffic noise; and
 - (d) ensure truck drivers use specified routes.

Construction and Staff Parking

- B25. Prior to the commencement of construction, the Applicant must submit a Construction Worker and Staff Transportation Strategy to the Planning Secretary for approval. A copy of the Strategy must be provided to the Certifier for information. The Construction Worker and Staff Transportation Strategy must:
- (a) detail the provision of sufficient accessible parking facilities for school staff;
 - (b) include details of other travel arrangements for school staff and construction workers in order to minimise demand for parking in nearby public and residential streets;
 - (c) include measures to prevent construction workers and school staff from parking on the surrounding streets;
 - (d) include details of on-site secure tool storage facilities for overnight use by construction workers at Chatswood Public School and Chatswood High School;
 - (e) include a Complaint Management System for surrounding residents to report issues with school staff and/or construction workers using the local surrounding roads for parking and associated impacts on the availability of on-street parking for residents and visitors. The Complaint Management System must include a Complaints Register to be maintained recording information on all complaints received about construction worker and school staff parking and associated impacts on on-street car parking availability. The Complaint Management System must:
 - (i) include:
 - a 24 hour toll-free telephone number for the registration of complaints;
 - a postal and email address to which written complaints and enquiries may be sent;
 - process of resolving complaints;
 - a mechanism for community members to make enquiries in common community languages in the area; and

- (ii) record the number of complaints received, nature of the complaints and how the complaint was resolved.

Operational Noise – Design of Mechanical Plant and Equipment

- B26. Prior to installation of mechanical plant and equipment:
- a detailed assessment of mechanical plant and equipment must be undertaken by a suitably qualified person demonstrating compliance with the noise criteria as recommended in Table 15 of the Acoustic Assessment Report (Ref: 6698-1.1R Rev A) dated 10 March 2020 and prepared by Day Design; and
 - evidence must be submitted to the Certifier that any noise mitigation recommendations identified in the assessment carried out under (a) have been incorporated into the design to ensure the development will not exceed the noise criteria identified in Table 15 of the Acoustic Assessment Report (Ref: 6698-1.1R Rev A) dated 10 March 2020 and prepared by Day Design.

Biodiversity

- B27. Prior to the commencement of vegetation clearing, the class and number of ecosystem credits in the table below must be retired to offset the residual biodiversity impacts of the development.
- B28. The requirement to retire credits in condition B27 may be satisfied by payment to the Biodiversity Conservation Fund of an amount equivalent to the class and number of ecosystem credits, as calculated by the Biodiversity Offsets Payment Calculator.
- B29. Evidence of the retirement of credits or payment to the Biodiversity Conservation Fund in satisfaction of condition B27 must be provided to the Planning Secretary prior to carrying out development that will impact on biodiversity values.

A PCT as specified below	Ancillary code	Number of Credits	IBRA subregion
PCT 1237: Sydney Blue Gum – Blackbutt – Smooth-barked Apple moist shrubby open forest on shale ridges of the Hornsby Plateau, Sydney Basin Bioregion	Weedy	1	Cumberland
PCT 1237: Sydney Blue Gum – Blackbutt – Smooth-barked Apple moist shrubby open forest on shale ridges of the Hornsby Plateau, Sydney Basin Bioregion	Planted native	5	Cumberland

- B30. Prior to the commencement of development that will impact on biodiversity values, the class and number of species credits in the table below must be retired to offset the residual biodiversity impacts of the development.
- B31. The requirement to retire credits in condition B30 may be satisfied by payment to the Biodiversity Conservation Fund of an amount equivalent to the class and number of species credits, as calculated by the Biodiversity Offsets Payment Calculator.
- B32. Evidence of the retirement of credits or payment to the Biodiversity Conservation Fund in satisfaction of condition B30 must be provided to the Planning Secretary prior to carrying out development that will impact on biodiversity values.

Species credit	Number of Credits	IBRA subregion
Magenta Lilly Pilly (<i>Syzygium paniculatum</i>)	2	Anywhere in NSW

Construction and Demolition Waste Management

- B33. Prior to the commencement of the removal of any waste material from the site, the Applicant must notify the TfNSW Traffic Management Centre of the truck route(s) to be followed by trucks transporting waste material from the site.

Operational Waste Storage and Processing

- B34. Prior to the commencement of construction of waste storage and processing areas, the Applicant must obtain agreement from Council for the design of the operational waste storage area (where waste removal will be undertaken by Council). Where waste removal will be undertaken by a third party, evidence must be provided to the Certifier that the design of the operational waste storage area:
- (a) is constructed using solid non-combustible materials;
 - (b) is designed to ensure the door/gate to the waste storage area is vermin proof and can be openable from both inside and outside the storage area at all times;
 - (c) includes a hot and cold water supply with a hose through a centralised mixing valve;
 - (d) is naturally ventilated or an air handling exhaust system must be in place; and
 - (e) includes signage to clearly describe the types of materials that can be deposited into recycling bins and general garbage bins.

Construction Access arrangements

- B35. Prior to the commencement of construction, evidence of compliance of construction parking and access arrangements with the following requirements must be submitted to the Certifier:
- (a) all vehicles must enter and leave the site in a forward direction;
 - (b) the swept path of the longest construction vehicle entering and exiting the site in association with the new work, as well as manoeuvrability through the site, is in accordance with the latest version of AS 2890.2;
 - (c) the safety of vehicles and pedestrians accessing adjoining properties, where shared vehicle and pedestrian access occurs, has been addressed; and
 - (d) no construction vehicle access is permitted from the Pacific Highway vehicular entrance unless otherwise approved in writing by TfNSW.

Operational Access, Car Parking and Service Vehicle Arrangements

- B36. Prior to the commencement of construction of operational parking and access facilities, evidence of compliance of the design of operational parking and access arrangements with the following requirements must be submitted to the Certifier:
- (a) a minimum of 18 (Chatswood Public School) and 104 (Chatswood High School) on-site car parking spaces for use during operation of the development and designed in accordance with the latest versions of AS 2890.1 and AS 2890.6; and
 - (b) the swept path of the largest service vehicle entering and exiting the site in association with the new work, as well as manoeuvrability through the site, must be in accordance with the latest version of AS 2890.2.

Public Domain Works

- B37. Prior to the commencement of any footpath or public domain works, the Applicant must consult with Council and demonstrate to the Certifier that the streetscape design and treatment meets the requirements of Council including:
- (a) removal of all redundant crossings together with any necessary works to reinstate the footpath, nature strip, kerb and gutter as required; and
 - (b) addressing pedestrian management.

- B38. The Applicant must submit evidence of approval from Council for public domain works to the Certifier.

Site Contamination

- B39. Prior to the commencement of construction, the Applicant must engage a NSW EPA-accredited Site Auditor to provide advice throughout the duration of works to ensure that any work required in relation to soil or groundwater contamination is appropriately managed.

PART C DURING CONSTRUCTION

Site Notice

- C1. A site notice(s):
- (a) must be prominently displayed at the boundaries of the site during construction for the purposes of informing the public of project details including, but not limited to the details of the Builder, Certifier and Structural Engineer is to satisfy the following requirements;
 - (b) minimum dimensions of the notice must measure 841 mm x 594 mm (A1) with any text on the notice to be a minimum of 30-point type size;
 - (c) the notice is to be durable and weatherproof and is to be displayed throughout the works period;
 - (d) the approved hours of work, the name of the site/ project manager, the responsible managing company (if any), its address and 24-hour contact phone number for any inquiries, including construction/ noise complaint must be displayed on the site notice; and
 - (e) the notice(s) is to be mounted at eye level on the perimeter hoardings/fencing and is to state that unauthorised entry to the site is not permitted.

Operation of Plant and Equipment

- C2. All construction plant and equipment used on site must be maintained in a proper and efficient condition and operated in a proper and efficient manner.

Demolition

- C3. Demolition work must comply with the demolition work plans required by *Australian Standard AS 2601-2001 The demolition of structures* (Standards Australia, 2001) and endorsed by a suitably qualified person as required by condition B17.

Construction Hours

- C4. Construction, including the delivery of materials to and from the site, may only be carried out between the following hours:
- (a) between 7am and 6pm, Mondays to Fridays inclusive; and
 - (b) between 8am and 1pm, Saturdays.
- No work may be carried out on Sundays or public holidays.
- C5. Notwithstanding condition C4, provided noise levels do not exceed the existing background noise level plus 5dB, works may also be undertaken during the following hours:
- (a) between 6pm and 7pm, Mondays to Fridays inclusive; and
 - (b) between 1pm and 4pm, Saturdays.
- C6. Construction activities may be undertaken outside of the hours in condition C4 and C5 if required:
- (a) by the Police or a public authority for the delivery of vehicles, plant or materials; or
 - (b) in an emergency to avoid the loss of life, damage to property or to prevent environmental harm; or
 - (c) where the works are inaudible at the nearest sensitive receivers; or
 - (d) where a variation is approved in advance in writing by the Planning Secretary or his nominee if appropriate justification is provided for the works.
- C7. Notification of such construction activities as referenced in condition C6 must be given to affected residents before undertaking the activities or as soon as is practical afterwards.
- C8. Rock breaking, rock hammering, sheet piling, pile driving and similar activities may only be carried out between the following hours:
- (a) 9am to 12pm, Monday to Friday;
 - (b) 2pm to 5pm Monday to Friday; and

- (c) 9am to 12pm, Saturday.

Implementation of Management Plans

- C9. The Applicant must carry out the construction of the development in accordance with the most recent version of the CEMP (including Sub-Plans).

Construction Traffic

- C10. All construction vehicles (excluding site personnel vehicles) are to be contained wholly within the site, except if located in an approved on-street work zone, and vehicles must wholly enter the site or an approved on-street work zone before stopping.

Hoarding Requirements

- C11. The following hoarding requirements must be complied with:
- (a) no third-party advertising is permitted to be displayed on the subject hoarding/ fencing; and
 - (b) the construction site manager must be responsible for the removal of all graffiti from any construction hoardings or the like within the construction area within 48 hours of its application.

No Obstruction of Public Way

- C12. The public way (outside of any approved construction works zone) must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances.

Construction Noise Limits

- C13. The development must be constructed to achieve the construction noise management levels detailed in *the Interim Construction Noise Guideline* (DECC, 2009). All feasible and reasonable noise mitigation measures must be implemented and any activities that could exceed the construction noise management levels must be identified and managed in accordance with the management and mitigation measures identified in the approved Construction Noise and Vibration Management Plan.
- C14. The Applicant must ensure construction vehicles (including concrete agitator trucks) do not arrive at the site or surrounding residential precincts outside of the construction hours of work outlined under condition C4.
- C15. The Applicant must implement, where practicable and without compromising the safety of construction staff or members of the public, the use of 'quackers' to ensure noise impacts on surrounding noise sensitive receivers are minimised.

Vibration Criteria

- C16. Vibration caused by construction at any residence or structure outside the site must be limited to:
- (a) for structural damage, the latest version of *DIN 4150-3 (1992-02) Structural vibration - Effects of vibration on structures* (German Institute for Standardisation, 1999); and
 - (b) for human exposure, the acceptable vibration values set out in the *Environmental Noise Management Assessing Vibration: a technical guideline* (DEC, 2006) (as may be updated or replaced from time to time).
- C17. Vibratory compactors must not be used closer than 30 metres from residential buildings unless vibration monitoring confirms compliance with the vibration criteria specified in condition C16.
- C18. The limits in conditions C16 and C17 apply unless otherwise outlined in a Construction Noise and Vibration Management Plan, approved as part of the CEMP required by condition B21 of this consent.

Tree Protection

- C19. For the duration of the construction works:

- (a) street trees must not be trimmed or removed unless it forms a part of this development consent or prior written approval from Council is obtained or is required in an emergency to avoid the loss of life or damage to property;
- (b) all street trees immediately adjacent to the approved disturbance area / property boundaries must be protected at all times during construction in accordance with Council's tree protection requirements. Any street tree, which is damaged or removed during construction due to an emergency, must be replaced, to the satisfaction of Council;
- (c) all trees on the site that are not approved for removal, including trees 84 and 95, must be suitably protected during construction as per the recommendations of the Arboricultural Impact Assessments (Ref: 18SYD-11012, v5 and 18SYD-11012, v6), dated 6 March and prepared by Eco Logical Australia; and
- (d) if access to the area within any protective barrier is required during the works, it must be carried out under the supervision of a qualified arborist. Alternative tree protection measures must be installed, as required. The removal of tree protection measures, following completion of the works, must be carried out under the supervision of a qualified arborist and must avoid both direct mechanical injury to the structure of the tree and soil compaction within the canopy or the limit of the former protective fencing, whichever is the greater.

Air Quality

C20. The Applicant must take all reasonable steps to minimise dust generated during all works authorised by this consent.

C21. During construction, the Applicant must ensure that:

- (a) exposed surfaces and stockpiles are suppressed by regular watering;
- (b) all trucks entering or leaving the site with loads have their loads covered;
- (c) trucks associated with the development do not track dirt onto the public road network;
- (d) public roads used by these trucks are kept clean; and
- (e) land stabilisation works are carried out progressively on site to minimise exposed surfaces.

Imported Soil

C22. The Applicant must:

- (a) ensure that only VENM, ENM, or other material approved in writing by EPA is brought onto the site;
- (b) keep accurate records of the volume and type of fill to be used; and
- (c) make these records available to the Certifier upon request.

Disposal of Seepage and Stormwater

C23. Adequate provisions must be made to collect and discharge stormwater drainage during construction to the Certifier. The prior written approval of Council must be obtained to connect or discharge site stormwater to Council's stormwater drainage system or street gutter.

Emergency Management

C24. The Applicant must prepare and implement awareness training for employees and contractors, including locations of the assembly points and evacuation routes, for the duration of construction.

Stormwater Management System

C25. Within three months of the commencement of construction, the Applicant must design an operational stormwater management system for the development and submit it to the satisfaction of the Certifier. The system must be designed by a suitably qualified and experienced person(s) and comply with the following:

- (a) comply with applicable Australian Standards and Part C.5 of Willoughby Development Control Plan 2006;

- (b) for the high school site, an on site detention (OSD) system with a minimum volume of 497m³ and permitted site discharge (PSD) of 342L/s, with a catchment area of 1.52ha of impervious area, covering the total area or otherwise to the satisfaction of Council;
- (c) for the public school site, an OSD system with a minimum volume of 356m³ and a PSD of 245L/s, with a catchment area of 1.09ha of impervious area or otherwise to the satisfaction of Council; and
- (d) ensure that the system capacity has been designed in accordance with *Australian Rainfall and Runoff* (Engineers Australia, 2016) and *Managing Urban Stormwater: Council Handbook* (EPA, 1997) guidelines.

C26. Detailed design plans and hydraulic calculations for any changes to the stormwater drainage system on Pacific Highway must be submitted to TfNSW for approval within three months of the commencement of construction.

Note: The documentation must be sent to development.sydney@rms.nsw.gov.au. A plan checking fee will be payable and a performance bond may be required before TfNSW approval is issued.

Road upgrade works

- C27. Within three months of commencement of construction, the Applicant must commence consultation with Council about the installation of roundabout(s) or other road upgrade works on Centennial Avenue (at the intersection of Jenkins Street and/or Edgar Street) in order to improve the safety and efficiency of drop-off/pick-up vehicle movements.
- C28. If following consultation required by condition C27, the installation of roundabout(s) or other road upgrade works is deemed necessary by Council, plans and specifications to Council's requirements of the roundabout(s) must be submitted to Council for approval prior to the installation of the roundabout or other road upgrade works.

Unexpected Finds Protocol – Aboriginal Heritage

- C29. In the event that surface disturbance identifies a new Aboriginal object, all works must halt in the immediate area to prevent any further impacts to the object(s). A suitably qualified archaeologist and the registered Aboriginal representatives must be contacted to determine the significance of the objects. The site is to be registered in the Aboriginal Heritage Information Management System (AHIMS) which is managed by Heritage NSW and the management outcome for the site included in the information provided to AHIMS. The Applicant must consult with the Aboriginal community representatives, the archaeologists and Heritage NSW to develop and implement management strategies for all objects/sites. Works shall only recommence with the written approval of Heritage NSW.

Unexpected Finds Protocol – Historic Heritage

- C30. If any unexpected archaeological relics are uncovered during the work, then all works must cease immediately in that area and Heritage NSW contacted. Depending on the possible significance of the relics, an archaeological assessment and management strategy may be required before further works can continue in that area. Works may only recommence with the written approval of Heritage NSW.

Waste Storage and Processing

- C31. All waste generated during construction must be secured and maintained within designated waste storage areas at all times and must not leave the site onto neighbouring public or private properties.
- C32. All waste generated during construction must be assessed, classified and managed in accordance with the Waste Classification Guidelines Part 1: Classifying Waste (EPA, 2014).
- C33. The Applicant must ensure that concrete waste and rinse water are not disposed of on the site and are prevented from entering any natural or artificial watercourse.
- C34. The Applicant must record the quantities of each waste type generated during construction and the proposed reuse, recycling and disposal locations for the duration of construction.
- C35. The Applicant must ensure that the removal of hazardous materials, particularly the method of containment and control of emission of fibres to the air, and disposal at an approved waste

disposal facility is in accordance with the requirements of the relevant legislation, codes, standards and guidelines.

Outdoor Lighting

C36. The Applicant must ensure that all external lighting is constructed and maintained in accordance with AS 4282-2019 Control of the obtrusive effects of outdoor lighting.

Site Contamination

C37. Remediation of the site must be carried out in accordance with the Remedial Action Plan (Ref: 55579/127236, Rev 0) prepared by JPS&G and dated 20 February 2020 and any variations to the Remedial Action Plan title approved by an NSW EPA-accredited Site Auditor) or the unexpected finds protocol prepared in accordance with condition B19(c).

C38. If work is to be carried out / completed in stages, a NSW EPA-accredited Site Auditor must confirm satisfactory completion of each stage by the issuance of Interim Audit Advice(s).

C39. The Applicant must ensure the proposed development does not result in a change of risk in relation to any pre-existing contamination on the site that would result in significant contamination.

Independent Environmental Audit

C40. Proposed independent auditors must be agreed to in writing by the Planning Secretary prior to the or commencement of an Independent Audit.

C41. Independent Audits of the development must be conducted and carried out in accordance with the Independent Audit Post Approval Requirements.

C42. The Planning Secretary may require the initial and subsequent Independent Audits to be undertaken at different times to those specified above, upon giving at least 4 week's notice to the Applicant of the date or timing upon which the audit must be commenced.

C43. In accordance with the specific requirements in the Independent Audit Post Approval Requirements, the Applicant must:

- (a) review and respond to each Independent Audit Report prepared under condition C41 of this consent, or condition C42 where notice is given;
- (b) submit the response to the Planning Secretary; and
- (c) make each Independent Audit Report and response to it publicly available within 60 days after submission to the Planning Secretary.

C44. Independent Audit Reports and the applicant/proponent's response to audit findings must be submitted to the Planning Secretary within 2 months of undertaking the independent audit site inspection as outlined in the Independent Audit Post Approval Requirements unless otherwise agreed by the Planning Secretary.

C45. Notwithstanding the requirements of the Independent Audit Post Approval Requirements, the Planning Secretary may approve a request for ongoing independent operational audits to be ceased, where it has been demonstrated to the Planning Secretary's satisfaction that an audit has demonstrated operational compliance.

Operational Readiness Work

C46. Operational readiness work must not commence on site until the following details have been submitted to the Certifier:

- (a) a plan and description of the area(s) of the site to be used for operational readiness work (including pedestrian access) and areas still under construction (including construction access);
- (b) the maximum number of staff to be involved in operational readiness work on site at any one time;
- (c) (c) arrangements to ensure the safety of school staff on the site, including how:
 - (i) areas to be used for operational readiness work will be clearly and securely separated from the areas of the site still under construction;

- (ii) pedestrian access to and within the site will be managed to ensure no conflict with construction vehicle movements; and
 - (d) access and parking arrangements to minimise impacts on the surrounding street network having regard to number of staff involved in operational readiness work on site at any one time and parking arrangements for construction workers on site.
- C47. Operational readiness work must only be undertaken in accordance with the details submitted under condition C46 and the following requirements:
- (a) no more than 30 (15 per school) staff are involved in operational readiness work on site at any one time;
 - (b) no more than 10 (5 per school) vehicles must access the school related to the operational readiness work;
 - (c) no students or parents are permitted on the site; and
 - (d) the Applicant has implemented appropriate arrangements to ensure the safety of school staff on the site.

Boundary retaining wall

- C48. If during construction works, the existing boundary retaining wall/s located on the Chatswood Public School site is damaged and/or requires rectification works, the Applicant must:
- (a) submit to the Certifier structural drawings prepared by a suitably qualified practicing structural engineer detailing the required works to the retaining wall; and
 - (b) submit evidence of consultation with the relevant adjoining landowner/s to the Planning Secretary.
- C49. All costs associated with repairing any damage or undertaking rectification works to the retaining wall required under condition C48 are to be borne by the Applicant.

Construction and Staff Parking

- C50. The Construction Worker and Staff Transportation Strategy prepared under condition B25 must be implemented and maintained for the duration of the construction works. The Strategy must be reviewed every three months during the construction phase to ensure it is satisfactorily reducing the impacts on the availability of on-street parking for residents and visitors. Evidence of the Strategy review and any required changes to the Strategy must be submitted to the Planning Secretary for approval.
- C51. A copy of the Complaint Register maintained under condition B25 must be provided to the Planning Secretary upon request, within the timeframe stated in the request.

PART D PRIOR TO COMMENCEMENT OF OPERATION

Notification of Occupation

- D1. At least one month before commencement of operation, the date of commencement of the operation of the development must be notified to the Planning Secretary in writing. If the operation of the development is to be staged, the Planning Secretary must be notified in writing at least one month before the commencement of each stage, of the date of commencement and the development to be carried out in that stage.

External Walls and Cladding

- D2. Prior to commencement of operation, the Applicant must provide the Certifier with documented evidence that the products and systems used in the construction of external walls including finishes and claddings such as synthetic or aluminium composite panels comply with the requirements of the BCA.
- D3. The Applicant must provide a copy of the documentation given to the Certifier to the Planning Secretary within seven days after the Certifier accepts it.

Works as Executed Plans

- D4. Prior to the commencement of operation, works-as-executed drawings signed by a registered surveyor demonstrating that the stormwater drainage and finished ground levels have been constructed as approved, must be submitted to the Certifier.

Warm Water Systems and Cooling Systems

- D5. The installation of warm water systems and water cooling systems (as defined under the *Public Health Act 2010*) must comply with the *Public Health Act 2010*, Public Health Regulation 2012 and Part 1 (or Part 3 if a Performance-based water cooling system) of *AS/NZS 3666.2:2011 Air handling and water systems of buildings – Microbial control – Operation and maintenance* and the NSW Health Code of Practice for the Control of Legionnaires' Disease.

Outdoor Lighting

- D6. Prior to the commencement of operation, the Applicant must submit evidence from a suitably qualified practitioner to the Certifier that demonstrates that installed lighting associated with the development achieves the objective of minimising light spillage to any adjoining or adjacent sensitive receivers and:
- (a) complies with the latest version of AS 4282-2019 - *Control of the obtrusive effects of outdoor lighting* (Standards Australia, 1997); and
 - (b) has been mounted, screened and directed in such a manner that it does not create a nuisance to surrounding properties or the public road network.

Mechanical Ventilation

- D7. Prior to commencement of operation, the Applicant must provide evidence to the satisfaction of the Certifier that the installation and performance of the mechanical ventilation systems complies with:
- (a) *AS 1668.2-2012 The use of air-conditioning in buildings – Mechanical ventilation in buildings* and other relevant codes; and
 - (b) any dispensation granted by Fire and Rescue NSW.

Operational Noise – Design of Mechanical Plant and Equipment

- D8. Prior to the commencement of operation, the Applicant must submit evidence to the Certifier that the noise mitigation recommendations in the assessment undertaken under condition B26 have been incorporated into the design of mechanical plant and equipment to ensure the development will not exceed the maximum permitted noise criteria as recommended in Table 15 of the Acoustic Assessment Report (Ref: 6698-1.1R Rev A) dated 10 March 2020 and prepared by Day Design.

Fire Safety Certification

- D9. Prior to commencement of occupation, a Fire Safety Certificate must be obtained for all the Essential Fire or Other Safety Measures forming part of this consent. A copy of the Fire Safety

Certificate must be submitted to the relevant authority and Council. The Fire Safety Certificate must be prominently displayed in the building.

Structural Inspection Certificate

- D10. Prior to the commencement of occupation of the relevant parts of any new or refurbished buildings, a Structural Inspection Certificate or a Compliance Certificate must be submitted to the Certifier. A copy of the Certificate with an electronic set of final drawings (contact approval authority for specific electronic format) must be submitted to the approval authority and the Council after:
- (a) the site has been periodically inspected and the Certifier is satisfied that the structural works is deemed to comply with the final design drawings; and
 - (b) the drawings listed on the Inspection Certificate have been checked with those listed on the final Design Certificate/s.

Compliance with Food Code

- D11. Prior to the commencement of operation, the Applicant is to obtain a certificate from a suitably qualified tradesperson, certifying that the kitchen, food storage and food preparation areas have been fitted in accordance with the AS 4674 *Design, construction and fit-out of food premises* and provide evidence of receipt of the certificate to the satisfaction of the Certifier.

Post-construction Dilapidation Report

- D12. Prior to commencement of operation, the Applicant must engage a suitably qualified person to prepare a post-construction dilapidation report at the completion of construction. This report is:
- (a) to ascertain whether the construction created any structural damage to adjoining buildings or infrastructure;
 - (b) to be submitted to the Certifier. In ascertaining whether adverse structural damage has occurred to adjoining buildings or infrastructure, the Certifier must:
 - (i) compare the post-construction dilapidation report with the pre-construction dilapidation report required by these conditions; and
 - (ii) have written confirmation from the relevant authority that there is no adverse structural damage to their infrastructure and roads.
 - (c) to be forwarded to Council for information.

Protection of Public Infrastructure

- D13. Unless the Applicant and the applicable authority agree otherwise, the Applicant must:
- (a) repair, or pay the full costs associated with repairing, any public infrastructure that is damaged by carrying out the development; and
 - (b) relocate, or pay the full costs associated with relocating any infrastructure that needs to be relocated as a result of the development.

Note: This condition does not apply to any damage to roads caused as a result of general road usage.

Road Damage

- D14. Prior to the commencement of operation, the cost of repairing any damage caused to Council or other Public Authority's assets in the vicinity of the Subject Site as a result of construction works associated with the approved development must be met in full by the Applicant.

Protection of Property

- D15. Unless the Applicant and the applicable owner agree otherwise, the Applicant must repair, or pay the full costs associated with repairing any property that is damaged by carrying out the development.

Road upgrade works

- D16. Prior to the commencement of operation (unless otherwise agreed by the Planning Secretary), the installation of roundabout(s) or other road upgrade works (if any) required by condition C28 must be completed to Council's requirements.

Note: All works associated with the installation of roundabout(s) shall be at no cost Council.

Bicycle Parking and End-of-Trip Facilities

D17. Prior to occupation, compliance with the following requirements for secure bicycle parking and end-of-trip facilities must be submitted to the Certifier:

- (a) the provision of a minimum 60 bicycle parking spaces for Chatswood Public School for staff, students and visitors;
- (b) the provision of a minimum 84 bicycle parking spaces for Chatswood High School for staff, students and visitors;
- (c) the layout, design and security of bicycle facilities must comply with the minimum requirements of the latest version of AS 2890.3:2015 *Parking facilities - Bicycle parking*, and be located in easy to access, well-lit areas that incorporate passive surveillance;
- (d) the provision of end-of-trip facilities for staff; and
- (e) appropriate pedestrian and cyclist advisory signs are to be provided.

Note: All works/regulatory signposting associated with the proposed development shall be at no cost to the relevant roads authority.

School Transport Plan

D18. Prior to the commencement of operation, a School Travel Plan (STP), must be submitted to the satisfaction of the Planning Secretary. The plan must:

- (a) be prepared by a suitably qualified consultant in consultation with Council and TfNSW;
- (b) include arrangements to promote the use of active and sustainable transport modes, including:
 - (i) objectives and modes share targets (i.e. Site and land use specific, measurable and achievable and timeframes for implementation);
 - (ii) specific tools and actions to help achieve the objectives and mode share target of 16% reduction in car trips;
 - (iii) measures to increase use of the Pacific Highway overhead bridge by staff and students including (but not limited to) installation of signage in consultation with Council and education / awareness program to promote use of the overhead bridge.
 - (iv) details regarding the methodology and monitoring/review program to measure the effectiveness of the objectives and mode share targets, including the frequency of monitoring and the requirement for travel surveys to identify travel behaviours of users of the development.
- (c) include operational transport access management arrangements, including:
 - (i) detailed pedestrian analysis including the identification of safe route options to identify the need for management measures such as staggered school start and finish times to ensure students and staff are able to access and leave the Site in a safe and efficient manner during school start and finish;
 - (ii) the location of all car parking spaces on the school campuses and their allocation (i.e. staff, visitor, accessible, emergency, etc.);
 - (iii) the location and operational management procedures of the drop-off and pick-up parking, including staff management/traffic controller arrangements;
 - (iv) the location and operational management procedures for the drop-off and pick-up of students by buses and coaches including staff management/traffic controller arrangements;
 - (v) delivery and services vehicle and bus access and management arrangements;
 - (vi) management of approved access arrangements;
 - (vii) potential traffic impacts on surrounding road networks and mitigation measures to minimise impacts, including measures to mitigate queuing impacts associated with vehicles accessing drop-off and pick-up zones;
 - (viii) car parking arrangements and management associated with the proposed use of school facilities by community members; and

- (d) measures to promote and support the implementation of the plan, including financial and human resource requirements, roles and responsibilities for relevant employees involved in the implementation of the plan; and
- (e) a monitoring and review program.

Utilities and Services

D19. Prior to commencement of operation, the Applicant must obtain a Compliance Certificate for water and sewerage infrastructure servicing of the site under section 73 of the *Sydney Water Act 1994*.

Stormwater Operation and Maintenance Plan

- D20. Prior to the commencement of operation, a Stormwater Operation and Maintenance Plan (SOMP) is to be submitted to the Certifier along with evidence of compliance with the SOMP. The SOMP must ensure the proposed stormwater quality measures remain effective and contain the following:
- (a) maintenance schedule of all stormwater quality treatment devices;
 - (b) record and reporting details;
 - (c) relevant contact information; and
 - (d) Work Health and Safety requirements.

Signage

- D21. Prior to the commencement of operation, way-finding signage and signage identifying the location of staff car parking must be installed.
- D22. Prior to the commencement of operation, bicycle way-finding signage must be installed within the site to direct cyclists from footpaths to designated bicycle parking areas.

Operational Waste Management Plan

- D23. Prior to the commencement of operation, the Applicant must prepare a Waste Management Plan for the development and submit it to the Certifier. The Waste Management Plan must:
- (a) detail the type and quantity of waste to be generated during operation of the development;
 - (b) describe the handling, storage and disposal of all waste streams generated on site, consistent with the *Protection of the Environment Operations Act 1997*, *Protection of the Environment Operations (Waste) Regulation 2014* and the *Waste Classification Guideline* (Department of Environment, Climate Change and Water, 2009);
 - (c) detail the materials to be reused or recycled, either on or off site; and
 - (d) include the Management and Mitigation Measures included in Appendix 30 of the EIS.

Site Contamination

D24. Prior to the commencement of operation, the Applicant must submit a Section A1 Site Audit Statement or a Section A2 Site Audit Statement accompanied by an Environmental Management Plan prepared by a NSW EPA accredited Site Auditor. The Section A1 or A2 Site Audit Statement must verify the relevant part of the site is suitable for the intended land use and be provided, along with any Environmental Management Plan to the Planning Secretary and the Certifier.

Landscaping

- D25. Prior to the commencement of operation, landscaping of the site must be completed in accordance with landscape plans approved under condition A2.
- D26. Prior to the commencement of operation, the Applicant must submit a Landscape Management Plan to manage the revegetation and landscaping on-site, to the Certifier. The plan must:
- (a) describe the ongoing monitoring and maintenance measures to manage revegetation and landscaping; and
 - (b) be consistent with the Applicant's Management and Mitigation Measures at 3 in the EIS;

Improvements to Public School Northern Boundary Interface

D27. Prior to the commencement of operation, all improvement works required under condition B1 must be completed and evidence of completion submitted the Certifier.

PART E POST OCCUPATION

Out of Hours Event Management Plan

- E1. Prior to the commencement of the first out of hours events (School Use) run by the school that involve 100 or more people, the Applicant is to prepare an Out of Hours Event Management Plan (School Use) in consultation with Council and submit it to the Council and Planning Secretary for information. The plan must include the following:
- (a) the number of attendees, time and duration;
 - (b) arrival and departure times and modes of transport;
 - (c) where relevant, a schedule of all annual events;
 - (d) measures to encourage non-vehicular travel to the school and promote and support the use of alternate travel modes (i.e. public transport);
 - (e) details of the use of the school halls at the Public School and/or High School, where applicable, restricting use before 8am and after 10pm;
 - (f) measures to minimise localised traffic and parking impacts; and
 - (g) include measures to minimise noise impacts on any sensitive residential receivers, including the preparation of acoustic management plan.
- E2. The Out of Hours Event Management Plan (School Use) must be implemented by the Applicant for the duration of the identified events or use.
- E3. Prior to the commencement of out of hours events (Community Use) run by the external parties that involve 100 or more people, the Applicant is to prepare an Out of Hours Event Management Plan (Community Use) in consultation with Council and submit it to the Council and Planning Secretary for information. The plan must include the following:
- (a) the number of attendees, time and duration;
 - (b) arrival and departure times and modes of transport;
 - (c) where relevant, a schedule of all annual events;
 - (d) measures to encourage non-vehicular travel to the school and promote and support the use of alternate travel modes (i.e. public transport);
 - (e) details of the use of the school halls at the Public School and/or High School, where applicable, restricting use before 8am and after 10pm;
 - (f) measures to minimise localised traffic and parking impacts; and
 - (g) measures to minimise noise impacts on any sensitive residential receivers, including the preparation of acoustic management plan.
- E4. The Out of Hours Event Management Plan (Community Use) must be implemented by the Applicant for the duration of the identified community event or use.

Operation of Plant and Equipment

- E5. All plant and equipment used on site must be maintained in a proper and efficient condition and operated in a proper and efficient manner.

Warm Water Systems and Cooling Systems

- E6. The operation and maintenance of warm water systems and water cooling systems (as defined under the Public Health Act 2010) must comply with the Public Health Act 2010, Public Health Regulation 2012 and Part 2 (or Part 3 if a Performance-based water cooling system) of AS/NZS 3666.2:2011 Air handling and water systems of buildings – Microbial control – Operation and maintenance and the NSW Health Code of Practice for the Control of Legionnaires' Disease.

Community Communication Strategy

- E7. The Community Communication Strategy, as submitted to the Planning Secretary, must be implemented for a minimum of 12 months following the completion of construction.

Environmental Management Plan

- E8. Upon completion of remediation works, the Applicant must manage the site in accordance with the Environmental Management Plan approved by the Site Auditor under condition D24 and any on-going maintenance of remediation notice issued by EPA under *the Contaminated Land Management Act 1997*.

Operational Noise Limits

- E9. The Applicant must ensure that noise generated by operation of the development does not exceed the noise limits contained in the Acoustic Assessment Report (Ref: 6698-1.1R Rev A) dated, 10 March 2020 and prepared by Day Design.
- E10. The Applicant must undertake short term noise monitoring in accordance with the *Noise Policy for Industry* where valid data is collected following the commencement of use of each stage of the development. The monitoring program must be carried out by an appropriately qualified person and a monitoring report must be submitted to the Planning Secretary within two months of commencement use of each stage of the development or other timeframe agreed to by the Planning Secretary to verify that operational noise levels do not exceed the recommended noise levels for mechanical plant identified in the Acoustic Assessment Report (Ref: 6698-1.1R Rev A), dated 10 March 2020 and prepared by Day Design. Should the noise monitoring program identify any exceedance of the recommended noise levels referred to above, the Applicant is required to implement appropriate noise attenuation measures so that operational noise levels do not exceed the recommended noise levels or provide attenuation measures at the affected noise sensitive receivers.

Unobstructed Driveways and Parking Areas

- E11. All driveways, footways and parking areas must be unobstructed at all times. Driveways, footways and car spaces must not be used for the manufacture, storage or display of goods, materials, refuse, skips or any other equipment and must be used solely for vehicular and/or pedestrian access and for the parking of vehicles associated with the use of the premises.

Pacific Highway operational vehicular entrance

- E12. During operation of the development, the Pacific Highway vehicular entrance must:
- (a) only be used by ambulance vehicles and service / delivery vehicles which are not larger than an ambulance vehicle; and
 - (b) only be used by service / delivery vehicles outside of school hours.

Vehicle Ingress and Egress

- E13. All vehicles are to enter and leave the site in a forward direction.
- E14. All vehicles must be wholly contained on site before being required to stop. Any gates must be located so as to allow the largest vehicle to be wholly within the site before stopping.

School Transport Plan

- E15. The School Transport Plan required by condition D18 of this consent must be updated annually and implemented unless otherwise agreed by the Planning Secretary.

Ecologically Sustainable Development

- E16. Unless otherwise agreed by the Planning Secretary, within six months of commencement of operation, Green Star certification must be obtained demonstrating the development achieves a minimum 4 star Green Star Design & As Built rating. If required to be obtained, evidence of the certification must be provided to the Certifier and the Planning Secretary. If an alternative certification process has been agreed to by the Planning Secretary under condition B15, evidence of compliance of implementation must be provided to the Planning Secretary and Certifier.

Outdoor Lighting

- E17. Notwithstanding condition D6, should outdoor lighting result in any residual impacts on the amenity of surrounding sensitive receivers, the Applicant must provide mitigation measures in consultation with affected landowners to reduce the impacts to an acceptable level.

Landscaping

E18. The Applicant must maintain the landscaping and vegetation on the site in accordance with the approved Landscape Management Plan required by condition D25 for the duration of occupation of the development.

Hours of Operation for Waste Collection

E19. Waste collection must be undertaken during the hours of 7:30am to 6pm Monday to Friday.

ADVISORY NOTES

General

AN1. All licences, permits, approvals and consents as required by law must be obtained and maintained as required for the development. No condition of this consent removes any obligation to obtain, renew or comply with such licences, permits, approvals and consents.

Long Service Levy

AN2. For work costing \$25,000 or more, a Long Service Levy must be paid. For further information please contact the Long Service Payments Corporation Helpline on 131 441.

Legal Notices

AN3. Any advice or notice to the consent authority must be served on the Planning Secretary.

Access for People with Disabilities

AN4. The works that are the subject of this application must be designed and constructed to provide access and facilities for people with a disability in accordance with the BCA. Prior to the commencement of construction, the Certifier must ensure that evidence of compliance with this condition from an appropriately qualified person is provided and that the requirements are referenced on any certified plans.

Utilities and Services

AN5. Prior to the construction of any utility works associated with the development, the Applicant must obtain relevant approvals from service providers.

AN6. Prior to the commencement of above ground works written advice must be obtained from the electricity supply authority, an approved telecommunications carrier and an approved gas carrier (where relevant) stating that satisfactory arrangements have been made to ensure provisions of adequate services.

Road Design and Traffic Facilities

AN7. All roads and traffic facilities must be designed to meet the requirements of Council or TfNSW (whichever is applicable). The necessary permits and approvals from the relevant road authority must be obtained prior to the commencement of road or pavement construction works.

Road Occupancy Licence

AN8. A Road Occupancy Licence must be obtained from the relevant road authority for any works that impact on traffic flows during construction activities.

SafeWork Requirements

AN9. To protect the safety of work personnel and the public, the work site must be adequately secured to prevent access by unauthorised personnel, and work must be conducted at all times in accordance with relevant SafeWork requirements.

Hoarding Requirements

AN10. The Applicant must submit a hoarding application to Council for the installation of any hoardings over Council footways or road reserve.

Handling of Asbestos

AN11. The Applicant must consult with SafeWork NSW concerning the handling of any asbestos waste that may be encountered during construction. The requirements of the Protection of the Environment Operations (Waste) Regulation 2014 with particular reference to Part 7 – 'Transportation and management of asbestos waste' must also be complied with.

Speed limit authorisation

AN12. At least eight weeks prior to the commencement of operation, the Applicant must submit the following details to TfNSW and obtain authorisation to install School Zone signs and associated pavement markings, and / or removal / relocation of any existing Speed Limit signs:

- (a) a copy of the conditions of consent;

- (b) the proposed school commencement/opening date;
- (c) two sets of detailed design plans showing the following:
 - (i) accurate Site boundaries;
 - (ii) details of all road reserves, adjacent to the Site boundaries;
 - (iii) all proposed access points from the Site to the public road network and any additional conditions imposed/proposed on their use;
 - (iv) all existing and proposed pedestrian crossing facilities on the adjacent road network;
 - (v) all existing and proposed traffic control devices and pavement markings on the adjacent road network (including School Zone signs and pavement markings); and
 - (vi) all existing and proposed street furniture and street trees.

Fire Safety Certificate

AN13. The owner must submit to Council an Annual Fire Safety Statement, each 12 months after the final Safety Certificate is issued. The certificate must be on, or to the effect of, Council's Fire Safety Statement.

WRITTEN INCIDENT NOTIFICATION AND REPORTING REQUIREMENTS

Written Incident Notification Requirements

1. A written incident notification addressing the requirements set out below must be notified to the Planning Secretary through the major projects portal within seven days after the Applicant becomes aware of an incident. Notification is required to be given under this condition even if the Applicant fails to give the notification required under condition A24 or, having given such notification, subsequently forms the view that an incident has not occurred.
2. Written notification of an incident must:
 - (a) identify the development and application number;
 - (b) provide details of the incident (date, time, location, a brief description of what occurred and why it is classified as an incident);
 - (c) identify how the incident was detected;
 - (d) identify when the applicant became aware of the incident;
 - (e) identify any actual or potential non-compliance with conditions of consent;
 - (f) describe what immediate steps were taken in relation to the incident;
 - (g) identify further action(s) that will be taken in relation to the incident; and
 - (h) identify a project contact for further communication regarding the incident.
3. Within 30 days of the date on which the incident occurred or as otherwise agreed to by the Planning Secretary, the Applicant must provide the Planning Secretary and any relevant public authorities (as determined by the Planning Secretary) with a detailed report on the incident addressing all requirements below, and such further reports as may be requested.
4. The Incident Report must include:
 - (a) a summary of the incident;
 - (b) outcomes of an incident investigation, including identification of the cause of the incident;
 - (c) details of the corrective and preventative actions that have been, or will be, implemented to address the incident and prevent recurrence; and
 - (d) details of any communication with other stakeholders regarding the incident.