

SCHOOL INFRASTRUCTURE NSW





HUNTER RIVER HIGH SCHOOL

36 ELKIN AVENUE, HEATHERBRAE NSW 2324

ISSUE FOR SCHEMATIC DESIGN - REF01 2024.05.02

Stantec Project Number: 301350909

DRAWING LIST NO.

HRHS-STNC-XX-XX-DR-C-000001

HRHS-STNC-XX-XX-DR-C-007001 HRHS-STNC-XX-XX-DR-C-050001

HRHS-STNC-XX-XX-DR-C-055001

HRHS-STNC-XX-XX-DR-C-060001

HRHS-STNC-XX-XX-DR-C-060101

HRHS-STNC-XX-XX-DR-C-060102

HRHS-STNC-XX-XX-DR-C-060103

HRHS-STNC-XX-XX-DR-C-070001

HRHS-STNC-XX-XX-DR-C-076001

HRHS-STNC-XX-XX-DR-C-100001

HRHS-STNC-XX-XX-DR-C-403001

HRHS-STNC-XX-XX-DR-C-406001

HRHS-STNC-XX-XX-DR-C-406002

HRHS-STNC-XX-XX-DR-C-406003

HRHS-STNC-XX-XX-DR-C-440101

HRHS-STNC-XX-XX-DR-C-440102

HRHS-STNC-XX-XX-DR-C-440103

HRHS-STNC-XX-XX-DR-C-500001

HRHS-STNC-XX-XX-DR-C-520001

HRHS-STNC-XX-XX-DR-C-520101

HRHS-STNC-XX-XX-DR-C-520102

HRHS-STNC-XX-XX-DR-C-520103

HRHS-STNC-XX-XX-DR-C-526001

HRHS-STNC-XX-XX-DR-C-526002

HRHS-STNC-XX-XX-DR-C-526003

HRHS-STNC-XX-XX-DR-C-526004

HRHS-STNC-XX-XX-DR-C-527001

DRAWING NAME

COVER SHEET, DRAWING REGISTRY AND LOCALITY PLAN

GENERAL NOTES

EXISTING CONDITIONS PLAN

DEMOLITION PLAN

GENERAL ARRANGEMENT PLAN - SITE WIDE

SITEWORKS PLAN - SHEET 1

SITEWORKS PLAN - SHEET 2

SITEWORKS PLAN- SHEET 3

EROSION AND SEDIMENT CONTROL - PLAN

EROSION AND SEDIMENT CONTROL - DETAILS

BULK EARTHWORKS PLAN

ROADS TYPICAL SECTIONS

ROADS DETAILS - SHEET 1

ROADS DETAILS - SHEET 2

ROADS DETAILS - SHEET 3

PAVEMENT PLAN - SHEET 1

PAVEMENT PLAN - SHEET 2

PAVEMENT PLAN - SHEET 3

STORMWATER DRAINAGE CATCHMENT PLAN

STORMWATER DRAINAGE PLAN - SITE WIDE

STORMWATER DRAINAGE PLAN - SHEET 1

STORMWATER DRAINAGE PLAN - SHEET 2

STORMWATER DRAINAGE PLAN - SHEET 3

STORMWATER DRAINAGE DETAILS - SHEET 1

STORMWATER DRAINAGE DETAILS - SHEET 2

STORMWATER DRAINAGE DETAILS - SHEET 3

STORMWATER DRAINAGE DETAILS - SHEET 4

STORMWATER DRAINAGE PIT SCHEDULE

REVISION

С

С

С

С

С

С

С

С

С

С

С

DATE

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

2024.05.02

The professional's seal on the cover sheet represents that the information on the cover sheet is accurate in designer's professional opinion but does not assume professional responsibility for documents sealed by others that are referenced on the cover sheet. All professionals sealing drawings as a part of the design are professionally responsible for their own sealed documents.

- RELEVANT AUTHORITY SPECIFICATIONS AND DETAILS. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH OTHER CONSULTANTS' DRAWINGS AND SPECIFICATIONS AND WITH OTHER SUCH WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK.
- ALL DIMENSIONS ARE IN MILLIMETRES & ALL LEVELS ARE IN METRES, UNO (UNLESS NOTED OTHERWISE).
- NO DIMENSION SHALL BE OBTAINED BY SCALING THE DRAWINGS. . ALL LEVELS AND SETTING OUT DIMENSIONS SHOWN ON THE DRAWINGS
- SHALL BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS. . EXISTING SERVICES WHERE SHOWN HAVE BEEN PLOTTED FROM SUPPLIED

DATA AND SUCH THEIR ACCURACY CAN NOT BE GUARANTEED. IT IS THE

RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF WORK. CAD FILES / DTM FILES TO BE SUPPLIED IN AUTOCAD FORMAT FOR SETOUT PURPOSES (UPON REQUEST).

SITEWORKS NOTES

- ORIGIN OF LEVELS:- REFER SURVEY NOTES.
- . CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES TO BE REPORTED TO STANTEC.
- . CONTRACTOR TO CONFIRM ALL CBR VALUES PRIOR TO COMMENCEMENT OF WORKS.
- . MAKE SMOOTH CONNECTION WITH EXISTING WORKS. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME
- DENSITY AS THE ADJACENT MATERIAL. . ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN
- PROVIDE 10mm WIDE EXPANSION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR UNIT PAVEMENTS.
- ASPHALTIC CONCRETE SHALL CONFORM TO RMS. SPECIFICATION R116. 9. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH RMS. FORM 3051 (UNBOUND), RMS. FORM 3052 (BOUND) COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE
- WITH AS 1289 5.2.1. FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³ BASECOURSE MATERIAL PLACED.
- 10. ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH RMS. FORM 3051, 3051.1 AND COMPACTED TO MINIMUM 95% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³ OF SUB-BASE COURSE MATERIAL PLACED.
- 1. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (9) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH RMS. FORM 3051 AND 3051.1 WILL BE CONSIDERED. SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF STANTEC.
- 12. SHOULD THE CONTRACTOR WISH TO USE A RECYCLED PRODUCT THIS SHALL BE CLEARLY INDICATED IN THEIR TENDER AND THE PRICE DIFFERENCE BETWEEN AN IGNEOUS PRODUCT AND A RECYCLED PRODUCT SHALL BE CLEARLY INDICATED.
- 13. WHERE NOTED ON THE DRAWINGS THAT WORKS ARE TO BE CARRIED BY OTHERS, (eg. ADJUSTMENT OF SERVICES), THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CO-ORDINATION OF THESE WORKS.

SURVEY NOTES

- THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN SHOWN AS PER THE TOPOGRAPHIC SURVEY RECEIVED ON 14/06/2022 PREPARED BY PARKER SCANLON, REFERENCE 'B1975', DATED 04/05/2020.
- THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. STANTEC DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE OR ITS SUITABILITY AS A BASIS FOR CONSTRUCTION DRAWINGS. SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT STANTEC.

CONCRETE NOTES

- ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600 CURRENT EDITION WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- 2. CONCRETE QUALITY ALL REQUIREMENTS OF THE CURRENT ACSE CONCRETE SPECIFICATION DOCUMENT 1 SHALL APPLY TO THE FORMWORK, REINFORCEMENT AND CONCRETE UNLESS NOTED OTHERWISE.

ELEMENT	AS 3600 F'c MPa AT 28 DAYS	SPECIFIED SLUMP	NOMINAL AGG. SIZE
VEHICULAR BASE KERBS, PATHS, AND PITS	32 25	60 80	20 20

- CEMENT TYPE SHALL BE (ACSE SPECIFICATION) TYPE SL - PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH AS 1379.
- NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN WRITING BY STANTEC.
- CLEAR CONCRETE COVER TO ALL REINFORCEMENT FOR DURABILITY SHALL BE 40mm TOP AND 70mm FOR EXTERNAL EDGES UNLESS NOTED OTHERWISE.
- ALL REINFORCEMENT SHALL BE FIRMLY SUPPORTED ON MILD STEEL PLASTIC TIPPED CHAIRS, PLASTIC CHAIRS OR CONCRETE CHAIRS AT NOT GREATER THAN 1m CENTRES BOTH WAYS. BARS SHALL BE TIED AT ALTERNATE INTERSECTIONS.
- THE FINISHED CONCRETE SHALL BE A DENSE HOMOGENEOUS MASS, COMPLETELY FILLING THE FORMWORK, THOROUGHLY EMBEDDING THE REINFORCEMENT AND FREE OF STONE POCKETS. ALL CONCRETE INCLUDING SLABS ON GROUND AND FOOTINGS SHALL BE COMPACTED AND CURED IN ACCORDANCE WITH R.M.S. SPECIFICATION R83.
- REINFORCEMENT SYMBOLS: N DENOTES GRADE 450 N BARS TO AS/NZS 4671 GRADE N
- R DENOTES 230 R HOT ROLLED PLAIN BARS TO AS/NZS 4671 SL DENOTES HARD-DRAWN WIRE REINFORCING FABRIC TO AS/NZS 4671

NUMBER OF BARS IN GROUP - BAR GRADE AND TYPE

17 N 20 250

THE FIGURE FOLLOWING THE FABRIC SYMBOL SL IS THE

NOMINAL BAR SIZE IN mm — SPACING IN mm

REFERENCE NUMBER FOR FABRIC TO AS/NZS 4671. 8. FABRIC SHALL BE LAPPED IN ACCORDANCE WITH THE FOLLOWING DETAIL


> MIN 25 LAP TWO WIRES

JOINTING NOTES

PEDESTRIAN PAVEMENT JOINTS


- ALL PEDESTRIAN PAVEMENTS ARE TO BE JOINTED AS FOLLOWS. (U.N.O) EXPANSION JOINTS ARE TO BE LOCATED WHERE POSSIBLE AT TANGENT POINTS OF CURVES AND ELSEWHERE AT MAX. 5.4m CENTRES.
- CONTRACTION JOINTS ARE TO BE LOCATED AT A MAX. SPACING OF 1.8m WHERE POSSIBLE JOINTS SHOULD BE LOCATED TO MATCH KERBING
- AND OR ADJACENT PAVEMENT JOINTS.

PEDESTRIAN PAVEMENT JOINT DETAIL:



VEHICULAR PAVEMENT JOINTS

- ALL VEHICULAR PAVEMENTS TO BE JOINTED AS FOLLOWS. (U.N.O) CONTRACTION JOINTS SHOULD GENERALLY BE LOCATED AT A MAX OF 5.0m CENTRES WITH DOWELED EXPANSION JOINTS AT MAX 20.0m CENTRES
- VEHICULAR PAVEMENT JOINT DETAIL



KERBING NOTES

MODIFIED DRY DENSITY (AS 1289 5.2.1).

- ALL CONCRETE TO HAVE A MINIMUM COMPRESSIVE STRENGTH OF 25 MPa U.N.O IN REINFORCED CONCRETE NOTES.
- ALL KERBS, GUTTERS, DISH DRAINS AND CROSSINGS TO BE CONSTRUCTED ON 100mm GRANULAR BASECOURSE COMPACTED TO MINIMUM 95%
- EXPANSION JOINTS (E.J) TO BE FORMED FROM 10mm COMPRESSIBLE CORK FILLER BOARD FOR THE FULL DEPTH OF THE SECTION AND CUT TO PROFILE. EXPANSION JOINTS TO BE LOCATED AT DRAINAGE PITS, ON TANGENT POINTS OF CURVES AND ELSEWHERE AT MAX 12m CENTRES EXCEPT FOR INTEGRAL KERBS WHERE THE EXPANSION JOINTS ARE TO MATCH THE JOINT LOCATIONS IN THE SLABS.
- WEAKENED PLANE JOINTS TO BE MIN 3mm WIDE AND LOCATED AT 3m CENTRES EXCEPT FOR INTEGRAL KERBS WHERE THE WEAKENED PLANE JOINTS ARE TO MATCH THE JOINT LOCATIONS IN THE SLABS.
- BROOMED FINISH TO ALL RAMPED AND VEHICULAR CROSSINGS. ALL OTHER KERBING OR DISH DRAINS TO BE STEEL FLOAT FINISHED.
- IN THE REPLACEMENT OF KERB AND GUTTER:- EXISTING ROAD PAVEMENT IS TO BE SAWCUT 900mm U.N.O FROM THE LIP OF GUTTER. UPON COMPLETION OF THE NEW KERB AND GUTTER NEW BASECOURSE AND SURFACE TO BE LAID 600mm WIDE U.N.O.
- EXISTING ALLOTMENT DRAINAGE PIPES ARE TO BE BUILT INTO THE NEW KERB AND GUTTER WITH 100mm DIA HOLE.
- EXISTING KERB AND GUTTER IS TO BE COMPLETELY REMOVED WHERE NEW KERB AND GUTTER IS SHOWN.

PROPOSED SERVICES NOTES

- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH RELEVANT SERVICE AUTHORITY DOCUMENTATION AND CURRENT NSW STREETS OPENING CONFERENCE GUIDE TO CODES AND PRACTICES FOR STREETS OPENING LITERATURE.
- THE CONTRACTOR SHALL ATTEND, MANAGE & SUPERVISE THE PROVISION OF PUBLIC UTILITY SERVICES TO THE WORKS GENERALLY AS INDICATED ON THE SERVICES PLANS, NOTING THAT PRIOR & DURING CONSTRUCTION THE PUBLIC UTILTITY AUTHORITIES WILL FINALISE THEIR DOCUMENTATION TO CONSTRUCTION ISSUE STANDARD.
- THE CIVIL CONTRACTOR (TRENCH PROVIDER) IS TO ARRANGE ON SITE MEETING WITH ALL SERVICE AUTHORITIES PRIOR TO THE INSTALLATION OF CONDUITS.
- THE CIVIL CONTRACTOR TO CO-ORDINATE INSTALLATION OF ELECTRICITY, GAS, TELECOMMUNICATION, WATER AND SEWER SERVICES.
- ELECTRICITY, GAS AND TELECOMMUNICATION SERVICES ARE TO BE LAID FOLLOWING THE INSTALLATION OF STORMWATER, SEWER AND WATER SERVICES AND KERB AND GUTTER.
- ALL UTILITY AUTHORITY REPRESENTATIVES TO INSPECT ROAD CROSSINGS PRIOR TO SEALING.
- ALL ELECTRICAL ROAD CROSSINGS TO BE CLASS 6 (ORANGE) uPVC CONDUITS.
- ALL GAS ROAD CROSSINGS TO BE uPVC GREY SEWER GRADE CONDUITS. ALL STREET POLES TO BE POSITIONED THE APPROPRIATE DISTANCE FROM
- FACE OF KERB TO FACE OF POLE ACCORDING TO THE CURRENT NSW STREETS OPENING CONFERENCE GUIDE TO CODES AND PRACTICES FOR STREETS OPENING LITERATURE. CONTRACTOR TO ALLOW TO EXCAVATE AND BACKFILL TRENCH GENERALLY IN ACCORDANCE WITH NOTE 2.
- 10. ALL SERVICE PIT COVERS AND MARKERS ARE TO BE LAID WHOLLY WITHIN THE CONCRETE FOOTPATH. CONTACT SUPERINTENDANT SHOULD DIFFICULTIES ARISE.

TELSTRA - DUTY OF CARE NOTE

FELSTRA'S PLANS SHOW ONLY THE PRESENCE OF CABLES AND PLANT. THEY ONLY SHOW THEIR POSITION RELATIVE TO ROAD BOUNDARIES, PROPERTY FENCES ETC. AT THE TIME OF INSTALLATION AND TELSTRA DOES NOT NARRANT OR HOLD OUT THAT SUCH PLANS ARE ACCURATE THEREAFTER DUE TO CHANGES THAT MAY OCCUR OVER TIME. DO NOT ASSUME DEPTH OR ALIGNMENT OF CABLES OR PLANT AS THESE VARY SIGNIFICANTLY. THE CONTRACTOR HAS A DUTY OF CARE WHEN EXCAVATING NEAR TELSTRA CABLES AND PLANT. BEFORE USING MACHINE EXCAVATORS TELSTRA PLANT MUST FIRST BE PHYSICALLY EXPOSED BY SOFT DIG POTHOLING TO IDENTIFY IT'S LOCATION TELSTRA WILL SEEK COMPENSATION FOR DAMAGES CAUSED TO IT'S PROPERTY AND LOSSES CAUSED TO TELSTRA AND IT'S CUSTOMERS.

EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- THE SITE SUPERINTENDENT/ENGINEER WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS DOCUMENTED.
- 2. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH 2.1. LOCAL AUTHORITY REQUIREMENTS
- 2.2. EPA REQUIREMENTS
- 2.3. NSW DEPARTMENT OF HOUSING MANUAL "MANAGING URBAN
- STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH 2004. . MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE LOCAL AUTHORITY.
- 4. WHEN STORMWATER PITS ARE CONSTRUCTED, PREVENT SITE RUNOFF
- ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS. . CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY. REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

LAND DISTURBANCE

- WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- 6.1. INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES AS SHOWN ON
- PLAN. REFER DETAIL. 6.2. CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL.
- 6.3. INSTALL SEDIMENT BASIN AS SHOWN ON PLAN
- 6.4. INSTALL SEDIMENT TRAPS AS SHOWN ON PLAN. . UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- B. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER
- CONTROL. . FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION

SEDIMENT CONTROL

- 10. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS. INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

OTHER MATTERS

- 3. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND
- 14. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY:
- 14.1. PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE
- 14.2. ENSURING THAT NOTHING IS NAILED TO THEM
- 14.3. PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS 14.4. ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE
- TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER 14.5. A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE
- THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH 14.6. CARE IS TAKEN NOT TO CUT ROOTS UNNECESSARILY NOR TO COMPACT THE SOIL AROUND THEM.

- **BULK EARTHWORKS NOTES**
- REFER SPECIFICATIONS NOTES FOR EARTHWORKS GENERAL
- REQUIREMENTS. . STRIP EXISTING TOPSOIL IN CONSULTATION WITH THE GEOTECHNICAL ENGINEER / REPORT. FOR THE PURPOSES OF EARTHWORKS CALCULATIONS
- A TOPSOIL STRIPPING DEPTH OF 300mm HAS BEEN ASSUMED. GROUND SLAB DEPTH OF 150mm HAS BEEN ASSUMED WHERE REQUIRED. NO ALLOWANCE HAS BEEN MADE FOR BULKING FACTORS. NOTE ALL
- VOLUMES DEPICTED ARE SOLID VOLUMES ONLY AND MAY NOT REFLECT DETAILED EARTHWORKS. NO ALLOWANCE HAS BEEN MADE FOR DETAILED EARTHWORKS; ie SERVICE

TRENCHING, DETAILED EXCAVATION, FOOTINGS, RETAINING WALLS AND

- THE LIKE. . THE CONTRACTOR SHALL USE FINAL SURFACE LEVELS AND TYPICAL
- PAVEMENT DETAILS FOR ACTUAL EARTHWORKS LEVELS. . BULK EARTHWORKS ARE BASED ON THE SETDOWN TO UNDERSIDE OF
- PAVEMENT BUILDUPS AS SPECIFIED FROM FINISHED SURFACE LEVELS.
- SITE STRIPPING VOLUMES HAVE NOT BEEN INCLUDED IN BULK EARTHWORKS CALCULATIONS.

STORMWATER DRAINAGE NOTES

- ON COMPLETION OF STORMWATER INSTALLATION, ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL CONDITION, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL AND GRASSED AREAS AND ROAD
- PAVEMENTS, UNLESS DIRECTED OTHERWISE. PIPES 300 DIA. AND LARGER TO BE REINFORCED CONCRETE CLASS '3'
- APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS. U.N.O.
- PIPES UP TO 300 DIA SHALL BE SEWER GRADE uPVC WITH SOLVENT
- WELDED JOINTS.
- . EQUIVALENT STRENGTH VCP OR FRC PIPES MAY BE USED.
- 5. ALL STORMWATER DRAINAGE LINES UNDER PROPOSED BUILDING SLABS TO BE uPVC PRESSURE PIPE GRADE 6. ENSURE ALL VERTICALS AND DOWNPIPES ARE uPVC PRESSURE PIPE, GRADE 6 FOR A MIN OF 3.0m IN
- PIPES TO BE INSTALLED TO TYPE HS3 (ROAD) HS2 (LOTS) SUPPORT IN ACCORDANCE WITH AS 3725 (2007) IN ALL CASES BACKFILL TRENCH WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS
- 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75) ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY
- WITH THE REQUIREMENTS OF AS 3500 3.1 (2006) AND AS/NZS 3500 3.2 (2010). PRECAST PITS MAY BE USED EXTERNAL TO THE BUILDING SUBJECT TO APPROVAL BY STANTEC.
- . ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA.
- 10. WHERE SUBSOIL DRAINS PASS UNDER FLOOR SLABS AND VEHICULAR
- PAVEMENTS, UNSLOTTED uPVC SEWER GRADE PIPE IS TO BE USED. 1. CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES
- SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL. 12. GRATES AND COVERS SHALL CONFORM TO AS 3996.
- 13. ALL INTERNAL PIT DIMENSIONS TO CONFORM TO AS3500.3 TABLE 7.5.2.1 14. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS, ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE
- POSSIBILITY OF PERSONNEL FALLING DOWN PITS. 15. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER FOR FURTHER
- 16. THE CONTRACTOR IS TO ORGANISE AND STAGE CONSTRUCTION WORK AND UNDERTAKE ANY DIVERSION WORKS TO ENSURE THE EXISTING DRAINAGE
- IS ABLE TO CONVEY ALL STORMWATER FLOWS THAT MAY OCCUR DURING THE PERIOD OF THE CONSTRUCTION WORKS.
- 17. ANY DAMAGE TO THE WORKS DUE TO STORMWATER FLOWS OR FLOODING DURING THE CONSTRUCTION PERIOD IS AT THE CONTRACTOR'S RISK.
- 18. SETOUT POINTS FOR STORMWATER STRUCTURES ARE AS INDICATED IN THE DRAWINGS UNLESS OTHERWISE NOTED. 19. ALL PAVED SURFACE LEVELS AND GRADES TO BE COORDINATED WITH
- GULLY PIT LEVELS TO ENSURE NO UNDRAINED AREAS OCCUR. 20. THE SIDES OF ALL PIPE TRENCH EXCAVATIONS DEEPER THAN 1.0m SHALL BE FULLY SUPPORTED AT ALL TIMES AND HAVE APPROPRIATE EDGE
- PROTECTION. 21. ALL NEW PIPES TO BE LAID IN AN UPSTREAM DIRECTION. THE LINE, LEVEL AND LOCATION OF EXISTING SERVICES CROSSING THE LINE OF THE PROPOSED STORMWATER PIPE SHALL BE DETERMINED BY EXCAVATION PRIOR TO THE LAYING OF THE PIPE. IF CONFLICT IS APPARENT, THE ENGINEER SHALL BE NOTIFIED AND INSTRUCTIONS AS TO WHETHER THE EXISTING SERVICE IS TO BE ADJUSTED OR THE PROPOSED PIPE INVERT
- ALTERED WILL BE ISSUED. 22. PIPE BEDDING, HAUNCH AND BACKFILL TO BE AS SHOWN ON THE CIVIL
- DETAILS DRAWINGS AND THE CIVIL SPECIFICATION. 23. SUBSOIL DRAINAGE PIPES TO BE SLOTTED PIPE AND FILTER SOCK CLASS 1000 TO AS2439 PART 1 LAID AT PREFERABLE MINIMUM GRADE 1 IN 100 OR

ABSOLUTE MINIMUM 1 IN 200 WHERE LIMITED BY OUTFALL LEVELS.

- 24. STORMWATER STRUCTURES ARE TO BE CONSTRUCTED PERPENDICULAR TO THE INCOMING PIPEWORK UNLESS OTHERWISE NOTED. 25. PRECAST COMPONENTS SHALL BE CONNECTED BY MEANS OF EPOXY OR
- CHEMICAL GROUTED BARS OF THE SAME DIAMETER AND SPACING AS THE SMALLER BARS IN THE RESPECTIVE COMPONENTS. 26. PRE-CAST PITS MUST HAVE LIFTING ANCHORS. 27. WORKING LOADS ARE THOSE DUE TO FILL MATERIAL AND STANDARD
- HIGHWAY VEHICLES AS PER AS3725. CONSTRUCTION LOADS HAVE NOT BEEN ALLOWED FOR. 28. ALL EXPOSED EDGES ON STORMWATER PITS TO BE ROUNDED TO 5mm RAD.

Notes JMB 2024.05.02 JMB 2024.04.17 JMB 2024.04.04 ISSUE FOR SCHEMATIC DESIGN - REF (B ISSUE FOR SCHEMATIC DESIGN - REF 01 HAL A ISSUE FOR SCHEMATIC DESIGN - REF 01 By Appd YYYY.MM.DD Issued/Revision

Issue Status

PRELIMINARY

NOT FOR CONSTRUCTION

This document is suitable only for the purpose noted above. Use of this document for any other purpose is not permitted.

Colour Disclaimer This drawing has been documented in colour. This drawing is required to be printed in colour. Failure to do so may result inloss of information. Black and white printing may be used if specific black and white documents have been obtained from Stantec. Notes

Stantec Australia Pty. Ltd.

Level 6, Building B 207 Pacific Highway

St Leonards, NSW 2065

Tel: +61 2 8484 7000 Copyright Reserved The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the

drawing - any errors or omissions shall be reported to Stantec without dela



Client/Project Logo

Client/Project

UNO.

SINSW

HUNTER RIVER HIGH SCHOOL

HEATHERBRAE NSW 2324

File Name: HRHS-STNC-XX-XX-DR-C-007001.DWG CPO JMB JMB 2024.04.04 Dwn. Dsgn. Chkd. YYYY.MM.DD GENERAL NOTES


Project No.

301350957


Revision Drawing No.


HRHS-STNC-XX-XX-DR-C-007001

Scale





























JOINT SEALANT DETAIL 'A'

1:1

HOURS MAX. OF POURING SLAB)

'BOSTIC-FINDLAY SEAL-N-FLEX EC' OR-PARCHEM EMER-SEAL PU 40' HYDROCARBON RESISTANT SEALANT TO BE STRICTLY SUPPLIED AND INSTALLED IN ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS BY A SPECIALIST CONTRACTOR BOND BREAKING STRIP-EXPANDING FILLER-**BOARD**

/-JOINT A REINFORCING FABRIC— AS SPECIFIED _DOWEL JOINT, 400mm LONG N16 @ 500mm CENTRES

EXPANSION JOINT (EJ) DETAIL (SCALE 1:10)


—SEALANT RESERVOIR AND SEALANT TYPE. REFER REINFORCING FABRIC— DETAIL 'A' FOR JOINT AS SPECIFIED SEALANT.

SAWN CONTRACTION JOINT

SHOWN AS 'SCJ' ON PLAN

THAN 30


N.T.S 'd'= SUBBASE THICKNESS TO MATCH DEPTH OF PAVEMENT SUBBASE, BUT NOT LESS




TYPICAL JOINT PLAN FOR FOOTPATHS AND MEDIANS

JOINT SEALANT DETAIL 'B'

CONCRETE TO HAVE BROOM FINISH WITH SMOOTH TROWELLED EDGES. SCJ- FOOTPATH SAWCUT JOINT. REFER TO DETAIL EJ- FOOTPATH EXPANSION JOINT. REFER TO DETAIL






TYPICAL ISOLATION JOINT DETAIL

SHOWN AS 'IJ' ON PLAN

N.T.S

NOTE: TO ALSO BE CONSTRUCTED IN LOCATIONS WHERE CONCRETE PAVEMENTS ABUT FORMS OF BLOCKOUT AS SPECIFIED BY THIS ISOLATION JOINT DETAIL. 'd'= SUBBASE THICKNESS TO MATCH DEPTH OF PAVEMENT SUBBASE, BUT NOT LESS THAN 30




DOWELLED CONSTRUCTION JOINT (CONSTRUCTION AT POUR END)

SHOWN AS 'DCJ' ON PLAN

'd'= SUBBASE THICKNESS TO MATCH DEPTH OF PAVEMENT SUBBASE, BUT NOT LESS THAN 30





PRELIMINARY NOT FOR CONSTRUCTION

Colour Disclaimer

obtained from Stantec.

Notes

This document is suitable only for the purpose noted above. Use of this document for any other purpose is not permitted.

This drawing has been documented in colour. This drawing is required to be printed in colour. Failure to do so may result inloss of information. Black and white printing may be used if specific black and white documents have been

The Copyrights to all designs and drawings are the property of Stantec. Reproduction

or use for any purpose other than that authorised by Stantec is forbidden.
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.

Stantec Australia Pty. Ltd. Level 6, Building B 207 Pacific Highway St Leonards, NSW 2065 Tel: +61 2 8484 7000 Copyright Reserved



Client/Project Logo




HUNTER RIVER HIGH SCHOOL


HEATHERBRAE NSW 2324 File Name: HRHS-STNC-XX-XX-DR-C-406001.DWG CPO JMB JMB ######### Dwn. Dsgn. Chkd. YYYY.MM.DD


ROADS DETAILS -SHEET 2


Scale Project No. 301350957 1:10 Revision Drawing No.


B HRHS-STNC-XX-XX-DR-C-406002






























FLUSH OUT RISER IN PAVED AREAS (SCALE 1:10)




FLUSH OUT RISER IN LANDSCAPED AREAS (SCALE 1:10)














Issue Status

PRELIMINARY NOT FOR CONSTRUCTION

This document is suitable only for the purpose noted above. Use of this document for any other purpose is not permitted.

Colour Disclaimer This drawing has been documented in colour. This drawing is required to be printed in colour. Failure to do so may result inloss of information. Black and white printing may be used if specific black and white documents have been obtained from Stantec.

Notes

Stantec Australia Pty. Ltd. Level 6, Building B 207 Pacific Highway St Leonards, NSW 2065 Tel: +61 2 8484 7000

The Copyrights to all designs and drawings are the property of Stantec. Reproduction

or use for any purpose other than that authorised by Stantec is forbidden.
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.

Client/Project Logo Copyright Reserved

GOVERNMENT The APP Group

Client/Project SINSW

HUNTER RIVER HIGH SCHOOL


HEATHERBRAE NSW 2324 File Name: HRHS-STNC-XX-XX-DR-C-526001.DWG CPO JMB JMB ######### Dwn. Dsgn. Chkd. YYYY.MM.DD


STORMWATER DRAINAGE DETAILS -SHEET 2

Project No.


301350957 as shown Revision B Drawing No. HRHS-STNC-XX-XX-DR-C-526002

Scale





PIT SCHEDULE FOR: C-STRM SETOUT COORDS | INTERNAL DIM [mm] | INLET Ø [mm] | INLET INV [m] | OUTLET Ø [mm] | OUTLET INV [m] | PIT FIN RL | PIT DEPTH [m] PIT TYPE COMMENTS PIT NAME E: 381533.043 W: 650 0.876 Reinforced Concrete Ø 229 6.000 6.851 N: 6372137.515 L: 900 E: 381511.292 W: 900 5.789 7.256 1.492 5.819 Ø 229 02/02 Reinforced Concrete Ø 229 N: 6372131.161 L: 900 E: 381502.241 W: 900 5.681 1.647 02/03 Ø 229 Ø 375 5.651 7.258 Reinforced Concrete N: 6372141.082 L: 900 E: 381461.765 W: 900 5.231 5.201 7.273 02/04 Ø 375 Ø 375 2.112 Reinforced Concrete N: 6372107.632 L: 900 E: 381445.246 W: 900 5.000 4.970 7.300 2.355 02/05 Reinforced Concrete Ø 375 Ø 450 N: 6372126.512 L: 900 4.876 E: 381440.687 W: 900 02/06 Reinforced Concrete Ø 229 5.367 Ø 450 4.846 7.200 2.379 N: 6372133.115 L: 900 Ø 300 5.919 E: 381440.607 W: 900 7.121 02/07 4.743 Ø 450 4.713 2.456 Reinforced Concrete N: 6372150.127 L: 900 W: 900 E: 381513.868 Ø 229 1.056 04/01 6.236 7.292 Reinforced Concrete N: 6372181.816 L: 900 E: 381498.817 W: 900 7.297 1.254 6.073 Ø 229 6.043 04/02 Ø 229 Reinforced Concrete N: 6372168.114 L: 900 E: 381479.940 W: 900 5.858 Ø 229 5.828 7.274 1.446 04/03 Reinforced Concrete N: 6372169.284 L: 900 E: 381607.855 W: 600 5.811 6.665 0.854 Reinforced Concrete Ø 229 L: 900 N: 6372148.046 E: 381593.181 W: 600 5.642 05/02 Reinforced Concrete Ø 229 Ø 229 5.612 6.794 1.183 N: 6372156.496 L: 900 E: 381584.590 W: 900 Ø 229 5.306 6.160 0.854 06/01 Reinforced Concrete N: 6372108.674 L: 900 E: 381591.313 W: 900 6.244 06/02 Reinforced Concrete Ø 229 5.215 Ø 229 5.185 1.059 N: 6372114.749 L: 900 E: 381600.281 W: 900 5.033 1.146 06/03 Ø 229 5.063 Ø 229 6.179 Reinforced Concrete N: 6372122.963 L: 900 E: 381394.167 W: 600 Ø 300 6.462 7.293 0.831 07/01 Reinforced Concrete N: 6372123.571 L: 600 E: 381420.780 W: 600 6.192 Ø 300 7.200 1.038 07/02 Ø 300 6.162 Reinforced Concrete N: 6372127.910 L: 600 E: 381431.699 W: 600 07/03 Ø 300 6.053 Ø 300 6.023 7.200 1.177 Reinforced Concrete L: 600 N: 6372127.833



Issue Status

PRELIMINARY NOT FOR CONSTRUCTION

This document is suitable only for the purpose noted above. Use of this document for any other purpose is not permitted.

Colour Disclaimer This drawing has been documented in Stantec colour. This drawing is required to be printed in colour. Failure to do so may result inloss of information. Black and white printing may be used if specific black and white documents have been obtained from Stantec.

Stantec Australia Pty. Ltd. Level 6, Building B 207 Pacific Highway St Leonards, NSW 2065 Tel: +61 2 8484 7000



Client/Project SINSW

HUNTER RIVER HIGH SCHOOL

HEATHERBRAE NSW 2324

File Name: HRHS-STNC-XX-XX-DR-C-527001.DWG CPO JMB JMB 2024.04.04 Dwn. Dsgn. Chkd. YYYY.MM.DD STORMWATER DRAINAGE PIT SCHEDULE

Project No.

Scale as shown

301350957

Revision C Drawing No. HRHS-STNC-XX-XX-DR-C-527001

Copyright Reserved The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.

The APP Group