KENT ROAD PUBLIC SCHOOL DEVELOPMENT **CIVIL WORKS**





DRAWING SCHEDULE					
DRAWING NUMBER	DRAWING NAME				
C01	COVER SHEET, LOCALITY PLAN AND DRAWING SCHEDULE				
C02	GENERAL NOTES AND LEGENDS				
C03	OVERALL GENERAL ARRANGEMENT PLAN				
C04	SEDIMENT AND EROSION CONTROL PLAN & DETAILS				
C10	SITEWORKS PLAN				
C11	PAVEMENT PLAN				
C12	SIGNAGE AND LINEMARKING PLAN				
C13	TYPICAL SECTION				
C15	LONGITUDINAL SECTION				
C16	CROSS SECTIONS, SHEET 1				
C17	CROSS SECTIONS, SHEET 2				
C20	TYPICAL DETAILS, SHEET 1				
C21	TYPICAL DETAILS, SHEET 2				
C22	TYPICAL DETAILS, SHEET 3				







SCALE : A1	DRAWN BY	AUTHORISED BY
1:1000	LA	NB
PROJECT No	DRAWING No	REVISION
201492	C01	P2
Plot File Created:	Jun 22, 2021 - 10:10am	A .

GENERAL NOTES

- Contractor must verify all dimensions and existing levels on site prior to commencement of works. Any discrepancies to be reported to the
- Engineer.

 2. Strip all topsoil from the construction area. All stripped topsoil shall
- be disposed of off-site unless directed otherwise.

 3. Make smooth connection with all existing works.
- Compact subgrade under buildings and povements to minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1. Compaction under buildings to extend 2m minimum beyond building
- 5. All work on public property, property which is to become public property, or any work which is to come under the control of the Stalutury Authority, the Contractor is to ensure that the drawings used for construction have been approved by all relevant authorities
- used for construction have been approved by all relevant authorities prior to commencement site.

 6. All work on public property, property which is to become public property, or any work which is to come under the control of the Statutory Authority is to be carried out in accordance with the requirements of the relevant Authority. The Contractor shall obtain these requirements for the Authority, where the requirements of the Authority and the specifications, the requirements of the Authority shall be applicable.

 7. For all temporary batters refer to geolechnical recommendations.

REFERENCE DRAWINGS

These drawings have been based from, and to be read in conjunction with the following Consultants drawings. Any conflict to the drawings must be notified immediately to the Engineer.

 Dwg Title
 Dwg No
 Rev
 Date

 PLAN OF DETAIL &
 5650-DET2_A
 A
 12.04.21

 LEVELS OVER PART OF

HERRING ROAD AND KENT ROAD MARSFIELD

UTILITY MAPPING UNDERGROUND NSW21-0138-US-01 R1 16.04.21 LITHITY SURVEY

SURVEY AND SERVICES INFORMATION SURVEY

Origin of levels : RL 71.096
Datum of levels : A.H.D. AUSTRALIAN HEIGHT DATUM
Coordinate system : MGA

Coordinate System: MGA
Survey prepared by: MEPSTEAD & ASSOCIATES
Setout Points: PM 50022
Taylor Thomson Whitting does not guarantee that the survey information shown on these drawings is accurate and will accept no liability for any inaccuracies in the survey information provided to us from any cause whatsoever.

UNDERGROUND SERVICES - WARNING

The locations of underground services shown on Taylor Thomson Whittings The locations of underground services shown on Toylor Thomson Whittings drawings have been plotted from diagrams provided by service authorities. This information has been prepared solely for the authorities own use and may not necessarily be updated or accurate. The position of services as recorded by the authority at the time of installation may not reflect changes in the physical environment subsequent to installation. Toylor Thomson Whitting does not guarantee that the services information shown on these drawings shows more than the presence or obsence of services, and will accept no liability for inaccuracies in the services information shown from any cause whistoseer.

The Contractor must confirm the exact location and extent of services prior to construction and notify any conflict with the drawings immediately to the Engineer/Superintendent.

to the Engineer/Superintendent.

The contractor is to get approval from the relevant state survey department, to remove/adjust any survey mark. This includes but is not limited to; State Survey Marks (SSM), Permanent Marks (PM), codostral reference marks or any other survey mark which is to be removed or

odjusted in any way.

Taylor Thomson Whitting plans do not indicate the presence of any survey mark. The contractor is to undertake their own search.

BOUNDARY AND EASEMENT NOTE

The property boundary and easement locations shown on Taylor Thomson Whitting drawing's have been based from information received from: MEPSTEAD & ASSOCIATES DATED 12.04.2021 9/4 CENTRAL AVE, THORNLEIGH NSW 2120 PH: 02 9875 4500

Taylor Thomson Whitting makes no guarantees that the boundary or easement information shown is correct. Taylor Thomson Whitting will accept assential minimional situation is curect. Topic minimism among all order is advised to check/confirm all boundaries in relation to all proposed work prior to the commencement of construction. Boundary inaccuracies found are to be reported to the superintendent prior to construction starting.

SE 1A 30 04 21

CHK DR DATE REV DESCRIPTION

SAFETY IN DESIGN

Contractor to refer to Appendix B of the Civil Specification for the Civil Risk and Solutions Register.

EXISTING SERVICES

Contractor to be aware existing services are located within the site. Location of all services to be verified by the Contractor prior to commencing works. Contractor to confirm with relevant authority regarding measures to be taken to ensure services are protected or procedures or in place to demolish and/or relocate.

EXISTING STRUCTURES

Contractor to be aware existing structures may exist within the site. To prevent damage to existing structure(s) and/or personnel, site works to be carried out as far as practicably possible from existing structure(s).

EXISTING TREES

Contractor to be aware existing trees exist within the site which need to Conductor to be owner existing neces existing receives which need to be protected. To prevent domage to trees and/or personnel, site works to be carried out as far as practicably possible from existing trees. Advice needs to be soupplif from Arborist and/or Landscape Architect an measures required to protect trees.

GROUNDWATER

Contractor to be aware ground water levels are close to existing surface level. Temporary de-watering may be required during construction works. **EXCAVATIONS**

Deep excavations due to stormwater drainage works is required. Contractor to ensure safe working procedures are in place for works. All excavations to be fenced off and batters adequately supported to approval of Geolechnical Engineer.

GROUND CONDITIONS

Contractor to be aware of the site geotechnical conditions, refer to geotechnical report by (insert report details) for details.

HAZARDOUS MATERIALS

Existing asbestos products & contaminated material may be present on Existing diseases processed and the processed an details) for details.

CONFINED SPACES

Contractor to be aware of potential hazards due to working in confined spaces such as stormwater pits, trenches and/or tanks. Contractor to provide safe working methods and use appropriate PPE when entering confined spaces.

Contractor to be aware manual handling may be required during construction. Contractor to take appropriate measures to ensure manual handling procedures and assessments are in place prior to commencing

WATER POLLUTION

Contractor to ensure appropriate measures are taken to prevent pollutants from construction works contaminating the surrounding environment.

SITE ACCESS/EGRESS

Contractor to be aware site works occur in close proximity to footpaths and roadways. Contractor to erect appropriate barriers and signage to protect site personnel and public.

VEHICLE MOVEMENT

Contractor to supply and comply with traffic management plan and provide adequate site traffic control including a certified traffic marshall to supervise vehicle movements where necessary.

- 1. All basecourse moterial to comply with RMS specification No 3051 and compacted to minimum 98% modified standard dry density in accordance with AS 1289 5.2.1.
 2. All trenth bockfill material shall be compacted to the same density as the adjacent material.
 3. All service trenches under vehicular powements shall be backfilled with an approved select material and compacted to a minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1.

TENDER NOTES

- I These drawings are preliminary drawings issued for tender as an indication of the extent of works only. They are not a complete construction set of drawings.

 To determine the full extent of work, these drawings shall be read in conjunction with the architectural drawings and other contract documents. Allow for all items shown on architectural and other drawings as not all items are shown on the structural/civil works drawings. Should any ambiguity, error, omissions, discrepancy, inconsistency or other fault exist or seem to exist in the documents,
- immediately or other than text of seem to seem to seek in the occurrents, immediately notify in writing to the Superinlendent.

 3. Rates shown on the drawings are for the final structure/civil works in place and do not allow for any wastage, rolling margins, over supply

STORMWATER DRAINAGE NOTES

- Pipes 300 dia and larger to be reinforced concrete Class "3" opproved spigot and socket with rubber ring joints U.N.O.
 Pipes up to 300 dia may be sever grade uPVC with solvent welded joints, subject to approval by the engineer.
 Equivalent strength VCP or FRP pipes may be used subject
- to approval.

 5. Precast pits may be used external to the building subject

- 5. Precost pits may be used external to the building subject to approval by
 6. Enlarges, connections and junctions to be manufactured filtings where pipes are less than 300 dia.
 7. Where subsoil drains pass under floor slobs and vehicular prevenents, unslotted uPVC sever grade pipe is to be used.
 8. Crates and covers shall conform with AS 3996-2006, and AS 14281 for access requirements.
 9. Pipes are to be installed in a coordance with AS 3725. All bedding to be type HZ U.N.O.
 10. Care is to be taken with invert levels of stormwater lines. Grades shown are not to be reduced without approval.
 11. All stormwater pipes to be 150 dia of 10.7 min fall U.N.O.
 12. Subsoil drains to be slotted flexible uPVC U.N.O.
 13. Adopt invert levels for pipe installation (grades shown are only nominal).

CHK DR DATE REV DESCRIPTION

CONCRETE FINISHING NOTES

- All exposed concrete pavements are to be broomed finished.
 All edges of the concrete pavement including keyed and dowelled joints are to be finished with an edging tool.

 3. Concrete povements with grades greater than 10 % shall be heavily
- 4. Carborundum to be added to all stair treads and ramped crossings

CONCRETE NOTES

EXPOSURE CLASSIFICATION : External : 82

CONCRETE Place concrete of the following characteristic compressive strength I'c

Location	AS 1379 fc NPo at 28 days	Specified Slump	Nom Agg
Kerbs	S20	80	2
Retaining wall footing	S40	80	2

- Use Type 'GP' cement, unless otherwise specified.
 All concrete shall be subject to project assessment and testing to AS
- And concrete Strain or surject to project security in a 1379.

 Consolidate by mechanical vibration. Cure all concrete surfaces as directed in the Specification.

 For all falls in slob, drip growers, reglets, chamfers etc. refer to Architects drawings and specifications.

 Unless shown on the drawings, the location of all construction joints shall be submitted to Engineer for review.

 No holes or chases shall be made in the slob without the approval of the Fannise.

- the Engineer.
 7. Conduits and pipes are to be fixed to the underside of the top
- Slurry used to lubricate concrete pump lines is not to be used in any Storry used to indirecte concrete pump lines is not to be used structural members.

 All slabs cost on ground require sand blinding with a Concrete Underlay.

FORMWORK

The design, certification, construction and performance of the formwork, falsework and bockpropping shall be the responsibility of the contractor. Proposed method of installation and removal of farmwork is to be submitted to the superintendent for comment prior to work being corried out.

JOINTING NOTES

Vehicular Pavement Jointing

- Venicular Pavement Johnny

 1. All vehicular powements to be jointed as shown on drawings.

 2. Keyed construction joints should generally be located at a maximum of 6m centres.

 3. Sown joints should generally be located at a maximum of 6m centres or 1.5 x the spocing of keyed joints, where key joint spocing is less than 4m, with dwelled exposino joints at maximum of 30m centred.

 4. Provide 10mm wide full depth expansion joints between buildings and all concrete or unit nowers.
- all concrete or unit povers.

 5. The timing of the saw cut is to be confirmed by the contractor on
- site. Site conditions will determine how mony hours after the concrete pour before the saw culs are commenced. Refer to the specification for weather conditions and temperatures required. Vehicular povement jointing as follows:

DEJA	2	FACE S		į	SI SI	DEJ	S
DEJA	6m MAX			6m MAX			
DEJA	-		30m MA)			_	
i ! EJ	FA	CE d	F BI	i Luo	i I N G		j

Pedestrian Footpath Jointing

CHK DR DATE

- 1. Expansion joints are to be located where possible at tangent points of urves and elsewhere at max 6.0m centres 2. Weakened plane joints are to be located at a max 1.5 x width of the
- 3. Where possible joints should be located to match kerbing and/or
- adjacent pavement joints.
 4. All pedestrian footpath jointings as follows U.N.O.

 	FACE	0 F	KER	В		-
Me	ವ		₩b]	G₩	3	*
 -	T i			1.5 x W	(1.5m M/	(X)
			6.0m	MAX		

KERBING NOTES

Includes all kerbs, autters, dish drains, crossinas and edges,

- 1. All kerbs, gutters, dish drains and crossings to be constructed on
- All kebs, gutters, dish drains and crossings to be constructed on 75mm (MM) grounder basecures compocted to minimum 98% modified maximum dry density in accordance with AS 1289 5.2.1. Expansion joints (EJ) to be formed from 10mm compressible cork filler board for the full depth of the section and cut to profile. Expansion joints to be located at drainage pils, on tangent points of curves and desember at 12m centres except for integral kersh where the expansion joints are to match the joint locations in slobs.
- exponsion pants are to match the joint locations in slobs. Weakened plane joints to be min 3mm wide and located at 3m centres except for integral kerbs where weakened plane joints are to match the joint locations in slobs.

 Broomed finished to all ramped and vehicular crossings, all other kerbing or dish drains to be steel float finished.
- kerbing or dish drains to be steel tool triished.

 In the replacement of kerks —
 Existing road powement is to be sowcut 900mm from lip of gutter.
 Upon completion of new kerbs, new hosecourse and surface is to
 be toid 900mm wide to match existing materials and thicknesses.
 Existing allotment drainage pipes are to be built into the new kerb
 with a 6100mm hale. Existing kerbs are to be completely removed
 where new kerbs are shown.

REINFORCEMENT NOTES

- Fix reinforcement as shown on drawings. The type and grade is indicated by a symbol as shown below. On the drawings this is followed by a numeral which indicates the size in millimetres of the
- N. Hot rolled ribbed bar R. Plain round bar SL Square mesh RL Rectangular mesh grade 500L grade 500L
- Provide bor supports or spacers to give the following concrete cover to all reinforcement unless otherwise noted on drawings.
- Footings $\,-\,$ 50 top, 50 bottom, 50 sides.
 - 30 generally.
 30 when cost in forms but later exposed to
- weather or ground.

 ... when cast directly in contact with ground.

- 3. Cover to reinforcement ends to be 50mm U.N.O.
 4. Provide NIZ-450 support bars to top Forinforcement as required, Lop 500 U.N.O.
 5. Maintain cover to all pipes, conduits, regiets, orly grooves etc.
 6. All cogs to be standard cogs unless noted otherwise.
 7. Fabric end and side laps are to be placed strictly in accordance with the manufacturers requirements to achieve a full fensile log. Fabric shall be loid so that there is a maximum of 3 layers at any location.

FABRIC LAPS

___| __25

Laps in reinforcement shall be made only where shown on the drawings unless otherwise approved. Lap lengths as per table below.

ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH CITY OF RYDE CONSTRUCTION SPECIFICATIONS.

S The same of managementation and the contract of the contract

CITY OF RYDE APPROVED FOR CONSTRUCTION 9/07/2021

> Subject to the Conditions of Development Consent

> > RTC Approval 25/02/2021

ISSUE FOR REVIEW

REV DESCRIPTION


CLIENT Education NSW School Infrastructure 13/8 WINDMILL STREET MILLERS POINT NSW 2000





DRAWING NAME: GENERAL NOTES AND LEGENDS

SCALE: A1 DRAWN BY AUTHORISED BY N/A LA NB DRAWING N REVISION 201492 C02 P2 Plot File Created: Jun 21, 2021 - 2:52pm



1:100

Œ							
A1 .	0 1 2 3	5 6 7 8	9 10				_
							CI
_							1
							1
P2	ISSUE FOR APPROVAL	SF LA 22.06.21					4
P1	ISSUE FOR REVIEW	SF LA 30.04.21					4
REV	DESCRIPTION	CHK DR DATE	REV DESCRIPTION	CHK DR DATE	REV DESCRIPTION	CHK DR DATE	_









G NAME:	SCALE : A1	DRAWN BY	AUTHORISED
ALL GENERAL	AS SHOWN	LA	NB
NGEMENT PLAN	PROJECT No	DRAWING No	REVISION
	201492	C03	P2
	Plot File Created: 1	un 21 2021 - 2:54nm	


ALL PROPOSED SEDIMENT AND EROSION CONTROL WORKS AND DETAILS TO THE CITY OF RYDE STANDARD DETAILS ON DRAWING ESC.1 AND ESC.5 FOR DETAILS.






many with a second to the colour same







THIS DRAWING IS COPYRIGHT AND IS THE PROPERTY OF TAYLOR THOMSON WHITTING (NSW) PTY LTD AND MUST NOT BE USED WITHOUT AUTHORISATION. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT NOTES ON DRAWING C01

GENERAL LEGEND

- - EXISTING PROPERTY BOUNDARY

SEDIMENT AND **EROSION LEGEND**

___ x ____ SILTATION FENCE 00

SANDBAG SEDINENT TRAP

EROSION AND SEDIMENT CONTROL NOTES

- 1. All work shall be generally carried out in accordance with
- (A) Local authority requirements,
 (B) EPA Pollution control manual for urban stormwater,
- (B) EPA Pollution control manual for urban stormwater.
 (C) LANDCOM NSW Managing Urban Stormwater: Soils and
 Construction ("Blue Book").

 2. Erosion and sediment control drawings and notes are provided for
 the whole of the works. Should the Controctor stage these works
 then the design may be required to be modified. Variation to these
 details may require approval by the relevant authorities.
 The erosion and sediment control plan shall be implemented and
 adapted to meet the varying situations as work on site progresses.
 3. Maintain all erosion and sediment control derices to the satisfaction
 of the superintendent and the local authority.
 4. When stormwater pils are constructed prevent site runoff entering
 the pils unless sit fences are erected around pils.
- the pits unless silt fences are erected around pits.
- . Minimise the area of site being disturbed at any one time. 6. Protect all stockpiles of materials from scour and erosion. Do not stockpile loose material in roadways, near drainage pits or in
- All soil and water control measures are to be put back in place at the end of each working day, and modified to best suit site conditions.
- conditions.

 Control water from upstream of the site such that it does not enter the disturbed site.

 9. All construction vehicles shall enter and exit the site via the temporary construction entry/exit.

 10. All vehicles leaving the site shall be cleaned and inspected before

- leaving.

 11. Maintain all stormwater pipes and pits clear of debris and sediment. Inspect stormwater system and clean out after each
- storm event.

 12. Clean out all erosion and sediment control devices after each storm event.


Sequence Of Works

- Prior to commencement of excavation the following soil management devices must be installed.
 Construct sit fences below the site and across all potential runofit sites.
- Construct temporary construction entry/exit and divert runoff to suitable control systems.
 Construct measures to divert upstream flows into existing stammater system.
- 1.4. Construct sedimentation traps/basin including outlet control and
- overflow.
 1.5. Construct turf lined swales.
- 1.3. Construct turf lined swales.
 16. Provide scanding sediment trops upstream of existing pits.
 2. Construct geotexitie filter pit surround around all proposed pits as they are constructed.
 3. On completion of powement provide sand bag kerb inlet sediment trops around pits.
 4. Provide and maintain a strip of turf on both sides of all roads after the construction of kerbs.

WATER QUALITY TESTING REQUIREMENTS

Prior to discharge of site stormwater, groundwater and seepage water into council's stormwater system, confroctors must undertake water quality tests in conjunction with a suitably qualified environment consultant authining the following:

- Compliance with the criteria of the Australian and New Zealand
- Compliance with the criteria of the Australian and New Zealand Guidelines for Fresh and Marine Water Quality (2000) If required subject to the environmental consultants advice, provide remedial measures to improve the quality of water that is to be discharged into Councils starm water drainage system. This should include comments from a suitably qualified environmental consultant confirming the suitability of these remedial measures to manage the water discharged from the site into Councils storm water drainage system. Duttining the proposed, anaging monitarian, contingency plans and validation program that will be in place to continually monitor the quality of water discharged from this site. This should outline the frequency of water quality testing that will be undertoken by a suitably qualified environmental consultant.



SCALE : A1 AUTHORISED BY DRAWN BY AS SHOWN LA NB PROJECT No DRAWING No REVISION C04 P2 201492 Plot File Created: Jun 21, 2021 - 2:55pm










PLAN & DETAILS


SEDIMENT AND EROSION CONTROL

P2 ISSUE FOR APPROVAL P1 ISSUE FOR REVIEW SF LA 30.04.21 CHK DR DATE CHK DR DATE REV DESCRIPTION









SIGNAGE LEGEND

Existing sign pole

Proposed sign pole

LINEMARKING LEGEND

Et] Edge line type E1

NOTE
Line marking to be in accordance with AS1742.2 and the
City of Canada Bay's Traffic Committee approvals.
All redundant line marking is to be removed.

0 2.5 5 7.5 10 12.5 15 17.5 20m

1:250 A1 1:500 A3

SCALE : A1 DRAWN BY AUTHORISED BY

1:250 LA NB

PROJECT No DRAWING No REVISION

201492 C12 P2


Plot File Created: Jun 21, 2021 - 2:57pm







DRAWING NAME:




0 0.25 0.5 0.75 1 1.25 1.5 1.75 2m


1:25 A1 1:50 A3 AUTHORISED BY SCALE : A1 DRAWING NAME: NB LA 1:25 TYPICAL SECTION KENT ROAD PUBLIC SCHOOL Structural Civil Traffic Façade REVISION P2 DRAWING No PROJECT No DEVELOPMENT C13 201492 School Infrastructure Plot File Created: Jun 21, 2021 - 2:58pm HERRING ROAD, MARSFIELD, NSW 2122 612 9439 7288 | 48 Chandos Street St Leonards NSW 2065 SF LA 22.06.21 SF LA 30.04.21 L3/8 WINDMILL STREET, MILLERS POINT, NSW 2000 P2 ISSUE FOR APPROVAL P1 ISSUE FOR REVIEW CHK DR DATE

CHK DR DATE REV DESCRIPTION

CHK DR DATE REV DESCRIPTION

REV DESCRIPTION





CITY OF RYDE

APPROVED FOR CONSTRUCTION

Signed.

Date. 9/07/2 22 1

Subject to the Conditions of Development Consent

RTC Approval 25/07/2021

0	1	2	3	4	5	6	7
L	- Jan	_	-		and a	-	-
_		1	:100 A1	1:2	00 A3		
0	0.25	0.5	0.75	1	1.25	1.5	1.75
		14	707	000	1	1	ï

A1,0 1 2 3	5 6 7 8	9 10				
P2 ISSUE FOR APPROVAL	SF LA 02.07.21					
P1 ISSUE FOR REVIEW	SF LA 30.04.21					CHK DR DATE
REV DESCRIPTION	CHK DR DATE	REV DESCRIPTION	CHK DR	DATE	REV DESCRIPTION	CHK DK DATE







PROJECT:	DRAWN
KENT ROAD PUBLIC SCHOOL DEVELOPMENT	LONG
HERRING ROAD, MARSFIELD, NSW 2122	

DRAWING NAME:	SCALE : A1
LONGITUDINAL SECTION	AS SHOWN
	PROJECT No
	201492


SCALE : A1	DRAWN BY	AUTHORISED B
AS SHOWN	LA	NB
PROJECT No	DRAWING No	REVISION
201492	C15	P2
Plot File Created:	Jul 02, 2021 - 2:37pm	







CITY OF RYDE


25/07/2021





CHK DR DATE REV DESCRIPTION





PI ISSUE FOR REVIEW

REV DESCRIPTION

SF LA 30.04.21

CHK DR DATE REV DESCRIPTION










Structural Civil

NG NAME:	SCALE : A1	DRAWN BY	AUTHORISED BY	
CAL DETAILS, SHEET 2	NTS	LA	NB	
	PROJECT No	DRAWING No	REVISION	
	201492	C21	P2	
	Plot File Created:	Created: Jun 21 2021 - 3:02nm		













ING NAME:	SCALE : A1	DRAWN BY	AUTHORISED
CAL DETAILS, SHEET 3	NTS	LA	NB
	PROJECT No	DRAWING No	REVISION
	201492	C22	P2
	Plot File Created: Jun 21 2021 - 3:02nm		